

## Marking the Stall

All spaces must be designated by an approved accessible parking sign. Signs cannot be less than 12" x 18" in size. There should be a minimum of 60" between the bottom of the sign and the ground. Local sign companies have the required sign in stock.

Painting the accessible symbol on the pavement is not an acceptable replacement for approved parking signs.

Paint cross-hatching on the access aisles so people don't park in these areas.

## Accessible Route

The route that a person with a disability takes to get from the parking stall to the building is called the *accessible route*.

The accessible route must be at least 3-foot wide. This width requirement applies to curb ramps, sidewalks and built-up curb ramps.

Accessible ramps must be located adjacent to the access aisle, *not* in the parking stall.

## Changing Your Parking Lot

Restriping an existing parking lot, as is, does not require a permit.

Changing parking stalls or drive aisle width or location in your parking lot may require a permit.

Call Zoning staff at 266-5978 if you have questions about your proposed parking lot changes.

If a permit is required, you will need the application packet called *Getting Your Parking Lot Approved*. The packet contains a checklist and instructions on how and what to submit when applying for a permit. Zoning can send you a packet or you can get one at the Zoning Counter.

Allow a minimum of 7 working days for review of your plans before a permit can be issued.

Submit your plans and application at the Zoning Counter.

Zoning Counter  
Madison Municipal Building  
Department of Planning & Development  
215 Martin Luther King Jr. Blvd, Ste. LL100  
Madison, Wisconsin 53703

# Accessible Parking Stalls



VAN ACCESSIBLE

Meeting requirements of the *Americans with Disabilities Act* in the City of Madison

8/23/05

The City of Madison accepts the size and design standards of ANSI A117.1 for barrier-free parking stalls.

Here are guidelines to use in providing usable accessible parking.

## Number of Stalls

Total Parking Stalls in Lot	Minimum Stalls Required	
	Accessible	Van Accessible
1-25	1	1
26-50	2	1
51-75	3	1
76-100	4	1
101-150	5	1
151-200	6	1
201-300	7	1
301-400	8	1
401-500	9	1
501-1000	2% of total	2-5
	20 plus 1 for each 100 over	
1001 and over	1000	5+

## Slope

Parking stalls and access aisles must be level. This means a slope no greater than 1:48 in all directions.

Access ramps and routes should not exceed a 1:12 (8.34%) slope.



## Stall Width

There are two types of stalls, van accessible and accessible. Each stall must be 8 feet wide. An 8-foot wide access aisle must be next to one stall in every eight. This stall must be marked *Van Accessible* as shown on the front cover.

Two adjacent 8-foot wide stalls may share the same 8-foot wide access aisle.

If the lot has 3 to 8 accessible stalls, the first 2 stalls can share an 8-foot wide access aisle. The access aisle for stalls 3 through 8 can be 5-foot wide.

If the lot has more than 8 accessible stalls, there must be an 8-foot wide access aisle for every eighth stall.

Van accessible stalls need a vertical clearance height of at least 8 feet 2 inches.

See the illustrations for examples of the parking stall layouts described.




## Need Help?


Give us a call at 266-4551 and ask for help with accessible parking lots.

# Accessible Parking Stall Configurations

### Stall design with built-up curb ramp



### Stalls with curb ramp outside of accessible parking



### Multi-stall design

