



Department of Public Works
City Engineering Division

608 266 4751

Robert F. Phillips, P.E.
City Engineer

City-County Building, Room 115
210 Martin Luther King, Jr. Boulevard
Madison, Wisconsin 53703
FAX 608 264 9275
www.cityofmadison.com

Assistant City Engineer
Michael R. Dailey, P.E.

Principal Engineers
Christina M. Bachmann, P.E.
John S. Fahrney, P.E.
Gregory T. Fries, P.E.
Christopher J. Petykowski, P.E.

Facilities & Sustainability
Jeanne E. Hoffman, Manager
James C. Whitney, A.I.A.

Operations Supervisor
Kathleen M. Cryan

GIS Manager
David A. Davis, R.L.S.

Financial Officer
Steven B. Danner-Rivers

Hydrogeologist
Brynn Bemis

NOTICE OF ADDENDUM

ADDENDUM NO. 1

CONTRACT NO. 6899

City View Drive Water Main – 2012

Revise and amend the contract document(s) for the above project as stated in this addendum, otherwise, the original document(s) shall remain in effect.

- **Sheets D-4 and D-5: Add the following paragraph to SECTION 108.2 (Permits) -**
“Madison Water Utility has received a permit to construct, operate and maintain utility facilities on Wisconsin Department of Transportation railroad property. This permit will apply to the steel casing installation, as described in Bid Item # 70014 of these provisions. A copy of this permit is available at the Madison Water Utility, Engineering Section office.”
- **Sheet D-6: Replace the first paragraph of BID ITEM # 20201 / 20202 / 20221 (Excavation Cut / Fill Borrow / Topsoil) with the following paragraph:**
“Excavation quantities to finished grade are included in Bid Item Excavation Cut. Any other work involving the final grading, placement of fill and stripping/replacement/importing of topsoil shall be incidental to their respective Bid Items. Please note that it is expected that the majority of material obtained on-site through Excavation Cut shall be placed as Fill in other areas of the project as specified in Article 201 - Excavation Cut and Article 202 - Fill of the Standard Specifications. All materials obtained through Excavation Cut and placed as Fill or Select Fill shall comply with the specifications in paragraph 202.3(c) - Special Compaction, in the Standard Specifications and shall be approved by the Engineer prior to placement. It has been assumed for the earthwork calculation that all Excavation Cut material will be acceptable for use as Fill. Topsoil shall be stripped, stockpiled, and redistributed evenly across the site to achieve the final finished grades. As part of this work, additional topsoil may need to be imported and distributed as required and per Standard Specifications (see attached soil boring report).”
- **Remove and replace proposal sheets E-5 and E-6 (attached), and the bidding proposal spreadsheet (.xls) file.**

Please acknowledge receipt of this addendum on page E1 of the contract documents. Electronic version of these documents can be found on the City of Madison web site at:

<http://www.cityofmadison.com/business/PW/contracts/openforBid.cfm>

If you are unable to download plan revisions associated with the addendum, please contact the Engineering office at 608-266-4751 receive the material by another route.

Alan Larson, P.E., B.C.E.E., Principal Engineer