



Department of Public Works
City Engineering Division

Robert F. Phillips, P.E.
City Engineer

City-County Building, Room 115
210 Martin Luther King, Jr. Boulevard
Madison, Wisconsin 53703
FAX 608 264 9275
www.cityofmadison.com

608 266 4751

Assistant City Engineer
Michael R. Dailey, P.E.

Principal Engineers
Christina M. Bachmann, P.E.
John S. Fahrney, P.E.
Gregory T. Fries, P.E.
Christopher J. Petykowski, P.E.

Facilities & Sustainability
Jeanne E. Hoffman, Manager
James C. Whitney, A.I.A.

Operations Supervisor
Kathleen M. Cryan

GIS Manager
David A. Davls, R.L.S.

Financial Officer
Steven B. Danner-Rivers

Hydrogeologist
Brynn Bemis

NOTICE OF ADDENDUM
ADDENDUM NO. 2
WELL 15 VOC STRIPPER
CONTRACT NO. 6941

Revise and amend the contract document(s) for the above project as stated in this addendum, otherwise, the original document shall remain in effect.

A. SPECIFICATIONS

1. DIVISION 1–GENERAL REQUIREMENTS

- a. Page 01010-3, SECTION 01010–SUMMARY OF WORK, PART 1–GENERAL, 1.04 CONSTRUCTION REQUIREMENTS, Paragraph B

ADD the following to the end of paragraph 6:

“The existing 4-inch temporary electric service conduit may interfere with installation of 12-inch water lines between the well head and the air stripping units. CONTRACTOR may be required to delay installation of 12-inch water lines at this location until after removal of the electric service and conduit. Interior and exterior wall areas at conduit supports and penetrations shall be finished to match final construction.”

2. DIVISION 9–FINISHES

- a. Page 09250-2, SECTION 09250–GYPSUM BOARD, PART 2-PRODUCTS, 2.02 MATERIALS, Paragraph A

DELETE “conforming to ASTM C630” from paragraph 2.

REPLACE “USG Sheetrock W/R Gypsum Panels” with “Fiberock Aqua-Tough Interior Panel” in paragraph 2.

B. DRAWINGS

1. SHEET NO. DE1.2–ELECTRICAL DEMOLITION PLAN

REPLACE Demolition Note C with the following:

“C. Existing Utility Meter, conduit and wire shall remain until new service is energized and all

existing equipment is transferred to new service. Once energized, meter, conduit and wire shall be removed. Coordinate with Utility Company.”

REPLACE Demolition Note N with the following:

“N. 4” conduit shall remain for temporary power provided by OWNER. Once new service is energized and all existing equipment is transferred to new service, CONTRACTOR shall remove existing conduit and wire as well as temporary conduit, wire, supports, pole, etc. provided by OWNER. Coordinate work with Utility Company and OWNER prior to removal.”

2. SHEET NO. AS1.2-OVERALL FLOOR PLAN

ADD the following to the end of Key Note 16:


“Remove existing conduit supports and conduit per demolition plan DE1.2 following energizing of new service. Conduit is approximately 4 inches off the wall, approximately 8 feet above the floor. The conduit extends to the south to a point beyond the south wall of the facility. Provide finished interior and exterior surfaces as shown on drawings after conduit and conduit support removal.”

Please acknowledge this addendum on page E1 of the Contract Documents.

Electronic version of these documents can be found on the City of Madison web site at:

<http://www.cityofmadison.com/business/PW/contracts/openforBid.cfm>

If you are unable to download plan revisions associated with the addendum, please contact the Engineering office at 608-266-4751 receive the material by another route.



Robert F. Phillips, P.E., City Engineer

Prepared by: STRAND ASSOCIATES, INC.®, 910 West Wingra Drive, Madison, WI 53715