



# Madison Parks Division

210 Martin Luther King, Jr. Blvd., Room 104  
Madison, WI 53703  
608-266-4711 • cityofmadison.com/parks



October 30, 2018

## NOTICE OF ADDENDUM ADDENDUM 3

CONTRACT NO. 8267

Revise and amend the contract document(s) for the above project as stated in this addendum, otherwise, the original document shall remain in effect.

### PROPOSAL:

The following bid items have been changed. Please download the current proposal on <http://www.bidexpress.com>.

Action	Bid Item	Description	Units
Change	20101	EXCAVATION CUT	CY
Change	20132	FIELD UNDERDRAIN	LF
Change	40105	CRUSHED AGGREGATE BASE COURSE – DRAINABLE	TON

### SECTION D: SPECIAL PROVISIONS:

#### **BID ITEM 20101 – EXCAVATION CUT**

**Revise the 3<sup>rd</sup> paragraph under DESCRIPTION as follows:**

Excavation Cut required for construction of the following bid items shall be incidental to each respective bid items:

~~BID ITEM 20131 – UNDERDRAIN COLLECTOR – 8"~~

**Add sentence to last paragraph under DESCRIPTION.**

Excavation Cut for subgrade drainage is incidental to this bid item.

#### **BID ITEM 40105 – CRUSHED AGGREGATE BASE COURSE DRAINABLE**

**Revise the 5<sup>th</sup> and 6<sup>th</sup> paragraphs to read as follows:**

Surface to receive crushed aggregate base course - drainable shall be graded at 0.5% from the outside edge of the turf towards the underdrain collector as shown on the plans. Grading of subgrade shall be incidental to BID ITEM 20101 EXCAVATION CUT.

Prior to installation of synthetic turf, the subgrade drainage shall be inspected and certified by the Synthetic Turf Installer. Surface shall be maintained in clean condition throughout construction process.

**Revise the METHOD OF MEASUREMENT to read as follows:**

#### **METHOD OF MEASUREMENT**

Crushed Aggregate Base Course Drainable shall be measured by the ton as listed on the proposal page. Quantities listed on the proposal page include additional stone required for 0.5% drainage of subgrade.

**APPENDIX B:**

**Replace existing Appendix B with new Appendix B.**

Update includes additional subgrade excavation and crushed aggregate base course – drainable to accommodate 0.5% subgrade drainage.

**PLANS:**

**7.0 UTILITY PLAN – DOG PARK**

Replace existing Sheet 7.0 with new Sheet 7.0

**7.6 STORM SCHEDULE**

Replace existing Sheet 7.6 with new Sheet 7.6

**10.2 DETAILS – UNDERDRAIN**


Replace existing Sheet 10.2 with new Sheet 10.2

Please acknowledge this addendum on page E1 of the contract documents and/or in Section E: Bidder's Acknowledgement on Bid Express.

Electronic version of these documents can be found on the Bid Express web site at:

<http://www.bidexpress.com>

If you are unable to download plan revisions associated with the addendum, please contact the Engineering office at 608-266-4751 receive the material by another route.

for   
Eric Knepp, Parks Superintendent