


NOTES:
 ALL ASPHALT PATHS SHALL BE 8' WIDE AND HAVE MIN 2% CROSS SLOPE.
 TOTAL LENGTH OF PATH= 802 Lf
 BIO RETENTION AREA BOTTOM (994.00)= 758 SF
 BIO RETENTION AREA TOP (995.50)=1361 SF

City of Madison
 Department of Public Works
PARKS DIVISION
 City-County Building, Suite 104
 210 Martin Luther King, Jr. Blvd.
 Madison, WI 53703

play
MADISON
PARKS



PROJECT:
PARK PAVING 2021

PROJECT ADDRESS:
ORCHARD RIDGE PARK
5214 WHITCOMB DR
MADISON, WI 53711

Although every effort has been made in preparing these plans and checking them for accuracy, the contractor and subcontractors must check all details and dimensions of their trade and be responsible for the same.

ITEM	DATE
ADVERTISED	5-20-21
REVISED	6-1-21

PUBLIC WORKS PROJECT #:
9039

SHEET TITLE:
GRADING AND PAVING

SHEET NUMBER:
6.2

2021 PLAYGROUND INSTALLATION (BY OTHERS) TO BE COMPLETED PRIOR TO PATH PROJECT. MATCH EX ASPHALT STUB.

DISTURBANCE LIMITS ALL DISTURBED AREA SHALL BE RESTORED WITH TOPSOIL, SEED, AND MATTING.

7" CONCRETE RAMP PER S.D.D. 3.14 W/ 2' FLARES REPLACE 12' CURB AND GUTTER

PATH EDGE: 2' TRANSITION AT 4% (TYPICAL)
 BASE COURSE SHALL EXTEND MIN 12" BEYOND EDGE OF ASPHALT (TYP)

PROPOSED BIO RETENTION PER S.D.D. 2.09 SEE PAGE 6.3 FOR DETAILS

OLD PLAY EQUIPMENT TO BE REMOVED PRIOR TO PROJECT