



Department of Public Works
City Engineering Division

Robert F. Phillips, P.E.
City Engineer

City-County Building, Room 115
210 Martin Luther King, Jr. Boulevard
Madison, Wisconsin 53703
FAX 608 264 9275
www.cityofmadison.com

608 266 4751

Assistant City Engineer
Michael R. Dailey, P.E.

Principal Engineers
Christina M. Bachmann, P.E.
John S. Fahrney, P.E.
Gregory T. Fries, P.E.
Christopher J. Petykowski, P.E.

Facilities & Sustainability
Jeanne E. Hoffman, Manager
James C. Whitney, A.I.A.

Operations Supervisor
Kathleen M. Cryan

GIS Manager
David A. Davis, R.L.S.

Financial Officer
Steven B. Danner-Rivers

Hydrogeologist
Brynn Bemis

NOTICE OF ADDENDUM

ADDENDUM NO. 2

CHEROKEE DRIVE UTILITIES WITH RESURFACING ASSESSMENT DISTRICT-2013

CONTRACT NO. 7016

Revise and amend the contract document(s) for the above project as stated in this addendum, otherwise, the original document shall remain in effect.

PROPOSAL PAGE :

REMOVE

Remove PROPOSAL pages E-5 - E-9

INSERT

Insert PROPOSAL REVISED page E-5 – E-9.

Changed Unit on BID ITEM 70440 to L.F.

Please acknowledge this addendum on page E1 of the contract documents.

Electronic version of these documents can be found on the City of Madison web site at:

<http://www.cityofmadison.com/business/PW/contracts/openforBid.cfm>

If you are unable to download plan revisions associated with the addendum, please contact the Engineering office at 608-266-4751 receive the material by another route.

Robert F. Phillips, City Engineer

PROPOSAL

NAME OF BIDDER

Cherokee Dr Utilities w/Resurfacing Assmit Dist-2013

REV 3/19/13

Contract 7016

| ITEM | TYPE OF WORK | ESTIMATED QUANTITES | UNIT PRICE BID | TOTAL BID |
|---|--|---------------------|----------------|-----------|
| STREET ACCOUNT NO.CS53-58260-810358-00-53W1553 | | | | |
| 10701 | TRAFFIC CONTROL | 1.00 | L.S. | \$ - |
| 10801 | ROOT CUTTING-CURB & GUTTER | 270.00 | L.F. | \$ - |
| 10802 | ROOT CUTTING-SIDEWALK | 45.00 | L.F. | \$ - |
| 10911 | MOBILIZATION | 1.00 | L.S. | \$ - |
| 20101 | EXCAVATION CUT | 3,733.00 | C.Y. | \$ - |
| 20219 | BREAKER RUN | 3,600.00 | TON | \$ - |
| 20221 | TOPSOIL | 3,590.00 | S.Y. | \$ - |
| 20303 | SAWCUT BITUMINOUS PAVEMENT | 170.00 | L.F. | \$ - |
| 20321 | REMOVE CONCRETE PAVEMENT | 3,181.00 | S.Y. | \$ - |
| 20322 | REMOVE CONCRETE CURB & GUTTER | 3,290.00 | L.F. | \$ - |
| 20323 | REMOVE CONCRETE SIDEWALK & DRIVE | 8,020.00 | SF | \$ - |
| 20401 | CLEARING | 191.00 | ID | \$ - |
| 20403 | GRUBBING | 270.00 | ID | \$ - |
| 20501 | ADJUST SEWER ACCESS STRUCTURE | 20.00 | EACH | \$ - |
| 20701 | TERRACE SEEDING | 3,590.00 | SY | \$ - |
| 21061 | EROSION MATTING, CLASS I, URBAN TYPE A | 3,590.00 | SY | \$ - |
| 30201 | TYPE "A" CONCRETE CURB & GUTTER | 3,230.00 | LF | \$ - |
| 30301 | 5 INCH CONCRETE SIDEWALK | 5,042.00 | SF | \$ - |
| 30302 | 7 INCH CONCRETE SIDEWALK & DRIVE | 3,500.00 | SF | \$ - |
| 30311 | CONCRETE MOUNTABLE MEDIAN ISLAND NOSE | 220.00 | SF | \$ - |

Cherokee Dr Utilities w/Resurfacing Assmit Dist-2013

REV 3/19/13

Contract 7016

| ITEM | TYPE OF WORK | ESTIMATED QUANTITIES | | UNIT PRICE BID | TOTAL BID |
|--|--|----------------------|------|----------------|-----------|
| 30340 | CURB RAMP DETECTABLE WARNING FIELDS | 160.00 | SF | | \$ - |
| 40101 | CRUSHED AGGREGATE BASE COURSE, GRADATION NO. 1 | 1,330.00 | TON | | \$ - |
| 40102 | CRUSHED AGGREGATE BASE COURSE, GRADATION NO. 2 | 1,450.00 | TON | | \$ - |
| 40202 | HMA PAVEMENT TYPE E-1 | 3,330.00 | TON | | \$ - |
| 40231 | ASPHALT DRIVE & TERRACE | 20.00 | S.Y. | | \$ - |
| 40311 | PULVERIZE AND SHAPE | 11,610.00 | S.Y. | | \$ - |
| 40370 | ADJUST MONUMENT CASTING-RESURFACING | 1.00 | EACH | | \$ - |
| 40381 | REMOVE & REPLACE CONC. C&G, MACHINE PLACED MORE THAN 100 CONTINUOUS FEET-RESURFACING | 2,700.00 | L.F. | | \$ - |
| 40382 | REMOVE & REPLACE CONC. C&G, HAND PLACED-RESURFACING | 1,250.00 | LF | | \$ - |
| 90001 | CONCRRETE SPEED HUMP-SPECIAL | 80.00 | S.Y. | | \$ - |
| 90033 | ADJUST MMSD SEWER ACCESS STRUCTURE | 8.00 | EACH | | \$ - |
| STREET ACCOUNT NO. CS53-58545-810358-00-53W1553 | | | | | |
| 60230 | FURNISH & INSTALL 2 INCH PVC (SCHEDULE 80) CONDUIT | 100.00 | LF | | \$ - |
| 60232 | FURNISH & INSTALL 2 INCH PVC (SCHEDULE 40) CONDUIT | 465.00 | LF | | \$ - |
| 60241 | GOPHER RACEWAY FOR ELECTRICAL CONDUIT OR CABLE-IN-DUCT | 50.00 | LF | | \$ - |
| 60261 | ELECTRICAL TRENCH | 515.00 | LF | | \$ - |
| 60702 | CONSTRUCT ELECTRICAL HANDHOLE TYPE 1 | 5.00 | EACH | | \$ - |
| STREET ACCOUNT NO. CS53-58270-810358-00-53W1553 | | | | | |
| 20217 | CLEAR STONE | 400 | TONS | | \$ - |
| 20502 | ADJUST CATCHBASIN | 3 | EACH | | \$ - |
| 21001 | EROSION CONTROL PLAN & IMPLEMENTATI | 1 | LS | | \$ - |
| 21002 | EROSION CONTROL INSPECTION | 20 | EACH | | \$ - |
| 21011 | CONSTRUCTION ENTRANCE | 5 | EACH | | \$ - |

Cherokee Dr Utilities w/Resurfacing Assmit Dist-2013

REV 3/19/13

Contract 7016

| ITEM | TYPE OF WORK | ESTIMATED QUANTITIES | | UNIT PRICE BID | TOTAL BID |
|---|--|----------------------|----------|----------------|-----------|
| | | | | | |
| 21012 | STREET CONSTRUCTION ENTRANCE BERM | 2 | EACH | | \$ - |
| 21013 | STREET SWEEPING | 1 | LS | | \$ - |
| 21015 | STREET CONSTRUCTION STONE BERM | 4 | EACH | | \$ - |
| 21024 | SILT SOCK COMPLETE | 256 | LF | | \$ - |
| 21041 | INLET PROTECTION TYPE D - COMPLETE | 57 | EACH | | \$ - |
| 21052 | POLYMER STABILIZATION | 2500 | SY | | \$ - |
| 50411 | 12 INCH RCP STORM SEWER PIPE | 603 | LF | | \$ - |
| 50741 | H INLET | 16 | EACH | | \$ - |
| STORM SEWER ACCOUNT NO. ESTM-58270-810381-00-53W1553 | | | | | |
| 10702 | TRAFFIC CONTROL FOR STORM SEWER INSTALLATION | 1 | LUMP SUM | | \$ - |
| 10912 | MOBILIZATION FOR STORM SEWER | 1 | LUMP SUM | | \$ - |
| 20312 | REMOVE STRUCTURE | 1 | EACH | | \$ - |
| 20313 | REMOVE INLET | 8 | EACH | | \$ - |
| 20314 | REMOVE PIPE | 349 | LF | | \$ - |
| 20332 | ABANDON CATCHBASIN | 2 | EACH | | \$ - |
| 20337 | PIPE PLUG STORM | 15 | EACH | | \$ - |
| 40366 | REBUILD INLET - RESURFACING | 10 | EACH | | \$ - |
| 50211 | SELECT BACKFILL FOR STORM SEWER | 1931 | TF | | \$ - |
| 50226 | UTILITY TRENCH PATCH- TYPE III | 6 | SY | | \$ - |
| 50412 | 15 INCH RCP STORM SEWER PIPE | 28 | LF | | \$ - |

Cherokee Dr Utilities w/Resurfacing Assmit Dist-2013

REV 3/19/13

Contract 7016

| ITEM | TYPE OF WORK | ESTIMATED QUANTITIES | | UNIT PRICE BID | TOTAL BID |
|--|--|----------------------|----------|----------------|-----------|
| | | | | | |
| 50414 | 21 INCH RCP STORM SEWER PIPE | 13 | LF | | \$ - |
| 50415 | 24 INCH RCP STORM SEWER PIPE | 299 | LF | | \$ - |
| 50416 | 27 INCH RCP STORM SEWER PIPE | 34 | LF | | \$ - |
| 50417 | 30 INCH RCP STORM SEWER PIPE | 22 | LF | | \$ - |
| 50421 | 54 INCH RCP STORM SEWER PIPE | 899 | LF | | \$ - |
| 50471 | 54 INCH RCP AE | 1 | EACH | | \$ - |
| 50499 | CONCRETE COLLAR (UNDISTRIBUTED) | 3 | EACH | | \$ - |
| 50611 | 54 INCH RCP AE GATE | 1 | EACH | | \$ - |
| 50723 | 3X3 STORM SAS | 4 | EACH | | \$ - |
| 50724 | 4X4 STORM SAS | 1 | EACH | | \$ - |
| 50725 | 5X5 STORM SAS | 1 | EACH | | \$ - |
| 50726 | 6X6 STORM SAS | 1 | EACH | | \$ - |
| 50763 | TERRACE INLET TYPE II | 1 | EACH | | \$ - |
| 50763 | TERRACE INLET TYPE III | 1 | EACH | | \$ - |
| 50792 | STORM SEWER TAP | 3 | EACH | | \$ - |
| 50801 | ULO | 7 | EACH | | \$ - |
| 90032 | 6X3 STORM SAS | 4 | EACH | | \$ - |
| WQ PRACTICES ACCOUNT NO: ESTM-58270-810551-00-53W1553 | | | | | |
| 90030 | PARK ACCESS/RESTORATION FOR STORM SEWER INSTALLATION | 1 | LS | | \$ - |
| 90031 | PLUNGE POOL | 1 | EACH | | \$ - |
| WATER ACCOUNT NO. EW01-58273-810455-00-53W1553 | | | | | |
| 10703 | TRAFFIC CONTROL FOR WATER MAIN INSTALLATION | 1.00 | LUMP SUM | | \$ - |
| 10913 | MOBILIZATION FOR WATER MAIN INSTALLATION | 1.00 | LUMP SUM | | \$ - |

Cherokee Dr Utilities w/Resurfacing Assmit Dist-2013

REV 3/19/13

Contract 7016

| ITEM | TYPE OF WORK | ESTIMATED QUANTITES | | UNIT PRICE BID | TOTAL BID |
|--------------------|---|---------------------|------|----------------|-----------|
| | | | | | |
| 40391 | REMOVE & REPLACE 5" THICK CONCRETE SIDEWALK-RESURFACING | 200.00 | S.F. | | \$ - |
| 40392 | REMOVE & REPLACE 7" THICK CONCRETE SIDEWALK AND DRIVE-RESURFACING | 120.00 | S.F. | | \$ - |
| 50225 | UTILITY TRENCH PATCH- TYPE III | 10.00 | S.Y. | | \$ - |
| 70002 | FURNISH AND INSTALL 6 INCH PIPE & FITTINGS | 80.00 | L.F. | | \$ - |
| 70003 | FURNISH AND INSTALL 8 INCH PIPE & FITTINGS | 2180.00 | L.F. | | \$ - |
| 70404 | REMOVAL OF EXCESS AMOUNTS OF BOULDERS | 50.00 | C.Y. | | \$ - |
| 70405 | CUT-IN CONNECTION | 6.00 | EACH | | \$ - |
| 70407 | FURNISH AND INSTALL HYDRANT | 4.00 | EACH | | \$ - |
| 70408 | SELECT FILL - SAND FOR WATER | 2260.00 | L.F. | | \$ - |
| 70413 | FURNISH AND INSTALL STYROFOAM | 80.00 | L.F. | | \$ - |
| 70414 | CUT OFF EXISTING WATER MAIN | 5.00 | EACH | | \$ - |
| 70415 | ABANDON WATER VALVE BOX | 4.00 | EACH | | \$ - |
| 70416 | ABANDON HYDRANT | 1.00 | EACH | | \$ - |
| 70418 | ADJUST WATER VALVE BOX | 12.00 | EACH | | \$ - |
| 70424 | TERRACE RESTORATION FOR WATER MAIN | 1800.00 | L.F. | | \$ - |
| 70425 | CUT OFF EXISTING WATER MAIN FITTING | 1.00 | EACH | | \$ - |
| 70428 | FURNISH AND INSTALL 6 INCH VALVE | 5.00 | EACH | | \$ - |
| 70429 | FURNISH AND INSTALL 8 INCH VALVE | 7.00 | EACH | | \$ - |
| 70440 | EXTEND AND RECONNECT 1-INCH SERVICE LATERAL | 120.00 | L.F. | | \$ - |
| 70446 | REPLACE 1-INCH COPPER SERVICE LATERAL | 600.00 | L.F. | | \$ - |
| 70452 | ADJUST WATER SERVICE BOX | 3.00 | EACH | | \$ - |
| 70456 | FURNISH EXCAVATION AND DITCH FOR LIVE TAP | 1.00 | EA | | \$ - |
| GRAND TOTAL | | | | | |