



Department of Public Works  
**Engineering Division**  
 Robert F. Phillips, P.E., City Engineer  
 City-County Building, Room 115  
 210 Martin Luther King, Jr. Boulevard  
 Madison, Wisconsin 53703  
 Phone: (608) 266-4751  
 Fax: (608) 264-9275  
[engineering@cityofmadison.com](mailto:engineering@cityofmadison.com)  
[www.cityofmadison.com/engineering](http://www.cityofmadison.com/engineering)

**Assistant City Engineer**  
 Michael R. Dailey, P.E.  
**Principal Engineer 2**  
 Gregory T. Fries, P.E.  
**Principal Engineer 1**  
 Christina M. Bachmann, P.E.  
 Eric L. Dundee, P.E.  
 John S. Fahrney, P.E.  
 Christopher J. Petykowski, P.E.  
**Facilities & Sustainability**  
 Jeanne E. Hoffman, Manager  
**Operations Manager**  
 Kathleen M. Cryan  
**Mapping Section Manager**  
 Eric T. Pederson, P.S.  
**Financial Manager**  
 Steven B. Danner-Rivers

May 3, 2017

**NOTICE OF ADDENDUM:  
 ADDENDUM 1**

**CONTRACT NO. 7957  
 UTILITY REPLACEMENT WITH RESURFACING ASSESSMENT DISTRICT - 2017**

Revise and amend the contract document(s) for the above project as stated in this addendum, otherwise, the original document shall remain in effect.

Revise and amend the contract document(s) for the above project as stated in this addendum, otherwise, the original document shall remain in effect.

**PLANS:**

None

**SPECIAL PROVISIONS:**

**BID ITEM 90030 – 5'X7' STORM SAS**

**DESCRIPTION**

Work under this item includes construction of a new 5' x 7' field poured storm structure, providing and installing two (2) castings (Two R-1550-0054), setting and adjustment of the castings to the grade as called out in the plan set or as directed in the field. The 5' x 7' field poured SAS shall have steel reinforcement and wall dimensions as described below:

**PROPOSAL:**

A summary of the changes to the proposal is as follows:


Action	Bid Item	Description	Quantity	Units
MODIFY	50225	UTILITY TRENCH PATCH TYPE III	50	T.F.
MODIFY	50227	UTILITY TRENCH PATCH TYPE IV	470	T.F.
REMOVE	70002	FURNISH AND INSTALL 6 INCH PIPE & FITTINGS	30	L.F.
MODIFY	70003	FURNISH AND INSTALL 8 INCH PIPE & FITTINGS	520	L.F.
REMOVE	70031	FURNISH AND INSTALL 6-INCH WATER VALVE	1	EACH
REMOVE	70040	FURNISH, INSTALL AND SALVAGE HYDRANT	1	EACH

MODIFY	70080	CUT-IN OR CONNECT TO EXISTING WATER SYSTEM	4	EACH
MODIFY	70101	FURNISH AND INSTALL STYROFOAM	120	L.F.
MODIFY	70104	ADJUST WATER VALVE BOX	3	EACH
MODIFY	90070	EXCAVATION AND HAULING OF PETROLEUM CONTAMINATED SOIL(UNDISTRIBUTED)	500	TON

-----  
Please acknowledge this addendum on page E1 of the contract documents and/or in Section E: Bidder's Acknowledgement on Bid Express.

Electronic version of these documents can be found on the Bid Express web site at:

<http://www.bidexpress.com>

  
\_\_\_\_\_  
Robert F. Phillips, P.E., City Engineer

RFP: sms