



Department of Public Works  
**Engineering Division**  
James M. Wolfe, P.E., City Engineer  
City-County Building, Room 115  
210 Martin Luther King, Jr. Boulevard  
Madison, Wisconsin 53703  
Phone: (608) 266-4751  
Fax: (608) 264-9275  
[engineering@cityofmadison.com](mailto:engineering@cityofmadison.com)  
[www.cityofmadison.com/engineering](http://www.cityofmadison.com/engineering)

**Assistant City Engineer**  
Bryan Cooper, AIA  
Gregory T. Fries, P.E.  
Chris Petykowski, P.E.  
**Deputy Division Manager**  
Kathleen M. Cryan  
**Principal Engineer 2**  
John S. Fahrney, P.E.  
Janet Schmidt, P.E.  
**Principal Engineer 1**  
Mark D. Moder, P.E.  
**Financial Manager**  
Steven B. Danner-Rivers

March 3, 2023

NOTICE OF ADDENDUM  
ADDENDUM NO. 1  
CONTRACT NO. 9285

CIPP UV LINING REHABILITATION OF  
SANITARY SEWERS WEST PHASE 1 - 2023

Revise and amend the contract document(s) for the above project as stated in this addendum, otherwise, the original document shall remain in effect.

**SPECIFICATIONS:**

**SECTION D: SPECIAL PROVISIONS**

**SECTION 102.1 PRE-QUALIFICATION OF BIDDERS**

The minimum qualifications section of 'CATEGORY #399 UV SEWER LINING' shall be updated as follows:

"The Contractor performing the work shall submit documentation demonstrating that they clearly meet the minimum qualifications as stated below:

- Contractor, **or the Contractor Subcontractor**, must show that they have a minimum of 30,000 linear feet of UV cured CIPP sewer lining successfully installed using the same UV CIPP lining system that will be used for this contract. The 30,000 linear feet shall be installed in sanitary sewer gravity mains of various sizes only, any UV CIPP installed in water main shall not apply.
- Contractor, **or the Contractor Subcontractor**, must show that the Contractor project supervisor or foreperson that will be overseeing the installation crew must have a minimum of 20,000 linear feet of UV cured CIPP sewer lining successfully installed using the same UV CIPP lining system that will be used for this contract. The 20,000 linear feet shall be installed in sanitary sewer gravity mains of various sizes only, any UV CIPP installed in water main shall not apply."

The remainder of the text within this section shall remain the same as the original contract.

**SECTION 509.7(a) INSPECTION AND TESTING**

Grouting of service connections will not be required under this contract. This section shall be updated as follows:

"CCTV Inspection and Acceptance - The Contractor shall perform a detailed closed-circuit television

inspection in accordance with NAASCO's Pipeline Assessment and Certification Program (PACP) standards, after installation of the CIPP liner and reconnection of the service connections."

The remainder of the text within this section shall remain the same as the original contract.


Please acknowledge this addendum on page E1 of the contract documents and/or in Section E: Bidder's Acknowledgement on Bid Express.

Electronic version of these documents can be found on the Bid Express web site at:

<http://www.bidexpress.com>

If you are unable to download plan revisions associated with the addendum, please contact the Engineering office at 608-266-4751 receive the material by another route.

Sincerely,



For:

James M. Wolfe, P.E., City Engineer  
City Engineer