



Department of Public Works
City Engineering Division

Robert F. Phillips, P.E.
City Engineer

City-County Building, Room 115
210 Martin Luther King, Jr. Boulevard
Madison, Wisconsin 53703
FAX 608 264 9275
www.cityofmadison.com

608 266 4751

Assistant City Engineer
Michael R. Dalley, P.E.

Principal Engineers
Christina M. Bachmann, P.E.
John S. Fahrney, P.E.
Gregory T. Fries, P.E.
Christopher J. Petykowski, P.E.

Facilities & Sustainability
Jeanne E. Hoffman, Manager
James C. Whitney, A.I.A.

Operations Supervisor
Kathleen M. Cryan

GIS Manager
David A. Davis, R.L.S.

Financial Officer
Steven B. Danner-Rivers

Hydrogeologist
Brynn Bemis

NOTICE OF ADDENDUM

**SOUTH INGERSOLL STREET AND RUTLEDGE STREET ASSESSMENT
DISTRICT - 2012**

ADDENDUM NO. 3

CONTRACT NO. 6803

REMOVE

Proposal pages E-5 thru E-10 (revised March 5, 2012)

INSERT

Proposal pages E-5 – E-10 (revised March 7, 2012) (bid items 30201, 30301)

Revise and amend the contract document(s) for the above project as stated in this addendum, otherwise, the original document shall remain in effect.

Please acknowledge this addendum on page E1 of the contract documents.

Electronic version of these documents can be found on the City of Madison web site at:

<http://www.cityofmadison.com/business/PW/contracts/openforBid.cfm>

If you are unable to download plan revisions associated with the addendum, please contact the Engineering office at 608-266-4751 receive the material by another route.

Robert F. Phillips, P.E., City Engineer

PROPOSAL

REVISED MARCH 7, 2012

NAME OF BIDDER

SOUTH INGERSOLL STREET AND RUTLEDGE STREET ASSESSMENT DISTRICT - 2012

CONTRACT NO. 6803

ITEM	TYPE OF WORK	ESTIMATED QUANTITIES		UNIT PRICE BID	TOTAL BID
STREET ACCOUNT NO. CS53-58250-810355-00-53W0603					
10701	TRAFFIC CONTROL	1	LUMP SUM		
10801	ROOT CUTTING - CURB & GUTTER	195	L.F.		
10802	ROOT CUTTING - SIDEWALK	100	L.F.		
10911	MOBILIZATION	1	LUMP SUM		
20101	EXCAVATION CUT	2175	C.Y.		
20130	UNDERDRAIN	110	L.F.		
20140	GEOTEXTILE FABRIC TYPE SAS (NON-WOVEN)	500	S.Y.		
20219	BREAKER RUN	1000	TON		
20221	TOPSOIL	2000	S.Y.		
20303	SAWCUT BITUMINOUS PAVEMENT	150	L.F.		
20322	REMOVE CONCRETE CURB & GUTTER	1600	L.F.		
20323	REMOVE CONCRETE SIDEWALK & DRIVE	6400	S.F.		
20324	REMOVE CONCRETE STEPS	125	S.F.		
20401	CLEARING	20	I.D.		
20403	GRUBBING	40	I.D.		
20701	TERRACE SEEDING	1800	S.Y.		
21061	EROSION MATTING, CLASS 1, URBAN TYPE A	200	S.Y.		
30201	TYPE "A" CONCRETE CURB & GUTTER	1875	L.F.		
30203	TYPE "X" CONCRETE CURB & GUTTER	75	L.F.		
30208	HAND FORMED CONCRETE CURB & GUTTER (TREE LOCATIONS)	50	L.F.		
30301	5 INCH CONCRETE SIDEWALK	4730	S.F.		

PROPOSAL

REVISED MARCH 7, 2012

NAME OF BIDDER

SOUTH INGERSOLL STREET AND RUTLEDGE STREET ASSESSMENT DISTRICT - 2012

CONTRACT NO. 6803

ITEM	TYPE OF WORK	ESTIMATED QUANTITIES		UNIT PRICE BID	TOTAL BID
30302	7 INCH CONCRETE SIDEWALK & DRIVE	1675	S.F.		
30340	CURB RAMP DETECTABLE WARNING FIELDS	72	S.F.		
40101	CRUSHED AGGREGATE BASE COURSE, GRADATION NO. 1	1000	TON		
40102	CRUSHED AGGREGATE BASE COURSE, GRADATION NO. 2	2100	TON		
40201	HMA PAVEMENT TYPE E-0.3	925	TON		
40211	TACK COAT	200	GAL		
40231	ASPHALT DRIVE & TERRACE	50	S.Y.		
40301	FULL WIDTH GRINDING	130	S.Y.		
90001	INTRODUCTION OF CITY RESIDENT INTO THE CONSTRUCTION WORKFORCE THROUGH EMPLOYMENT OF TWO (2) CONSTRUCTION CRAFT LABOR APPRENTICES	480	HRS	\$ 37.40	\$ 17,952.00
90002	SEEDING - WISDOT TYPE 30	200	S.Y.		

STREET ACCOUNT NO. CS53-58270-810355-00-53W0603

20217	CLEAR STONE	280	TON		
21001	EROSION CONTROL PLAN & IMPLEMENTATION	1	LUMP SUM		
21002	EROSION CONTROL INSPECTION	10	EACH		
21011	CONSTRUCTION ENTRANCE	3	EACH		
21012	STREET CONSTRUCTION ENTRANCE BERM	1	EACH		
21013	STREET SWEEPING	1	LUMP SUM		
21017	INLET PROTECTION TYPE D	6	EACH		
21024	SILT SOCK COMPLETE	120	L.F.		
21052	POLYMER STABILIZATION	2500	S.Y.		
50411	12 INCH RCP STORM SEWER PIPE	283	L.F.		

PROPOSAL

REVISED MARCH 7, 2012

NAME OF BIDDER

SOUTH INGERSOLL STREET AND RUTLEDGE STREET ASSESSMENT DISTRICT - 2012

CONTRACT NO. 6803

ITEM	TYPE OF WORK	ESTIMATED QUANTITIES		UNIT PRICE BID	TOTAL BID
50741	H INLET	8	EACH		
90032	PROVIDE & INSTALL INLET PROTECTION TYPE D HYBRID	20	EACH		
90033	MAINTAIN INLET PROTECTION TYPE D HYBRID	20	EACH		
90034	REMOVE INLET PROTECTION TYPE D HYBRID	20	EACH		
STORM ACCOUNT NO. ESTM-58270-810381-00-53W0603					
10702	TRAFFIC CONTROL FOR STORM SEWER INSTALLATION	1	LUMP SUM		
10912	MOBILIZATION FOR STORM SEWER	1	LUMP SUM		
20313	REMOVE INLET	3	EACH		
20314	REMOVE PIPE	54	L.F.		
20502	ADJUST CATCHBASIN	1	EACH		
50211	SELECT BACKFILL FOR STORM SEWER	283	T.F		
50792	STORM SEWER TAP	4	EACH		
50801	UTILITY LINE OPENING (ULO)	3	EACH		
90030	RECONSTRUCT CATCH BASIN	1	EACH		
90031	24" HDPE SLIPLINE	161	L.F.		
90035	PRIVATE STORM SEWER RECONNECT	3	EACH		
STORM ACCOUNT NO. ESTM-58270-810515-00-53W0603					
90036	RAINGARDEN	2	EACH		
STORM ACCOUNT NO. ESTM-58270-810551-00-53W0603					
50763	TERRACE INLET TYPE II	1	EACH		
SANITARY ACCOUNT NO. ES01-58275-810332-00-53W0603					
10704	TRAFFIC CONTROL FOR SANITARY SEWER INSTALLATION	1	LUMP SUM		
10914	MOBILIZATION FOR SANITARY SEWER	1	LUMP SUM		

PROPOSAL

REVISED MARCH 7, 2012

NAME OF BIDDER

SOUTH INGERSOLL STREET AND RUTLEDGE STREET ASSESSMENT DISTRICT - 2012

CONTRACT NO. 6803

ITEM	TYPE OF WORK	ESTIMATED QUANTITIES		UNIT PRICE BID	TOTAL BID
20311	REMOVE SAS	3	EACH		
20331	ABANDON SEWER ACCESS STRUCTURE	5	EACH		
20336	PIPE PLUG	40	EACH		
20501	ADJUST SEWER ACCESS STRUCTURE	2	EACH		
50201	ROCK EXCAVATION (UNDISTRIBUTED)	50	CY		
50212	SELECT BACKFILL SANITARY SEWER	1654	TF		
50226	UTILITY TRENCH PATCH TYPE III	40	TF		
50301	8 INCH PVC SANITARY SEWER PIPE (SDR-35 & SDR-26)	1061	LF		
50353	SANITARY SEWER LATERAL (SDR35 & SDR-26)	593	LF		
50354	RECONNECT SANITARY SEWER LATERAL	22	EACH		
50361	WASTEWATER CONTROL	1	EACH		
50390	SEWER ELECTRONIC MARKERS	44	EACH		
50701	4' DIA SAS	6	EACH		
50791	SANITARY SEWER TAP	4	EACH		
50783	INSIDE DROP	2.18	VF		
WATER ACCOUNT NO. EW01-58273-810455-00-53W0603					
10703	TRAFFIC CONTROL FOR WATER MAIN INST/	1	LUMP SUM		
10913	MOBILIZATION FOR WATER MAIN INSTALLATION	1	LUMP SUM		
50801	UTILITY LINE OPENING (ULO)	1	EACH		
70001	FURNISH AND INSTALL 4 INCH PIPE & FITTING	20	L.F.		
70002	FURNISH AND INSTALL 6 INCH PIPE & FITTINGS	100	L.F.		
70003	FURNISH AND INSTALL 8 INCH PIPE & FITTINGS	1300	L.F.		

PROPOSAL

REVISED MARCH 7, 2012

NAME OF BIDDER

SOUTH INGERSOLL STREET AND RUTLEDGE STREET ASSESSMENT DISTRICT - 2012

CONTRACT NO. 6803

ITEM	TYPE OF WORK	ESTIMATED QUANTITIES		UNIT PRICE BID	TOTAL BID
70004	FURNISH AND INSTALL 10 INCH PIPE & FITTINGS	40	L.F.		
70005	FURNISH AND INSTALL 12 INCH PIPE & FITTINGS	70	L.F.		
70405	CUT-IN CONNECTION	1	EACH		
70407	FURNISH AND INSTALL HYDRANT	5	EACH		
70408	SELECT FILL - SAND FOR WATER	1530	L.F.		
70413	FURNISH AND INSTALL STYROFOAM	72	L.F.		
70414	CUT OFF EXISTING WATER MAIN	5	EACH		
70415	ABANDON WATER VALVE BOX	4	EACH		
70416	ABANDON HYDRANT	2	EACH		
70417	ABANDON WATER VALVE ACCESS STRUCTURE	2	EACH		
70418	ADJUST WATER VALVE BOX	2	EACH		
70424	TERRACE RESTORATION FOR WATER MAIN	50	L.F.		
70427	FURNISH AND INSTALL 4 INCH VALVE	1	EACH		
70428	FURNISH AND INSTALL 6 INCH VALVE	5	EACH		
70429	FURNISH AND INSTALL 8 INCH VALVE	5	EACH		
70440	EXTEND AND RECONNECT SERVICE LATERAL - 1 INCH	115	L.F.		
70443	RECONNECT / DISCONNECT SERVICE LATERAL - 1 INCH	6	EACH		
70444	RECONNECT / DISCONNECT SERVICE LATERAL - 1.5 INCHES OR 2 INCHES	1	EACH		
70450	FURNISH AND INSTALL CURB BOX	3	EACH		
70451	FURNISH AND INSTALL CURB STOP	3	EACH		
70452	ADJUST WATER SERVICE BOX	5	EACH		
70453	ABANDON EXISTING CURB BOX	2	EACH		

PROPOSAL

REVISED MARCH 7, 2012

NAME OF BIDDER

SOUTH INGERSOLL STREET AND RUTLEDGE STREET ASSESSMENT DISTRICT - 2012

CONTRACT NO. 6803

ITEM	TYPE OF WORK	ESTIMATED QUANTITIES		UNIT PRICE BID	TOTAL BID
70454	REPLACE COPPER SERVICE LATERAL	20	L.F.		
70455	PIPE PLUG FOR WATER MAIN INSTALLATION	2	EACH		
70456	FURNISH EXCAVATION AND DITCH FOR LIVE TAP	5	EA		
GRAND TOTAL					