#### PUBLIC INFORMATION MEETING, OCTOBER 13, 2022

WELL 19; LAKE MENDOTA DR.





### Well 19 Treatment System Project

Madison Water Utility, Project Owner Short Elliot Hendrickson (SEH), Consulting Engineer


#### PRESENTATION OVERVIEW:

- Introductions: Alder Vidaver, Design Team
- Well 19 Location & Background
- Project Need & Objectives
- Preliminary Design Options
- Final Design Development
- Project Schedule
- Q & A; Public Input; Tour

#### LOCATION & BACKGROUND: WELL 19

The facility is situated on an easement on University of Wisconsin-Madison property





Well 19 is located east of Eagle Heights, North of the community gardens and west of Picnic Point

#### LOCATION & BACKGROUND: WELL 19

Constructed in 1974, it includes a well house and buried 3-million gallon reservoir




The buried reservoir: facing south



The well house: facing north



The well house entrance: facing west



Well 19 primarily serves the University of Wisconsin campus area, the Village of Shorewood Hills and is a significant supply point for the entire near west side of Madison

### PROJECT NEED / JUSTIFICATION

- There are three, naturally-occurring contaminants in Well 19's water
- At Water Utility Board Policy levels, action to mitigate contamination is required

Contaminant	Primary MCL (Enforceable)	Secondary MCL (Non-Enforceable)	Water Utility Board Policy	Well 19 Results
Radium	5 pCi/L		4 pCi/L	4.1 pCi/L*
Manganese		0.05 mg/L	0.02 mg/L	0.045 mg/L
Iron		0.3 mg/L	0.1 mg/L	0.2 mg/L

<sup>\*</sup> Running Annual Average

Due to poor water quality the utility self-limits production— currently only 30% of annual capacity, on average, is utilized

#### PROJECT OBJECTIVES

- 1. Reduce iron, manganese, and radium levels at Well 19 through the addition of a filtration system
- 2. Improve water quality to optimize use of this critically important supply point
- 3. **Upgrade** the original pumps and electronic controls for more energy-efficient operations

### PRELIMINARY DESIGN OPTIONS 1 & 2

#1: Vertical expansion of existing building with external backwash (BW) tank



#2: Addition to the existing building with external backwash (BW) tank



#### ENVIRONMENTAL & SOCIAL IMPACTS

Table – 1 Environmental and Social Impacts				
	Option – 1	Option – 2		
Post-construction impacts to long-term maintenance	Significant	Negligible		
Construction impacts to well operation and water supply	Significant	Negligible		
Impacts on the viewsheds from Eagle Heights and the Lakeshore Nature Preserve	Negligible	Moderate		
Increased impervious area	Moderate	Moderate		
Site disturbance during construction	Moderate	Moderate		

#### COST IMPACTS

### Table – 2 Estimated Cost Comparison

	Option – 1	Option – 2	
Construction Cost	\$6.8M	\$6.8M	
Annual O&M Costs	\$36K	\$44K	
50-Year Lifecycle Cost	\$12.4M	\$12.8M	

- Option 2 is more desirable from a social and environmental perspective
- Option 1 is slightly more desirable from a financial perspective
- Utility staff recommended Option 2
- The minimal additional cost compensates for the greater social and environmental benefits of Option 2.


#### WU BOARD APPROVES OPTION 2

- At its September meeting, the Water Utility Board unanimously approved staff's recommendation to move Option 2 to final design
- Pending Regulatory Approvals:
  - Dept. of Natural Resources (safe drinking water)
  - Public Service Commission (impact to rate-payers)
  - City Planning Commission (building code compliance)


#### FINAL DESIGN: AERIAL VIEW



#### FINAL DESIGN: FLOOR PLAN



#### FINAL DESIGN: ELEVATION VIEW



Looking northwest toward Eagle Heights

## FINAL DESIGN: LANDSCAPE PLAN OVERVIEW



- Focus on screening using Wisconsin native species
- Developed with input from Lakeshore Nature Preserve and UW Landscape Architects
- Matches recent plantings in adjacent Preserve
- Dense: fills low, mid-range and high canopy

## FINAL DESIGN: LANDSCAPE PLAN EXAMPLE SPECIES

Trees: Swamp White Oak



Shrubs: Gray Dogwood






Prairie Seed Mix: Gray-Headed Coneflower

# FINAL DESIGN: LANDSCAPE PLAN BEFORE & AFTER: UPPER SITE





# FINAL DESIGN: LANDSCAPE PLAN BEFORE & AFTER: LOWER SITE





#### PROJECT SCHEDULE

- Preliminary Design: Completed September 2022
- Final Design: September 2022 to March 2023
- Bidding & Construction Contract Award: April 2023 to June 2023
- Construction: July 2023 to July 2025 (two-year construction duration due to supply chain issues for specialized equipment)

#### STAY INFORMED — STAY UPDATED

**Project Website**: <u>cityofmadison.com/water/projects/well-19-iron-manganese-radium-</u> treatment

- Latest news
- Subscribe to receive project updates





Instagram



**Twitter** 

#### **Contacts:**

- Project Manager Kelly Miess, <a href="mailto:kmiess@madisonwater.org">kmiess@madisonwater.org</a>
- General inquires <u>water@madisonwater.org</u>, (608) 266-4641

#### **Connect With Us**











Subscribe to Water Utility Email Lists

**Email** 



SUBSCRIBE



### **QUESTIONS?**



Opinions?



Concerns?

