


## CITY OF MADISON

## **ENGINEERING DIVISION DEPARTMENT OF PUBLIC WORKS PLAN OF PROPOSED IMPROVEMENT**

### **TRUCK SCALES PROJECT**

PROJECT NO. 11021 **CONTRACT NO. 8465** 



#### SHEET INDEX

- 1 COVER
- 2 GENERAL SITE PLAN
- 3 EXISTING SITE PLAN, DETAILS, GENERAL NOTES
- 4 GRADING & CONSTRUCTION PLANS, DETAILS
- 5 ENLARGED PLAN AND CROSS SECTION
- **6 REINFORCING PLAN AND DETAILS**
- 7 ELECTRICAL SCHEMATIC

WEST BADGER RD SITE LOCATION 1501 W BADGER RD

**PUBLIC WORKS IMPROVEMENT PROJECT** 

APPROVED BY THE **COMMON COUNCIL OF** MADISON WISCONSIN

19-00208 FILE ID: 54826

DATE: MARCH 25, 2019

PUBLIC WORKS IMPROVEMENT DESIGN

APPROVED BY

CITY ENGINEER



2. THE CONCRETE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL SITE PREPARATION EXCEPT WHERE NOTED AS BY OTHERS, ALL EXCAVATIONS, MATERIAL DISPOSAL, INSTALLATION OF ALL BASE MATERIALS, INSTALLATION OF ALL CONCRETE AND RE-BAR, GENERAL SITE CLEANUP; AND OTHER MISCELLANEOUS WORK ASSOCIATED WITH COMPLETING THE INTENT OF THIS CONTRACT.

THE CONCRETE CONTRACTOR SHALL FIELD LOCATE AND EXPOSE EXISTING STORM LEADERS DURING PROJECT LAYOUT. ADJUST LAYOUT TO THE NORTH IF NEEDED SO STORM PIPING IS LOCATED UNDER OFF APPROACH AND RAMP AS DEPICTED IN DETAIL 3 ON THIS SHEET. EXPOSING PIPE IS INCIDENTAL TO EXCAVATION.

4. THE CONCRETE CONTRACTOR SHALL USE CAUTION WHEN EXCAVATING AROUND THE EXISTING STORM SEWER PIPING FOR THE EXISTING ROOF DRAINS, THE CONCRETE CONTRACTOR IS RESPONSIBLE FOR VERIFYING ALL CONDITIONS IN THE FIELD WITH PLANS AND DETAILS. NOTITY THE CITY PROJECT MANAGER OF DIFFERING CONDITIONS AFFECTING DETAILS PRIOR TO BEGINNING ANY WORK.

5. THE CONCRETE CONTRACTOR SHALL REMOVE AND STOCKPILE EXISTING SELECT FILL MATERIALS BELOW ASPHALT FOR REUSE. 8" SILT SOCK AROUND STOCKPILES AND TARPS TO COVER THE STOCKPILE IS INCIDENTAL

6. THE CONCRETE CONTRACTOR SHALL REVIEW BID ITEM 20101 EXCAVATION CUT IN THE SPECIAL PROVISIONS FOR INFORMATION REGARDING UNDERCUT.

7. THE CONCRETE CONTRACTOR SHALL COMPACT ALL GRANULAR FILL WITH A VIBRATORY TYPE DEVICE TO 95% MAXIMUM DRY DENSITY. COMPACTION WITH A BACKHOE BUCKET SHALL NOT BE PERMITTED. THE CONCRETE CONTRACTOR SHALL NOTIFY THE CPM AT LEAST 2 DAYS BEFORE NEEDING THE MATERIALS TESTING CONTRACTOR ON SITE. THE CPM WILL COORDINATE THE COMPACTION TESTING WITH THE MATERIALS TESTING CONTRACTOR.

8. SEE REBAR SCHEDULE ON SHEET 6 FOR SPECIFICATIONS ON REINFORCING STEEL. THE CONCRETE CONTRACTOR SHALL BE RESPONSIBLE FOR DETERMINING QUANTITIES AND LENGTHS REQUIRED INCLUDING OVERLAPS.

9. THE CITY PROJECT MANAGER SHALL REVIEW ALL REBAR PLACEMENT PRIOR TO THE CONCRETE POUR, THE CONCRETE CONTRACTOR SHALL PROVIDE THE CPM WITH 2 WORKING DAY NOTICE BEFORE NEEDING REVIEW.

10. AT THE DISCRETION OF THE CONCRETE CONTRACTOR A MONOLITHIC POUR OF THE SCALE FOUNDATION SLAB, RAMPS AND APPROACHES SHALL BE ALLOWED. THE CONCRETE CONTRACTOR SHALL BE RESPONSIBLE FOR LOCATING AND INSTALLING ALL CONTROL JOINTS.


11. ALL CONCRETE SHALL BE fc = 4000 psi @ 28 DAYS STRENGTH. THE CONCRETE CONTRACTOR SHALL NOTIFY THE CPM AT LEAST 2 DAYS BEFORE NEEDING THE MATERIALS TESTING CONTRACTOR ON SITE FOR ANY CONCRETE POUR. THE CPM WILL COORDINATE THE TESTING OF EACH CONCRETE POUR.

12. THE SCALE FOUNDATION SLAB SHALL BE LEVEL IN ALL DIRECTIONS AT THE ELEVATION SPECIFIED IN THE PLANS AND DETAILS.


13. ALL CONCRETE SHALL HAVE A BROOM SWEPT FINISH,

14. THE SCALE INSTALLER SHALL BE RESPONSIBLE FOR THE DELIVERY AND INSTALLATION OF ALL SCALE EQUIPMENT AFTER THE CONTRACTOR HAS COMPLETED HIS/HER PORTION OF THE SITE PREPARATION.


15. THE CONCRETE CONTRACTOR SHALL BE RESPONSIBLE FOR SCHEDULING AND POURING THE SCALE PAN CONCRETE AFTER THE INSTALLATION OF ALL SCALE EQUIPMENT IS COMPLETED. THE CONCRETE CONTRACTOR SHALL VERIFY ALL CONCRETE AND INSTALLATION REQUIREMENTS WITH THE SCALE INSTALLER PRIOR TO ORDERING THE CONCRETE.



### **A-A/3 SECTION THRU SCALE PAN** (NOT TO SCALE)



### 1. EXISTING SITE PLAN



## **B-B/3 SECTION THRU APPROACH/RAMPS** (NOT TO SCALE)

۵ 

**SCALE:** 1" = 50"

# ENGINEERIN 846 **ADISON** ONTRA Ž 0 <u> L</u>U

DIVISION

H

Ш́

**LON** ENERAL G S M

Ш

TRE

2


G

### INLET BY CITY ENGINEERING RIM TO MATCH EXIST. ELEVATION ESTIMATED EL. 887.93 (+/-) BENCHMARK ELEVATION ASPHALT AT BUILDING CORNER EDGE OF RAMP BY CONCRETE CONTRACTOR ESTIMATED EL. 887.95 (+/-) ELEV 890.06 TOP OF APPROACH BY CONCRETE CONTRACTOR NEW ASPHALT SPOT EL 888.40 BY OWNER -- ELEV 888.50 TOP OF SCALE FDN. SLAB BY CONCRETE CONTRACTOR ELEV 888.50 TOP OF ANTENNA PAD BY CONCRETE CONTRACTOR EI = 88 **ELEV 890.06 TOP OF APPROACH** BY CONCRETE CONTRACTOR INLET BY CITY ENGINEERING RIM EL. 888.20 NEW ASPHALT SPOT EL 888.40 BY OWNER - NEW ASPHALT SHOULDER. ELEV 888.40 AT SCALE FDN AND BOTH APPROACHES PITHC TO EXIST, ASPHALT, ELEV 888,50 TOP OF RD PAD BY CONCRETE CONTRACTOR EDGE OF RAMP BY CONCRETE CONTRACTOR ESTIMATED EL. 888.31 (+/-) EI = 887.0 INLET BY CITY ENGINEERING RIM TO MATCH EXIST, ELEVATION ESTIMATED EL. 888.28 (+/-)


### 1. NEW GRADING PLAN

### OFF APPROACH AND RAMP, SEE SHEETS 3-5 FOR TYPICAL DETAILS SCALE PAN ASSEMBLY AND PAN SLAB ROOF DRAINAGE STORM SEWER, TYP. SCALE FOUNDATION SLAB EL. = 888.50 CONCRETE CONTRACTOR SHALL PROVIDE DEEPER GRADE BEAMS AS SHOWN WHEREVER STORM PIPING CROSSES THROUGH FOUNDATIONS SCALE FOUNDATION SLAB, SEE SHEETS 3-5 FOR TYPCIAL DETAILS

**B-B/4 STORM PIPE CROSSING DETAIL** (NOT TO SCALE)




### 2. CONSTRUCTION PLAN




C/4 TYPICAL DETAIL







NOTE: ANTENNA SIDE IS "STREET SIDE" FOR ALL LOCATIONS

### **TYPICAL PLAN VIEW - FOUNDATION SLAB AND VEHICLE APPROACHES**









REBAR SCHEDULE			
ID NO.	SIZE	SPACING	REMARKS
A	# 5	@ 12" O.C.	NOTE 5
В	# 5	@ 12" O.C.	NOTE 5
С	# 5	@ 12" O.C.	NOTE 5
D	# 5	@ 12" O.C.	NOTE 5
E	# 5	@ 6" O.C.	NOTE 6 & 7
F	# 5	@ 6" O.C.	NOTE 6 & 8
G	# 5	@ 12" O.C.	NOTE 5
н	# 5	@ 12" O.C.	NOTE 5
I	# 5	@ 12" O.C.	NOTE 5
J	# 5	@ 12" O.C.	NOTE 5
К	# 5	@ 6" O.C.	EACH WAY

- 1. REINFORCING STEEL SHALL BE DEFORMED BARS MEETING ASTM A615 GRADE 60.
- 2. CONTRACTOR SHALL BE RESPONSIBLE FOR DETERMINING QUANTITYAND LENGTHS OF REBAR REQUIRED FOR A COMPLETE INSTALLATION.
- 3. CONTRACTOR SHALL LAP REBARS A MINIMUM OF 40 BAR DIAMETERS.
- 4. ALL REBAR SHALL BE TIED PRIOR TO CONCRETE PLACEMENT.
- 5. MINIMUM COVER ON REBAR SHALL BE 2" UNLESS NOTED OTHERWISE.
- 6. CENTER BAR SPACING ON LOAD CELL CENTERLINE.
- 7. MINIMUM COVER ON REBAR SHALL BE 6".
- 8. MINIMUM COVER ON REBAR SHALL BE 6-5/8".





**GENERAL ELECTRICAL NOTES:** 

- 1. THIS SHEET IS SCHEMATICALLY DRAWN FOR INFORMATIONAL PURPOSES ONLY. E.C. IS RESPONSIBLE FOR FINAL INSTALLATION.
- 2. E.C. AND C.C. TO COORDINATE ALL WORK FOR BURIED ELECTRICAL WORK UNDER CONCRETE WORK.
- 3. ALL ELECTRICAL CONDUIT SHALL BE BURIED A MINIMUM OF 6" BELOW THE BOTTOM OF CONCRETE FOOTINGS. PROVIDE ELECTRICAL CAUTION TAPE NEAR THE TOP OF TRENCH BACKFILL AT LEAST 4" ABOVE THE CONDUIT.
- 4. ALL ELECTRICAL CONDUIT SHALL BE A MINIMUM OF 1" DIAMETER.
- 5. THE E.C. SHALL PROVIDE AND INSTALL ALL CONDUIT, BOXES, OUTLETS, COVERS, BREAKERS, WIRE PULLS, AND OTHER RELATED MATERIALS NECESSARY FOR A CODE COMPLIANT INSTALLATION DEPICTED IN THIS SCHEMATIC UNLESS NOTED AS FURNISHED AND INSTALLED BY THE S.I.
- 6. THE E.C. SHALL VERIFY ALL OUTLET AND CONNECTION LOCATIONS AND OTHER RELATED INSTALLATION REQUIREMENTS WITH THE S.I. PRIOR TO BEGINNING ANY ROUGH-IN.
- 7. SEE SPECIFIC NOTES IN THE SCHEMATIC PLAN FOR CONNECTION RESPONSIBILITIES.
- 8. THE E.C. SHALL BE RESPONSIBLE FOR VERIFYING THAT ALL MATERIALS FURNISHED BY THE S.I. TO BE INSTALLED BY THE E.C. ARE COMPLETE, NEW, AND IN SERVICEABLE CONDITION PRIOR TO INSTALLATION.
- 9. THE S.I. SHALL FURNISH, INSTALL, AND CONNECT THE SCALE PAN JUNCTION BOX, REMOTE DISPLAYS, ANTENNA, AND ALL EQUIPMENT INSIDE THE PC ENCLOSURE. THIS SHALL INCLUDE ALL EQUIPMENT WIRING BETWEEN LOAD SENSORS AND OTHER MISCELLANEOUS EQUIPMENT WIRING NOT SPECIFIED AS BEING INSTALLED BY THE E.C.
- 10. THE E.C. SHALL BE RESPONSIBLE FOR DRILLING ALL HOLES THROUGH BUILDING MATERIALS AS NEEDED TO COMPLETE THE ELECTRICAL INSTALLATION DEPICTED IN THE PLAN. ALL HOLES SHALL BE SEALED AND WATER PROOF AFTER CONDUIT HAS BEEN INSTALLED. SCRIM AND INSULATION SHALL BE REPLACED AND SEALED WITH SCRIM TAPE AS NEEDED. ALL HOLES AND PATCH WORK SHALL HAVE A NEAT APPEARANCE WHEN COMPLETED.
- 11. SIGNAL BOOSTER PROVIDED AND INSTALLED IN THE PC ENCLOSURE BY THE S.I. IF REQUIRED FOR BOOSTING DATA SIGNAL.

- 1 )110 V, 20 AMP w/ GFCI, W.P. OUTLET BY E.C.
- 2 JUNCTION BOX AND CONNECTIONS BY E.C.
- PC: PROVIDED BY S.I.; CONDUIT & INSTALL BY E.C.; EQUIPMENT CONNECTIONS BY S.I..
- HOME RUN CABLE: PROVIDED BY S.I.; CONDUIT & INSTALL BY E.C.; EQUIPMENT CONNECTIONS BY S.I.
- 5 ANTENNA CABLE: PROVIDED BY S.I.; CONDUIT & INSTALL BY E.C.; EQUIPMENT CONNECTIONS BY S.I.
- 6 ANTENNA POWER CABLE: PROVIDED BY S.I.; CONDUIT & INSTALL BY E.C.; EQUIPMENT CONNECTIONS BY S.I.
- 7 ANTENNA: PROVIDED, INSTALLED, CONNECTIONS BY S.I.; CONDUIT & INSTALL BY E.C.
- 8 A/C POWER: CONDUIT, WIRING, INSTALL & CONNECTIONS BY E.C. COORDINATE LOCATION WITH S.I.
- 9 COMMUNICATION WIRE: 22 GA., 2 PAIR; PROVIDED BY S.I.; CONDUIT & INSTALL BY E.C.; EQUIPMENT CONNECTIONS BY S.I.
- 10 E.C. TO PROVIDE AND INSTALL LARGE RADIUS SWEEPS ON ALL HORIZONTAL AND VERTICAL CONDUIT BENDS
- (11) E.C. TO STUB CONDUIT TO 12" ABOVE CONCRETE SLAB
- 12 REMOTE DISPLAY: PROVIDED, INSTALLED, CONNECTIONS BY S.I.; CONDUIT & INSTALL BY E.C.
- 13 110 V, 20 AMP w/ GFCI, W.P. OUTLET BY E.C.; MOUNT OUTLET TO POLE, COORDINATE LOCATION WITH S.I.
- 14 DEDICATED 110V 20A SERVICE: CONDUIT & WIRE PROVIDED, INSTALLED, CONNECTED BY E.C.
- 15 NETWORK CABLE: CONDUIT AND CABLE PROVIDED & INSTALLED BY E.C.