



Department of Public Works
Engineering Division
Robert F. Phillips, P.E., City Engineer
City-County Building, Room 115
210 Martin Luther King, Jr. Boulevard
Madison, Wisconsin 53703
Phone: (608) 266-4751
Fax: (608) 264-9275
engineering@cityofmadison.com
www.cityofmadison.com/engineering

Deputy City Engineer
Gregory T. Fries, P.E.

Deputy Division Manager
Kathleen M. Cryan

Principal Engineer 2
John S. Fahrney, P.E.
Christopher J. Petykowski, P.E.
Janet Schmidt, P.E.

Principal Engineer 1
Christina M. Bachmann, P.E.
Mark D. Moder, P.E.
James M. Wolfe, P.E.

Facilities & Sustainability
Bryan Cooper, Principal Architect

Mapping Section Manager
Eric T. Pederson, P.S.

Financial Manager
Steven B. Danner-Rivers

March 22, 2021

NOTICE OF ADDENDUM

ADDENDUM 1

Lakeview Library Lighting Upgrade

CONTRACT NO. 8599

Revise and amend the contract document(s) for the above project as stated in this addendum, otherwise, the original document shall remain in effect.

Please acknowledge this addendum on page E1 of the contract documents and/or in Section E: Bidder's Acknowledgement on Bid Express.

Electronic version of these documents can be found on the Bid Express web site at:
<http://www.bidexpress.com>

If you are unable to download plan revisions associated with the addendum, please contact the Engineering office at 608-266-4751 receive the material by another route.

- 1 Replace sheet EL 200 with a new sheet EL 200
 - A Keynote 3 was added to clarify that all wall- or shelf-mounted light fixtures should be removed and the boxes be covered with a cover matching the wall. Demolition plans may not show every single fixture.
- 2 Replace sheet EL 210 with new sheet EL 210
 - A Keynote 7 was edited to allow conduit installation on top of the short wall. This relates to below question about said keynote.
- 3 Reply to Questions:
 - A Question: "Does the contractor need to remove fixtures that are not shown?"
 - a Answer: All existing light fixtures and controls shall be removed. Demolition plans are schematic and show most, but not necessarily all, devices to be removed. Visible boxes shall be covered with a cover matching the surrounding wall cover.
 - B Question: "Note 7 on Sheet EL 210 requires conduit shall be installed inside the short wall. This may not be feasible due to stud elements. Can we install conduit on top of the wall?"
 - a Answer: Conduit can be installed on top of that short wall. Keep conduit in the center of the wall and as low as possible for reduced visibility. Use white conduit and attachments.

Sincerely,

Eng - Christy Bachmann

Robert F. Phillips, P.E.
City Engineer

RFP: ks

