



Department of Public Works
Engineering Division
Kathy Cryan, Interim Engineering Manager

City-County Building, Room 115
210 Martin Luther King, Jr. Boulevard
Madison, Wisconsin 53703
Phone: (608) 266-4751
Fax: (608) 264-9275
engineering@cityofmadison.com
www.cityofmadison.com/engineering

Deputy City Engineer
Gregory T. Fries, P.E.

Principal Architect 2
Bryan Cooper, AIA

Principal Engineer 2
John S. Fahrney, P.E.
Chris Petykowski, P.E.
Janet Schmidt, P.E.

Principal Engineer 1
Christina M. Bachmann, P.E.
Mark D. Moder, P.E.
James M. Wolfe, P.E.

Financial Manager
Steven B. Danner-Rivers

June 3, 2022

**NOTICE OF ADDENDUM
ADDENDUM NO. 1**

**CONTRACT NO. 8605, PROJECT NO. 44001
West Badger Road Salt Barn**

This addendum is issued to modify, explain or correct the original Drawings, Specifications, or Contract Documents marked as *West Badger Road Salt Barn, City of Madison Project 44001, Contract #8605, as issued on April 28, 2022* and is hereby made a part of the contract documents. This addendum consists of two (2) pages and the referenced exhibit. This addendum represents clarifications of the original documents and a minor change in the demolition scope only, therefore no extension to the bid due date will be considered.

Please acknowledge this addendum on page E1 of the contract documents and/or in Section E: Bidder's Acknowledgement on Bid Express.

An electronic version of these documents can be found on the Bid Express web site at:
<http://www.bidexpress.com>

If you are unable to download plan revisions associated with the addendum, please contact the Engineering office at 608-266-4751 receive the material by another route.

For questions regarding this bid, contact:

Randy Wiesner
City of Madison Engineering
Phone: 608-267-8679
Fax: 608-264-9275
Email: RWiesner@cityofmadison.com

Sincerely,

Chris Petykowski for:
Kathy Cryan, Interim Engineering Manager

Cc: Greg Fries



1. **GENERAL CONTRACT CONDITIONS**

There are no changes to the general contract conditions.

2. **GENERAL QUESTIONS/ANSWERS and CLARIFICATIONS**

Q1. Can we bring a portable crusher on site for demolition of concrete?

A1. Yes. A portable crusher may be brought on site for crushing concrete. If concrete is to be crushed the City will require the following:

- Any/all metal be removed from the crushed material.
- Crushed concrete shall be crushed to 100% passing a 1" sieve and 75% passing a 3/4" sieve.
- Crushed concrete shall be repurposed on site as foundation fill material and as bid item 40102 Crushed Aggregate Base Course Gradation No. 2 BEFORE any bid item 40102 can be brought on site.

3. **ACCEPTABLE EQUIVALENTS**

No requests for alternates have been received therefore no alternates will be reviewed during the construction process.

4. **SPECIFICATIONS**

There were no changes to any of the written specifications in Exhibit B.

5. **DRAWINGS**

A. The following changes were made to the Exhibit A Plan set. These corrected sheets will be published as Exhibit E.

- i. Sheet 1; demolition and removal of 2 area light poles as follows:
 - Remove (2) existing security cameras and mounts, retain for reinstallation.
 - Remove (3) existing area lights and provide to Owner.
 - Remove and recycle (2) galvanized area light poles and (3) arms in their entirety.
 - Reuse existing conduit as much as possible
- ii. Sheet 2; reinstall (2) salvaged PTZ cameras.
 - Reinstall both cameras under the northwest corner roof overhang.
 - One camera to point northerly to cover the Cold Storage building.
 - One camera to point southwesterly at the truck scale and Emil St. vehicle gate.
 - Reuse existing mounting brackets.
 - Install new data cable and conduit as per plan.
- iii. Sheet 7; Install new conduit and data cables as needed
 - Connect new conduit to existing conduit underground
 - Install new conduit up inside NW corner of new building to roof overhang.
 - Install new data cables (estimated (2) at 300' each) from original source to cameras

6. **PROPOSAL**

There were no changes made to the proposal sheet. The above mentioned drawing changes shall be included with bid item 90000-Demolition of Existing Buildings.

Note: a copy of the contractors attending the pre-bid conference is also attached in Exhibit E.

End of Contract 8605 Addendum 1.