



Madison Parks Division

210 Martin Luther King, Jr. Blvd., Room 104
PO Box 2987
Madison, WI 53701-2987
608-266-4711 • cityofmadison.com/parks



June 1, 2021

NOTICE OF ADDENDUM ADDENDUM NO. 1

CONTRACT NO. 9039

Revise and amend the contract document(s) for the above project as stated in this addendum, otherwise, the original document shall remain in effect.

Revise Plans:

- Sheet 1- Title – Add Sheet 6.3 to page numbering
- Add Sheet 6.3- Orchard Ridge Bio Retention
- Revise Sheet 6.1- Orchard Ride Site Access and Erosion Control
- Revise Sheet 6.2 – Orchard Ridge Grading

Revise Proposal Page Under Orchard Ridge Park

ACCOUNT NO. 13455-51-130

Revise the following quantity:

21049	INLET PROTECTION, RIGID FRAME - PROVIDE AND INSTALL	REVISE
21050	INLET PROTECTION, RIGID FRAME - MAINTAIN	REVISE
21051	INLET PROTECTION, RIGID FRAME - REMOVE	REVISE

Add the following items:

20130	UNDERDRAIN
20331	ABANDON SEWER ACCESS STRUCTURE
20336	PIPE PLUG
50211	SELECT BACKFILL FOR STORM SEWER
50443	12 INCH TYPE III STORM SEWER PIPE
50455	12" STORM SEWER BEND- 22.5 DEG

50741	TYPE "H" INLET
50792	STORM SEWER TAP

Revise Special Provisions as follows:

Under **SECTION 107.13:** **TREE PROTECTION SPECIFICATIONS**

Add the following:

Wingra Park:

There exist several trees where less than 14 feet of clearance exists below limbs. It is expected that smaller machinery will need to be utilized here to avoid damage to limbs. Asphalt paving may require loading the paver with equipment smaller than a truck.

Revise Item 90005 as follows:

BID ITEM 90005 – BIO RETENTION BASIN

DESCRIPTION

Work under this item shall include all work, materials, labor and incidentals necessary for the Contractor to provide, construct and install the bio retention basins outlined in the plans and detail drawings.

Planting and mulching shall occur in 2022 by others. All materials including engineered fill, clear stone, rip rap, fabric and other items shown on S.D.D. 2.09 and in the plans shall be included with this bid item. These quantities are not included in the calculations for the contract under individual bid items.

There is an existing storm sewer structure and water main near the bio retention basin. These utilities are no longer in use and shall be abandoned as part of this project. The 2” water line on site is currently capped in the sewer access structure. If the Contractor choses to cut this line for construction it shall be capped at the new cut location. Water main work and coordination shall be included in this item.

METHOD OF MEASUREMENT

Bio Retention Basin system shall be measure as each bio retention basin and included items constructed and accepted in the field.

BASIS OF PAYMENT

Bio Retention Basin shall be measured as described above and shall be paid for at the contract unit price which shall be full compensation for all work, materials, tools, equipment, labor, placement, disposal and incidentals required to complete the work as set forth in the description.

Please acknowledge this addendum on page E1 of the contract documents and/or in Section E: Bidder's Acknowledgement on Bid Express.

Electronic version of these documents can be found on the Bid Express web site at:

<http://www.bidexpress.com>

If you are unable to download plan revisions associated with the addendum, please contact the Engineering office at 608-266-4751 receive the material by another route.



Eric Knepp, Parks Superintendent