



Department of Public Works
Engineering Division
James M. Wolfe, P.E., City Engineer
City-County Building, Room 115
210 Martin Luther King, Jr. Boulevard
Madison, Wisconsin 53703
Phone: (608) 266-4751
Fax: (608) 264-9275
engineering@cityofmadison.com
www.cityofmadison.com/engineering

Assistant City Engineer
Bryan Cooper, AIA
Gregory T. Fries, P.E.
Chris Petykowski, P.E.
Deputy Division Manager
Kathleen M. Cryan
Principal Engineer 2
John S. Fahrney, P.E.
Janet Schmidt, P.E.
Principal Engineer 1
Mark D. Moder, P.E.
Financial Manager
Steven B. Danner-Rivers

March 3, 2023

NOTICE OF ADDENDUM
ADDENDUM NO. 1
CONTRACT NO. 9286

CIPP UV LINING REHABILITATION OF
SANITARY SEWERS EAST PHASE 1 - 2023

Revise and amend the contract document(s) for the above project as stated in this addendum, otherwise, the original document shall remain in effect.

SPECIFICATIONS:

SECTION D: SPECIAL PROVISIONS

SECTION 102.1 PRE-QUALIFICATION OF BIDDERS

The minimum qualifications section of 'CATEGORY #399 UV SEWER LINING' shall be updated as follows:

"The Contractor performing the work shall submit documentation demonstrating that they clearly meet the minimum qualifications as stated below:

- Contractor, **or the Contractor Subcontractor**, must show that they have a minimum of 30,000 linear feet of UV cured CIPP sewer lining successfully installed using the same UV CIPP lining system that will be used for this contract. The 30,000 linear feet shall be installed in sanitary sewer gravity mains of various sizes only, any UV CIPP installed in water main shall not apply.
- Contractor, **or the Contractor Subcontractor**, must show that the Contractor project supervisor or foreperson that will be overseeing the installation crew must have a minimum of 20,000 linear feet of UV cured CIPP sewer lining successfully installed using the same UV CIPP lining system that will be used for this contract. The 20,000 linear feet shall be installed in sanitary sewer gravity mains of various sizes only, any UV CIPP installed in water main shall not apply."

The remainder of the text within this section shall remain the same as the original contract.

SECTION 509.7(a) INSPECTION AND TESTING

Grouting of service connections will not be required under this contract. This section shall be updated as follows:

"CCTV Inspection and Acceptance - The Contractor shall perform a detailed closed-circuit television

inspection in accordance with NAASCO's Pipeline Assessment and Certification Program (PACP) standards, after installation of the CIPP liner and reconnection of the service connections."

The remainder of the text within this section shall remain the same as the original contract.


Please acknowledge this addendum on page E1 of the contract documents and/or in Section E: Bidder's Acknowledgement on Bid Express.

Electronic version of these documents can be found on the Bid Express web site at:

<http://www.bidexpress.com>

If you are unable to download plan revisions associated with the addendum, please contact the Engineering office at 608-266-4751 receive the material by another route.

Sincerely,



For

James M. Wolfe, P.E., City Engineer
City Engineer