



Department of Public Works
City Engineering Division

Robert F. Phillips, P.E.
City Engineer

City-County Building, Room 115
210 Martin Luther King, Jr. Boulevard
Madison, Wisconsin 53703
FAX 608 264 9275
www.cityofmadison.com

608 266 4751

Assistant City Engineer
Michael R. Dailey, P.E.

Principal Engineers
Christina M. Bachmann, P.E.
John S. Fahrney, P.E.
Gregory T. Fries, P.E.
Christopher J. Petykowski, P.E.

Facilities & Sustainability
Jeanne E. Hoffman, Manager
James C. Whitney, A.I.A.

Operations Supervisor
Kathleen M. Cryan

GIS Manager
David A. Davis, R.L.S.

Financial Officer
Steven B. Danner-Rivers

Hydrogeologist
Brynn Bemis

NOTICE OF ADDENDUM

**MANITOU WAY RESURFACING ASSESSMENT
DISTRICT-2012**

ADDENDUM NO. 1

CONTRACT NO. 6791

PROPOSAL:

REMOVE

Proposal pages E-5 thru E-8

INSERT

Proposal pages E-5 thru E-8 (revised May 18, 2012)

The quantities in the printed version of the proposal, in the contract document, did not match the electronic version posted on the City's website.

Revise and amend the contract document(s) for the above project as stated in this addendum, otherwise, the original document shall remain in effect.

Please acknowledge this addendum on page E1 of the contract documents.

Electronic version of these documents can be found on the City of Madison web site at:

<http://www.cityofmadison.com/business/PW/contracts/openforBid.cfm>

If you are unable to download plan revisions associated with the addendum, please contact the Engineering office at 608-266-4751 receive the material by another route.

Robert F. Phillips, P.E., City Engineer

PROPOSAL

NAME OF BIDDER

MANITOU WAY RESURFACING ASSESSMENT DISTRICT-2012

Rev 5/18/12

Contract No. 6791

ITEM	TYPE OF WORK	ESTIMATED QUANTITIES		UNIT PRICE BID	TOTAL BID
ACCOUNT NO. CS53-58260-810358-00-53W1341					
10701	TRAFFIC CONTROL	1.0	LS		\$ -
10801	ROOT CUTTING-CURB AND GUTTER	30.0	LF		\$ -
10802	ROOT CUTTING-SIDEWALK	15.0	LF		\$ -
10911	MOBILIZATION	1.0	LS		\$ -
20101	EXCAVATION CUT	400.0	CY		\$ -
20219	BREAKER RUN	872.0	TON		\$ -
20221	TOPSOIL	739.0	SY		\$ -
20321	REMOVE CONCRETE PAVEMENT	2140.0	SY		\$ -
20322	REMOVE CONCRETE CURB & GUTTER	1548.0	LF		\$ -
20323	REMOVE CONCRETE SIDEWALK & DRIVE	1703.0	SF		\$ -
20701	TERRACE SEEDING	739.0	SY		\$ -
30201	TYPE "A" CONCRETE CURB & GUTTER	1548.0	LF		\$ -
30301	5 INCH CONCRETE SIDEWALK	1213.0	SF		\$ -
30302	7 INCH CONCRETE SIDEWALK & DRIVE	955.0	SF		\$ -
30340	CURB RAMP DETECTABLE WARNING FIELD	40.0	SF		\$ -
40102	CRUSHED AGGREGATE BASE COURSE, GRADATION 2	100.0	TON		\$ -
40202	HMA PAVEMENT, TYPE E-1	585.0	TON		\$ -
40211	TACK COAT	333.0	GAL		\$ -
40231	ASPHALT DRIVE & TERRACE	20.0	SY		\$ -
40251	ASPHALT MATERIAL FOR CURB FRONT FILL	1548.0	LF		\$ -
40311	PULVERIZE & SHAPE	4860.0	SY		\$ -

MANITOU WAY RESURFACING ASSESSMENT DISTRICT-2012

Rev 5/18/12

Contract No. 6791

ITEM	TYPE OF WORK	ESTIMATED QUANTITIES		UNIT PRICE BID	TOTAL BID
40410	CONCRETE SPEED HUMP	70.0	SY		\$ -
ACCOUNT NO. CS53-58270-810358-00-53W1341					
20217	CLEAR STONE (UNDISTRIBUTED)	2.0	TON		\$ -
21001	EROSION CONTROL PLAN & IMPLEMENTATION	1.0	LUMP SUM		\$ -
21002	EROSION CONTROL INSPECTION	4.0	EACH		\$ -
21013	STREET SWEEPING	1.0	LUMP SUM		\$ -
21017	SILT SOCK (8 INCH) COMPLETE	700.0	L.F.		\$ -
21046	INLET PROTECTION, TYPE D MODIFIED - PROVIDE & INSTALL	12.0	EACH		\$ -
21047	INLET PROTECTION, TYPE D MODIFIED - MAINTAIN	36.0	EACH		\$ -
21048	INLET PROTECTION, TYPE D MODIFIED-REMOVE	12.0	EACH		\$ -
21052	POLYMER STABILIZATION	1000.0	SY		\$ -
90030	SITE TRACKING CONTROL	1.0	LUMP SUM		\$ -
90031	STORM CONTROL PLAN AND IMPLEMENTATION	1.0	LUMP SUM		\$ -
90032	STONE BERM FOR EROSION CONTROL	2.0	EACH		\$ -
ACCOUNT NO. ESTM-58270-810381-00-53W1341					
10702	TRAFFIC CONTROL FOR STORM SEWER INSTALLATION	1.0	LUMP SUM		\$ -
10912	MOBILIZATION FOR STORM SEWER INSTALLATION	1.0	LUMP SUM		\$ -
20312	REMOVE CATCHBASIN	2.0	EACH		\$ -
20711	TRENCH RESTORATION	597.0	T.F.		\$ -
21061	EROSION MATTING, CLASS I, URBAN TYPE A (ORGANIC)	939.0	S.Y.		\$ -
50211	SELECT BACKFILL FOR STORM SEWER	591.0	T.F.		\$ -
50225	UTILITY TRENCH PATCH TYPE III	480.0	T.F.		\$ -
50435	34 INCH X 53 INCH HERCP STORM SEWER PIPE	591.0	L.F.		\$ -

MANITOU WAY RESURFACING ASSESSMENT DISTRICT-2012

Rev 5/18/12

Contract No. 6791

ITEM	TYPE OF WORK	ESTIMATED QUANTITIES		UNIT PRICE BID	TOTAL BID
50485	34 INCH X 53 INCH HERCP AE	1.0	EACH	\$	-
50625	34 INCH X 53 INCH HERCP AE GATE	1.0	EACH	\$	-
50801	UTILITY LINE OPENING (ULO)	5.0	EACH	\$	-
90033	6' x 7' CAST IN PLACE SAS	3.0	EACH	\$	-
90034	APRON ENDWALL INSTALLATION	1.0	EACH	\$	-
90035	24" STONE	2.0	C.Y.	\$	-
90036	CMP ABANDONMENT	390.0	L.F.	\$	-
90037	REMOVE AND REPLACE TERRACE FLUME	1.0	EACH	\$	-
90038	FENCE -SAFETY	150.0	L.F.	\$	-

ACCOUNT NO. ES01-58275-810332-00-53W1341

10704	TRAFFIC CONTROL FOR SANITARY SEWER INSTALLATION	1.0	LUMP SUM	\$	-
10914	MOBILIZATION FOR SANITARY SEWER INSTALLATION	1.0	LUMP SUM	\$	-
20335	ABANDON SEWER PIPE WITH SLURRY	6.0	C.Y.	\$	-
20336	PIPE PLUG	30.0	EACH	\$	-
20311	REMOVE SEWER ACCESS STRUCTURE	1.0	EACH	\$	-
20331	ABANDON SEWER ACCESS STRUCTURE	6.0	EACH	\$	-
50103	RECONSTRUCT BENCH AND FLOWLINES	3.0	EACH	\$	-
50212	SELECT BACKFILL FOR SANITARY SEWER	1095.0	T.F.	\$	-
50225	UTILITY TRENCH PATCH TYPE III	1200.0	T.F.	\$	-
50301	8 INCH PVC SANITARY SEWER PIPE	1095.0	L.F.	\$	-
50353	SANITARY SEWER LATERAL	292.0	L.F.	\$	-
50354	RECONNECT	13.0	EACH	\$	-
50361	WASTEWATER CONTROL	1.0	LUMP SUM	\$	-

MANITOU WAY RESURFACING ASSESSMENT DISTRICT-2012

Rev 5/18/12

Contract No. 6791

ITEM	TYPE OF WORK	ESTIMATED QUANTITIES		UNIT PRICE BID	TOTAL BID
50390	SEWER ELECTRONIC MARKERS	30.0	EACH		\$ -
50701	4' DIA. SANITARY SAS	7.0	EACH		\$ -
50780	CLEANOUT	4.0	EACH		\$ -
GRAND TOTAL					