






# WARNER PARK PARKING LOT RE-DESIGN PHASE 3

## DEMOLITION PLAN

-  AREA TO BE PULVERIZED AS A PART OF PHASE 3
-  TREES/SHRUBS TO BE REMOVED
-  EXISTING CURB BLOCK TO BE REMOVED
-  EXISTING GRASS AREAS TO BE EXCAVATED AND FILLED WITH BASE COURSE-12" BEHIND BACK OF PROPOSED CURB
-  EXISTING BASE COURSE AREAS TO BE EXCAVATED AND FILLED WITH TOPSOIL

