



Department of Public Works  
**City Engineering Division**

Robert F. Phillips, P.E.  
**City Engineer**

City-County Building, Room 115  
210 Martin Luther King, Jr. Boulevard  
Madison, Wisconsin 53703  
FAX 608 264 9275  
www.cityofmadison.com

**608 266 4751**

**Assistant City Engineer**  
Michael R. Dailey, P.E.

**Principal Engineers**  
Christina M. Bachmann, P.E.  
John S. Fahrney, P.E.  
Gregory T. Fries, P.E.  
Christopher J. Petykowski, P.E.

**Facilities & Sustainability**  
Jeanne E. Hoffman, Manager  
James C. Whitney, A.I.A.

**Operations Supervisor**  
Kathleen M. Cryan

**GIS Manager**  
David A. Davis, R.L.S.

**Financial Officer**  
Steven B. Danner-Rivers

**Hydrogeologist**  
Brynn Bemis

**NOTICE OF ADDENDUM**

**CHEROKEE MARSH STORMWATER MANAGEMENT PONDS**

**ADDENDUM NO. 1**

**CONTRACT NO. 6900**

**REMOVE**

Specifications page A-1

**INSERT**

Specifications page A-1

SBE GOAL= 16%

**REMOVE**

Proposal pages E-5 thru E-7

**INSERT**

Proposal pages E-5 thru E-7

Additional Bid Items (50411,50413)

Revise and amend the contract document(s) for the above project as stated in this addendum, otherwise, the original document shall remain in effect.

Please acknowledge this addendum on page E1 of the contract documents.

Electronic version of these documents can be found on the City of Madison web site at:

<http://www.cityofmadison.com/business/PW/contracts/openforBid.cfm>

If you are unable to download plan revisions associated with the addendum, please contact the Engineering office at 608-266-4751 receive the material by another route.

Robert F. Phillips, P.E., City Engineer

PROPOSAL

REVISED 7/11/12

NAME OF BIDDER

**CHEROKEE MARSH STORMWATER MANAGEMENT PONDS**

**Contract Number: 6900**

ITEM	TYPE OF WORK	ESTIMATED QUANTITIES		UNIT PRICE BID	TOTAL BID
ACCOUNT NO. ESTM-58270-810384-00-53W1101					
10701	TRAFFIC CONTROL	1.00	LS		\$ -
10911	MOBILIZATION	2.00	EA		\$ -
20101	EXCAVATION CUT	109,788.00	CY		\$ -
20202	FILL	8,918.00	CY		\$ -
20218	CLEAR STONE	260.00	TON		\$ -
20221	4" TOPSOIL REDISTRIBUTION	26,000.00	SY		\$ -
20232	EXTRA HEAVY RIPRAP	125.00	TON		\$ -
20233	HEAVY RIPRAP FILTER FABRIC	250.00	SY		\$ -
20313	REMOVE INLET	3.00	EA		\$ -
20314	REMOVE PIPE	57.00	LF		\$ -
20315	REMOVE EX BOX CULVERT	40.00	LF		\$ -
20315	REMOVE EX BOX CULVERT WINGWALLS	1.00	LS		\$ -
20322	REMOVE CONCRETE CURB & GUTTER	80.00	EA		\$ -
20706	MIXED PRAIRIE SEEDING	17,271.00	SY		\$ -
20707	DETENTION BASIN SEEDING	8,642.00	SY		\$ -
21001	EROSION CONTROL PLAN & IMPLEMENTATION	1.00	LS		\$ -
21002	EROSION CONTROL INSPECTION	17.00	EA		\$ -
21011	CONSTRUCTION ENTRANCE	2.00	EA		\$ -
21013	CLEAR STONE BERM FOR EROSION CONTROL	3.00	EA		\$ -
21013	STREET SWEEPING	1.00	LS		\$ -
21022	SILT FENCE - PROVIDE, INSTALL & MAINTAIN	5,536.00	LF		\$ -

REVISED 7/11/12

# CHEROKEE MARSH STORMWATER MANAGEMENT PONDS

Contract Number: 6900

ITEM	TYPE OF WORK	ESTIMATED QUANTITIES		UNIT PRICE BID	TOTAL BID
21023	SILT FENCE - REMOVE & RESTORE	5,536.00	LF		\$ -
21046	INLET PROTECTION, TYPE D MODIFIED - PROVIDE & INSTALL	14.00	EA		\$ -
21047	INLET PROTECTION, TYPE D MODIFIED - MAINTAIN	14.00	EA		\$ -
21048	INLET PROTECTION, TYPE D MODIFIED - REMOVE	14.00	EA		\$ -
21061	EROSION MATTING, CLASS I, URBAN TYPE A	26,000.00	SY		\$ -
30201	TYPE "A" CONCRETE CURB & GUTTER	80.00	EA		\$ -
50211	SELECT BACKFILL FOR STORM SEWER	2,614.00	TF		\$ -
50226	UTILITY TRENCH PATCH TYPE III	50.00	TF		\$ -
50411	12 INCH RCP STORM SEWER PIPE	3.00	LF		\$ -
50413	18 INCH RCP STORM SEWER PIPE	40.00	LF		\$ -
50418	36 INCH STORM SEWER PIPE	2,352.00	LF		\$ -
50420	48 INCH STORM SEWER PIPE	262.00	LF		\$ -
50451	45 DEG 36" STORM SEWER BEND	3.00	EA		\$ -
50468	36 INCH RCP AE	10.00	EA		\$ -
50470	48 INCH RCP AE	2.00	EA		\$ -
50499	CONCRETE COLLAR	12.00	EA		\$ -
50608	36 INCH RCP AE GATE	10.00	EA		\$ -
50610	48 INCH RCP AE GATE	2.00	EA		\$ -
50725	5'X5' STORM SAS	2.00	EA		\$ -
50728	12'x5' SEWER ACCESS STRUCTURE	1.00	EA		\$ -
50741	TYPE "H" INLET	2.00	EA		\$ -
50802	CONCRETE SUPPORTS	10.00	EA		\$ -
90031	SITE DEWATERING	1.00	LS		\$ -
REVISED 7/11/12 90032	HAULING & OFF SITE DISPOSAL	100,823.00	CY		\$ -

# CHEROKEE MARSH STORMWATER MANAGEMENT PONDS

Contract Number: 6900

ITEM	TYPE OF WORK	ESTIMATED QUANTITIES		UNIT PRICE BID	TOTAL BID
90033	CLEARING & GRUBBING	1.00	LS		\$ -
90034	STORM CONTROL	1.00	LS		\$ -
90035	POLYMER STABILIZATION	13,000.00	SY		\$ -
90036	POLYMER SETTLING	30.00	LB		\$ -
90038	CLAY LINING PLACEMENT	2,841.00	CY		\$ -
90039	ACCESS PATH PERMANENT	1,300.00	LF		\$ -
90040	ACCESS PATH GRADING ONLY	1,340.00	LF		\$ -
90041	IMPROVE ACCESS PATH	1,000.00	LF		\$ -
90042	CONSTRUCTION SURVEYING	1.00	LS		\$ -
90043	SHORELINE BARRIER TYPE I	2,343.00	LF		\$ -
90044	CONSTRUCTION FENCING	1,450.00	LF		\$ -
					\$ -
<b>GRAND TOTAL</b>					