



Department of Public Works
City Engineering Division

Robert F. Phillips, P.E.
City Engineer

City-County Building, Room 115
210 Martin Luther King, Jr. Boulevard
Madison, Wisconsin 53703
FAX 608 264 9275
www.cityofmadison.com

608 266 4751

Assistant City Engineer
Michael R. Dailey, P.E.

Principal Engineers
Christina M. Bachmann, P.E.
John S. Fahrney, P.E.
Gregory T. Fries, P.E.
Christopher J. Petykowski, P.E.

Facilities & Sustainability
Jeanne E. Hoffman, Manager
James C. Whitney, A.I.A.

Operations Supervisor
Kathleen M. Cryan

GIS Manager
David A. Davis, R.L.S.

Financial Officer
Steven B. Danner-Rivers

Hydrogeologist
Brynn Bemis

5/8/2013

NOTICE OF ADDENDUM
ADDENDUM NO. 1

CONTRACT NO. 7106

Revise and amend the contract document(s) for the above project as stated in this addendum, otherwise, the original document shall remain in effect.

Bid Item #1: Mobilization covers all work not included in the bid items #2 - #19 that is required of the Contractor to provide a complete and safe project. This work shall include the survey to provide layout for grades and alignment of the curbs and islands, protection of trees and shrubs, surfaces and equipment and placement of the chain link fence as indicated on sheet C-1.0. This also includes sidewalk closures, as needed, which shall be done per City of Madison standards including required barricades, signs and permits.

Bid Item #3: It is the Contractor's option to mill or pulverize the existing asphalt pavement. Saw cutting pavement as indicated on details relates to the Contractor's option to mill the surface.

Bid Items # 5, #6 and #7: These bid items relate to erosion control. The Contractor is to provide erosion control as indicated in bid items #5 (tracking mat), #6 (inlet protection) and #7 (silt sock) and as specified in Spec Section 31 25 00 and as indicated on sheet C-2.0 and detailed.

Bid Item #8: Areas that require undercutting due to unsatisfactory base shall be backfilled as specified. Cost for excavation and backfill are included in this bid item.

Bid Item #9: The electrical installation is to include a Type 1 handhole at the base of the poles to accommodate the transition from conduit placement on the existing poles to the buried conduit.

Bid Item #11: Sidewalk patching/extensions include sections of new added walk at areas identified on sheet C-1.0. No replacement of existing sidewalks is anticipated. Replacement of existing sidewalks damaged by the Contractor shall be at the Contractor's expense.

Bid Item #12: This item includes areas that will require re-grading, see sheet C-2.0. Bid item includes removal of existing sub-base, placement of crushed aggregate and compaction.

Bid Item #15. Detectable Warning Field shall be 2'-0" x 4'-0" as shown on Madison Standard detail drawing 3.04.

Detector (traffic) loops will be provided and installed by City of Madison Traffic Engineering. The Contractor is to contact Madison Parking Utility when the existing loops are to be abandoned and then coordinate installation of new loops with City staff.

Please acknowledge this addendum on page E1 of the contract documents.
Electronic version of these documents can be found on Bid Express at:
<https://www.bidexpress.com/>

If you are unable to download plan revisions associated with the addendum, please contact the Engineering office at 608-266-4751 receive the material by another route.

David C. Dryer, P.E., City Traffic Engineer