



Department of Public Works  
**Engineering Division**  
Robert F. Phillips, P.E., City Engineer  
City-County Building, Room 115  
210 Martin Luther King, Jr. Boulevard  
Madison, Wisconsin 53703  
Phone: (608) 266-4751  
Fax: (608) 264-9275  
[engineering@cityofmadison.com](mailto:engineering@cityofmadison.com)  
[www.cityofmadison.com/engineering](http://www.cityofmadison.com/engineering)

**Assistant City Engineer**  
Michael R. Dailey, P.E.

**Principal Engineers**  
Christina M. Bachmann, P.E.  
John S. Fahrney, P.E.  
Gregory T. Fries, P.E.  
Christopher J. Petykowski, P.E.

**Facilities & Sustainability**  
Jeanne E. Hoffman, Manager

**Operations Manager**  
Kathleen M. Cryan

**Mapping Section Manager**  
Eric T. Pederson, P.S.

**Financial Manager**  
Steven B. Danner-Rivers

**Hydrogeologist**  
Brynn Bemis

April 1, 2014

NOTICE OF ADDENDUM  
ADDENDUM NO. 1  
NORTH ST, HOARD ST AND COMMERCIAL AVE RECONSTRUCTION 2014  
CONTRACT NO. 7248

Revise and amend the contract document(s) for the above project as stated in this addendum, otherwise, the original document shall remain in effect.

**SECTION B: PROPOSAL PAGES**

The proposal pages have been revised. The original proposal pages have been removed and new proposals have been inserted into Bid Express.

The proposal pages have been revised to add the following item:

90073	PROTECT AT&T DUCT PACKAGE	1.00	LS
-------	---------------------------	------	----

**SECTION D: SPECIAL PROVISIONS**

Add the following item:

**BID ITEM 90073 – PROTECT AT&T DUCT PACKAGE**

**DESCRIPTION**

There is an existing underground AT&T duct package on North st running from E Washington Ave to Commercial Ave. This duct package is shown on the plan set and is labeled as “FO”. It consists of two four duct packages approx twelve inches per side. This duct package is composed of clay tile installed in the 1920’s. There are AT&T access structures along this line of similar age.

Work under this bid item includes all work, materials, equipment, time, and incidentals required to support and protect the AT&T duct package and access structures throughout construction. It is anticipated that due to the depth of the duct package and the depth of the proposed sanitary sewer, this duct package will require additional protection/support during installation of the sanitary sewer main from

April 1, 2014

Page 2

E. Johnson St to Commercial Ave.

The Contractor shall work with AT&T to determine a method of providing and removing (as needed to bring site back to finish grade and as described below) temporary support, protection, and/or shoring.

The contractor shall contact AT&T prior to starting work, review the project, and install any requested protection or support requested by AT&T. Contact information for AT&T is listed below.

Ray Chinmoy- (608) 252-2448 or [cr093f@att.com](mailto:cr093f@att.com)

Carol Anason (608) 252-2432 or [ca2624@att.com](mailto:ca2624@att.com)

### **METHOD OF MEASUREMENT**

Protect AT&T Duct Package will be measured by the Lump Sum for all support and protection installed on the project.

### **BASIS OF PAYMENT**


Protection measured as provided above, will be paid for at the contract price, which price shall be full compensation for providing the design of the protection system; for furnishing and hauling materials to each location; for installing or constructing the protection measures; for maintenance as needed; for removal when required; and for all labor, tools, equipment and incidentals needed to complete the work in accordance with the contract.

Please acknowledge this addendum on page E1 of the contract documents and/or in Section E: Bidder's Acknowledgement on Bid Express.

Electronic version of these documents can be found on the Bid Express web site at:

<http://www.bidexpress.com>

If you are unable to download plan revisions associated with the addendum, please contact the Engineering office at 608-266-4751 to receive the material by another route.



Robert F. Phillips, P.E., City Engineer