



June 18, 2014

Department of Public Works

Engineering Division

Robert F. Phillips, P.E., City Engineer

City-County Building, Room 115
210 Martin Luther King, Jr. Boulevard
Madison, Wisconsin 53703

Phone: (608) 266-4751

Fax: (608) 264-9275

engineering@cityofmadison.com

www.cityofmadison.com/engineering

Assistant City Engineer

Michael R. Dailey, P.E.

Principal Engineers

Christina M. Bachmann, P.E.

John S. Fahrney, P.E.

Gregory T. Fries, P.E.

Christopher J. Petykowski, P.E.

Facilities & Sustainability

Jeanne E. Hoffman, Manager

Operations Manager

Kathleen M. Cryan

Mapping Section Manager

Eric T. Pederson, P.S.

Financial Manager

Steven B. Danner-Rivers

Hydrogeologist

Brynn Bemis

NOTICE OF ADDENDUM 1 FIRE STATION #5 ROOF DOOR AND HOSE TOWER REPAIRS

CONTRACT NO. 7334

Revise and amend the contract document(s) for the above project as stated in this addendum, otherwise, the original document shall remain in effect.

Item 1

On page D-1, Change the first sentence in section 109.7 from:

The contractor shall begin work on or before **August 18th 14, 2014.**

To:

The contractor shall begin work on or before **August 18th, 2014.**

Item 2

Install a 2" Carlon® Split Duct (or equivalent) conduit around the antenna cables as shown on "Fire Station #5 West Elevation Addendum 1 Photo". Back fill between the antenna cable and the interior of the conduit with foam and apply sealant at the exterior end of the conduit.

Please acknowledge this addendum on page E1 of the contract documents and/or in Section E: Bidder's Acknowledgement on Bid Express.

Electronic version of these documents can be found on the Bid Express web site at:

<http://www.bidexpress.com>

If you are unable to download plan revisions associated with the addendum, please contact the Engineering office at 608-266-4751 receive the material by another route.

Robert F. Phillips, P.E., City Engineer

Fire Station #5
West Elevation
Addendum 1 Photo



Addendum 1 Item 2
Install a 2" split duct conduit thru wall around existing antenna wires at this location. Fill in with backer foam and sealant.