



Department of Public Works
Engineering Division
Robert F. Phillips, P.E., City Engineer
City-County Building, Room 115
210 Martin Luther King, Jr. Boulevard
Madison, Wisconsin 53703
Phone: (608) 266-4751
Fax: (608) 264-9275
engineering@cityofmadison.com
www.cityofmadison.com/engineering

Deputy City Engineer
Gregory T. Fries, P.E.
Deputy Division Manager
Kathleen M. Cryan
Principal Engineer 2
Christopher J. Petykowski, P.E.
John S. Fahrney, P.E.
Janet Schmidt, P.E.
Principal Engineer 1
Christina M. Bachmann, P.E.
Mark D. Moder, P.E.
James M. Wolfe, P.E.
Facilities & Sustainability
Bryan Cooper, Principal Architect
Mapping Section Manager
Eric T. Pederson, P.S.
Financial Manager
Steven B. Danner-Rivers

June 19, 2020

**NOTICE OF ADDENDUM
ADDENDUM NO. 1
CONTRACT NO. 8349**

E DAYTON STREET ASSESSMENT DISTRICT - 2020

Revise and amend the contract document(s) for the above project as stated in this addendum, otherwise, the original document shall remain in effect.

CONTRACT:

Insert Water Utility specification page D-9 (attached).

The Bid Submission Deadline (Date and Time) has NOT been modified.

Please acknowledge this addendum on page E1 of the contract documents and/or in Section E: Bidder's Acknowledgement on Bid Express.

Electronic version of these documents can be found on the Bid Express web site at:
<http://www.bidexpress.com>

If you are unable to download plan revisions associated with the addendum, please contact the Engineering office at 608-266-4751 receive the material by another route.

Sincerely,

Robert F. Phillips, P.E., City Engineer

Cc: Greg Fries

SECTION 701 PROVISIONS FOR WATER INSTALLATION AND ABANDONMENT

The water designer for this project is:

- Pete Holmgren
608.261.5530
pholmgren@madisonwater.org

This project consists of water main improvements on the 600 and 700-blocks of East Dayton Street. Work will generally consist of the following:

- Install new 8-inch water main as shown on the plans.
- Reconnect existing water services as shown on the plans.
- Abandon the existing (active) early-1900's 4-inch cast-iron water main at the "cut-off" points shown on the plans.
- Remove the existing (inactive) early 1900's 30-inch cast-iron water main to the extent shown on the plans and as otherwise necessary for utility installation work.
- Abandon valve boxes and valve structures on all abandoned water main, and curb boxes on any abandoned services.
- Adjust new and existing (active) valve boxes, hydrants, and curb boxes to appropriate grades.

View the site prior to bidding and become familiar with existing conditions and utilities.

SECTION 703 CONSTRUCTION METHODS

Perform all work in accordance with these provisions and the City of Madison *Standard Specifications For Public Works Construction, 2020 Edition*.

BID ITEM 20314 REMOVE PIPE (30-INCH WATER MAIN)

Abandoned 20-inch and 30-inch cast iron water main are shown on the plans per Water Utility records. The 30-inch water main shall be removed during the installation of the new 8-inch water main, to the extents shown on the plans. The estimated depth to the top of the water main is 5.5-feet.

Pipe removal shall include but not be limited to cutting off the pipe ends at the removal limits; dewatering/water pumping as necessary; disposal of the removed pipe segments; replacement fill; and all other requirements per the Standard Specifications.

Pipe plugs shall be required at the cut off ends and will be paid as a separate bid item.

BID ITEM 70040 FURNISH, INSTALL AND SALVAGE HYDRANT

Due to the installation depth and the expected water table, the hydrant on the 700-block of East Dayton Street shall have its drain ports plugged during installation.