



Department of Public Works
Engineering Division
James M. Wolfe, P.E., City Engineer

City-County Building, Room 115
210 Martin Luther King, Jr. Boulevard
Madison, Wisconsin 53703
Phone: (608) 266-4751
Fax: (608) 264-9275
engineering@cityofmadison.com
www.cityofmadison.com/engineering

Assistant City Engineer
Bryan Cooper, AIA
Gregory T. Fries, P.E.
Chris Petykowski, P.E.
Deputy Division Manager
Kathleen M. Cryan
Principal Engineer 2
John S. Fahrney, P.E.
Janet Schmidt, P.E.
Principal Engineer 1
Mark D. Moder, P.E.
Andrew J. Zwieg, P.E.
Financial Manager
Steven B. Danner-Rivers

April 2, 2024

**NOTICE OF ADDENDUM
ADDENDUM 1
CONTRACT NO. 8735**

EAST WILSON STREET AND EAST DOTY STREET RECONSTRUCTION ASSESSMENT DISTRICT – 2023

Revise and amend the contract document(s) for the above project as stated in this addendum, otherwise, the original document shall remain in effect.

PLANS:

REMOVE

Remove sheets D-11, D-12, D-14, P-1, P-2, and P-4.

INSERT

Insert sheets D-11, D-12, D-14, P-1, P-2, and P-4

Sheets D-11, D-12, D-14, P-1, P-2, and P-4 are being revised to replace proposed Detectable Warning Fields for Pedestrian Directional Field at cycle track access ramps.

SPECIAL PROVISIONS:

ADD: Bid Item 21302 – CONSTRUCTION FENCE (PLASTIC)

The contract quantity is an undistributed amount to be used at the direction of the Construction Engineer.

ADD: BID ITEM 90012 – PEDESTRIAN DIRECTIONAL FIELD

DESCRIPTION

This special provision is for the contractor to install Pedestrian Directional Field in locations identified on the plans or as directed by the Engineer. The City will purchase and provide the contractor the Pedestrian Directional Fields. The product to be installed by the contractor is R-4984 1' X 2' Directional-Bar Plate, manufactured by Neenah Foundry. In the case that the City requires additional plates than originally estimated, the City will purchase the product and will provide the product to the Contractor to perform the installation. The Contractor shall arrange pick-up of the product with Jason Zander of the City of Madison at (608) 225-0867 and shall deliver it to the construction site.

CONSTRUCTION METHODS

The Contractor shall install the Pedestrian Directional Fields per the manufacturer instructions for the

product.

MEASUREMENT

Pedestrian Directional Field will be measured by each unit acceptably installed.

BASIS OF PAYMENT

This item, measured as provided above, will be paid for at the contract unit price for all labor, tools, equipment, pick-up, delivery, and incidentals necessary to acceptably complete the product installation.

PROPOSAL:

Items have been revised in the proposal. See Bid Express.

ACTION	ITEM NUMBER	TYPE OF WORK	UNIT
ADD	21302	CONSTRUCTION FENCE (PLASTIC)	L.F.
MODIFY	30340	CURB RAMP DETECTABLE WARNING FIELDS	S.F.
ADD	90012	PEDESTRIAN DIRECTIONAL FIELD	EACH

Please see Bid Express for revised bid item quantities.


Please acknowledge this addendum on page E1 of the contract documents and/or in Section E: Bidder's Acknowledgement on Bid Express.

Electronic version of these documents can be found on the Bid Express web site at:

<http://www.bidexpress.com>

If you are unable to download plan revisions associated with the addendum, please contact the Engineering office at 608-266-4751 receive the material by another route.

Sincerely,



James M. Wolfe, P.E., City Engineer

JMW:fbeg