



Department of Public Works
Engineering Division
James M. Wolfe, P.E., City Engineer
City-County Building, Room 115
210 Martin Luther King, Jr. Boulevard
Madison, Wisconsin 53703
Phone: (608) 266-4751
Fax: (608) 264-9275
engineering@cityofmadison.com
www.cityofmadison.com/engineering

Assistant City Engineer
Bryan Cooper, AIA
Gregory T. Fries, P.E.
Chris Petykowski, P.E.
Deputy Division Manager
Kathleen M. Cryan
Principal Engineer 2
John S. Fahrney, P.E.
Janet Schmidt, P.E.
Principal Engineer 1
Mark D. Moder, P.E.
Andrew J. Zwieg, P.E.
Financial Manager
Steven B. Danner-Rivers

June 28, 2023

**NOTICE OF ADDENDUM
ADDENDUM 1
CONTRACT NO. 8876
WEXFORD POND DREDGING**

Revise and amend the contract document(s) for the above project as stated in this addendum, otherwise, the original document shall remain in effect.

SECTION D: SPECIAL PROVISIONS

- **REVISE:** Revise SECTION 105.12 COOPERATION OF THE CONTRACTOR 5th paragraph to clarify that dredged material may not be temporarily stockpiled. The paragraph should read as follows.

Contractor is alerted that very little additional space is available within the project grading limits for material storage, staging, and other uses. Contractor may stage equipment, temporary stockpile topsoil and store materials within the staging areas identified on the plans that will not affect existing trees to remain or protected vegetation. **The Contractor SHALL NOT temporarily stockpile dredged material. Dredge material must be directly loaded and hauled via watertight haul trucks with tailgate seals to eliminate the loss of water during hauling operations.** These areas will be restored in kind when construction is complete.

- **REVISE:** Revise SECTION 105.12 COOPERATION OF THE CONTRACTOR 6th paragraph to clarify that dredged material may not be temporarily stockpiled. The paragraph should read as follows:

The Contractor shall use care when access the site and during construction not to damage existing trees, plantings, fences, utilities, structures, or other facilities that are to remain. Damage to these items during construction shall be repaired or replaced at the Contractor's expense per the City of Madison Standard Specifications and shall be considered incidental to this contract except as specified in the below paragraph. The Contractor shall protect existing elements within the approximate construction area available for Contractor's use as indicated on the drawings. The Contractor should be made aware that existing rip rap may exist in the existing pond within the proposed sediment dredging and pond excavation limits. The Contractor shall replace all existing riprap excavated at no additional cost. In addition, the Contractor may choose to install additional access roads, provide temporary stockpiles (**excluding stockpiling dredged material or excavation cut**), and store material and equipment within the approximate construction area. Any additional site disturbance not indicated on the drawings or included in the bid item quantities shall be restored in accordance with the specifications at no additional cost.

- **REVISE:** Revise SECTION 109.2 PROSECUTION OF THE WORK, 3rd paragraph to clarify that the clay liner may be placed on frozen foundation. The paragraph shall be revised to read:

The clay liner shall not be placed until the required subgrade preparation has been completed and the subgrade has been inspected and approved by the City's Geotechnical Consultant. The clay liner shall meet the criteria in WDNR SOC Standard 1001 Wet Detention Pond. Frozen clay cannot be utilized to create the liner. The clay liner shall not be placed until the required foundation preparation has been completed and the foundation has been inspected and approved by the Construction Engineer. **The clay liner shall not be placed upon snow or ice.**

- **REVISE:** Revise BID ITEM 90003 – CLAY LINER PROVISION AND PLACEMENT, 1st paragraph under CONSTRUCTION – PLACEMENT to clarify that the clay liner may be placed on frozen foundation. The paragraph shall be revised to read as follows:


The clay liner shall not be placed until the required foundation preparation has been completed and the foundation has been inspected and approved by the Construction Engineer. The clay liner shall not be placed upon snow, ice, and no frozen material shall be incorporated in the clay liner. **The clay liner MAY BE PLACED on frozen foundation subgrade free of snow and ice.**

Please acknowledge this addendum on page E1 of the contract documents and/or in Section E: Bidder's Acknowledgement on Bid Express.

Electronic version of these documents can be found on the Bid Express website at:

<http://www.bidexpress.com>

If you are unable to download plan revisions associated with the addendum, please contact the Engineering office at 608-266-4751 receive the material by another route.


James M. Wolfe, P.E., City Engineer

JMW:scl