



Department of Public Works
Engineering Division
James M. Wolfe, P.E., City Engineer

City-County Building, Room 115
210 Martin Luther King, Jr. Boulevard
Madison, Wisconsin 53703
Phone: (608) 266-4751
Fax: (608) 264-9275
engineering@cityofmadison.com
www.cityofmadison.com/engineering

Deputy City Engineer
Bryan Cooper, AIA
Gregory T. Fries, P.E.
Chris Petykowski, P.E.

Deputy Division Manager
Kathleen M. Cryan

Principal Engineer 2
John S. Fahrney, P.E.
Janet Schmidt, P.E.

Principal Engineer 1
Christina M. Bachmann, P.E.
Mark D. Moder, P.E.

Financial Manager
Steven B. Danner-Rivers

October 18, 2022

**NOTICE OF ADDENDUM
ADDENDUM 1**

**CONTRACT NO. 9432
HAWKS LANDING NORTH FLOOD MITIGATION**

Revise and amend the contract document(s) for the above project as stated in this addendum, otherwise, the original document shall remain in effect.

PROPOSAL

See below for a summary of items that have been removed, added or revised. Refer to the proposal for updated quantities. See proposal on bidexpress.com.

Added quantities for the following items:

- **20217 CLEAR STONE**
- **50225 UTILITY TRENCH PATCH TYPE III (UNDISTRIBUTED)**
- **50227 UTILITY TRENCH PATCH TYPE IV (UNDISTRIBUTED)**

SPECIAL PROVISIONS: SECTION D:

REPLACE: Bid Item 90002 with the following:

BID ITEM 90002: S-2 OUTLET STRUCTURE

DESCRIPTION

S-2 Outlet Structure shall include all work, equipment, and incidentals necessary to furnish and install the Precast Reinforced Outlet Control Structure S-2 as indicated in the contract drawings. The access door shall be Halliday #H2W4242 (or approved equal) with a channel frame and H-20 loading. All work shall be constructed in accordance with the details in the plans, or as approved by the Engineer.

MEASUREMENT

S-2 Outlet Structure shall be measured by each structure constructed and accepted and as defined in this Special Provision.

BASIS OF PAYMENT

The contract price shall include furnishing all labor and materials necessary to perform the work, including access door, gate, chain lock bracket, excavation; installation and removal of sheeting and bracing; removal of

water from the excavation; disposal of surplus material from the excavation; backfilling the excavation; backfilling the excavation and compaction of the backfill material; preparation of the foundation; construction of the structure, reconnection of all existing pipes, connection of new pipes, including connections; cleaning out the structure; restoring the site; and all other work incidental to the installation of outlet structure.

QUESTION AND ANSWER:

Q. Can the farm lands be used to respreads excess materials? Can contractors enter the pond property for test pits?

A. The Contractor shall not assume the ability to respreads materials on lands that are not owned by the City. They may contact the property owner to discuss this as an option however there is no express permission to do so.


The lands that the City will be purchasing as part of the pond construction are not deeded to the City at the time of the project letting. The lands will be acquired before the start of construction. The City can not provide express permission to do any investigative work on the lands at this time.

Please acknowledge this addendum on page E1 of the contract documents and/or in Section E: Bidder's Acknowledgement on Bid Express.

Electronic version of these documents can be found on the Bid Express website at:

<http://www.bidexpress.com>

If you are unable to download plan revisions associated with the addendum, please contact the Engineering office at 608-266-4751 receive the material by another route.



For:

James M. Wolfe, City Engineer

CC:
Greg Fries
Janet Schmidt