



Department of Public Works
Engineering Division
Kathy Cryan, Interim Engineering Manager
City-County Building, Room 115
210 Martin Luther King, Jr. Boulevard
Madison, Wisconsin 53703
Phone: (608) 266-4751
Fax: (608) 264-9275
engineering@cityofmadison.com
www.cityofmadison.com/engineering

Deputy City Engineer
Gregory T. Fries, P.E.
Principal Architect 2
Bryan Cooper, AIA
Principal Engineer 2
John S. Fahrney, P.E.
Chris Petykowski, P.E.
Janet Schmidt, P.E.
Principal Engineer 1
Christina M. Bachmann, P.E.
Mark D. Moder, P.E.
James M. Wolfe, P.E.
Financial Manager
Steven B. Danner-Rivers

August 1, 2022

**NOTICE OF ADDENDUM
ADDENDUM 1**

**CONTRACT NO. 9433
SPRING HARBOR DREDGING 2022**

Revise and amend the contract document(s) for the above project as stated in this addendum, otherwise, the original document shall remain in effect.

SECTION D: SPECIAL PROVISIONS

- REPLACE BID ITEM 9004 – HAULING AND DISPOSAL OF DRY MATERIALS FROM MMSD TO LANDFILL WITH THE FOLLOWING:

BID ITEM 9004- HAULING AND DISPOSAL OF DRY MATERIAL FROM MMSD TO LANDFILL

DESCRIPTION

This bid item shall include all mobilizations, labor, materials, and vehicles necessary for re-loading dry material in water-tight, sealed trucks, hauling the material from the MMSD drying bed to the Dane County Sanitary Landfill located at 7102 US-12 Madison, WI 53718. This bid item shall include the unloading of, and disposal of the material at the Landfill.

The Project Manager shall be notified 48 hours prior to hauling the first truck of material to the Landfill. The Contractor shall coordinate access and placement of the material with the Landfill. The Contractor will be provided contact information for the Dane County Landfill.

Mobilization for this work shall be incidental to this bid item.

The methods and equipment plan shall include a plan for the gradual removal of dry sediment to be hauled from MMSD to the Landfill.

The Landfill has the following criteria for accepting material: Maximum quantity of dried material hauled at a time from MMSD to Dane County landfill is 15 trucks per day at 15 CY per truck (225 CY) per day. The Material shall be dry enough and shall pass the paint filter test <https://www.epa.gov/hw-sw846/sw-846-test-method-9095b-paint-filter-liquids-test> which is a test for free liquids. To avoid traffic jams and long waits at the weigh stations, a possibility is weighing 1 or 2 of 15 trucks per day coming in from MMSD.

The Contractor shall note the Landfill's hours of operation:

Hours: Tuesday	7AM-2:45PM
Wednesday	7AM-2:45PM
Thursday	7AM-2:45PM
Friday	7AM-2:45PM
Saturday	8-10:45AM
Sunday	Closed
Monday	7AM-2:45PM

Once all material has been removed from the MMSD drying bed the site shall be restored as directed by the Project Manager.

Mobilization for this work shall be paid under Bid Item 10911 –MOBILIZATION.

The Contractor SHALL NOT be responsible for tipping fees at the Dane County Landfill. All fees shall be paid by the City of Madison.

METHOD OF MEASUREMENT

Hauling and Disposal of Dry Material from MMSD to Landfill, as described above shall be measured by Cubic Yards as listed on the Proposal Page.

BASIS OF PAYMENT

Hauling and Disposal of Dry Material from MMSD to Landfill, as measured above, shall be full compensation for all work, materials and incidentals to complete the work as described above.

Please acknowledge this addendum on page E1 of the contract documents and/or in Section E: Bidder's Acknowledgement on Bid Express.

Electronic version of these documents can be found on the Bid Express website at:

<http://www.bidexpress.com>

If you are unable to download plan revisions associated with the addendum, please contact the Engineering office at 608-266-4751 receive the material by another route.



for:
Kathy Cryan, Interim Engineering Manager

CC:
Greg Fries
Bryan Cooper
Chris Petykowski