



Department of Public Works
Engineering Division
James M. Wolfe, P.E., City Engineer

City-County Building, Room 115
210 Martin Luther King, Jr. Boulevard
Madison, Wisconsin 53703
Phone: (608) 266-4751
Fax: (608) 264-9275
engineering@cityofmadison.com
www.cityofmadison.com/engineering

Assistant City Engineer
Bryan Cooper, AIA
Gregory T. Fries, P.E.
Chris Petykowski, P.E.

Deputy Division Manager
Kathleen M. Cryan

Principal Architect
Amy Loewenstein Scanlon, AIA

Principal Engineer 2
Janet Schmidt, P.E.

Principal Engineer 1
Kyle Frank, P.E.
Mark D. Moder, P.E.
Fadi El Musa Gonzalez, P.E.
Andrew J. Zwieg, P.E.

Financial Manager
Steven B. Danner-Rivers

6/23/2026

NOTICE OF ADDENDUM ADDENDUM 1

CONTRACT NO. 9807 FORDEM AVE – FIRST STREET RELIEF SEWER

Revise and amend the contract document(s) for the above project as stated in this addendum, otherwise, the original document shall remain in effect.

Plans

- **COVER SHEET** - Update index to remove P2.
- **U-1** – Changed removed pipes to abandon with slurry.
- **U-2** – Changed removed pipes to abandon with slurry.

PROPOSAL

Items have been revised in the proposal. See Bid Express.

Action	Bid Item	Description
Update	20314	REMOVE PIPE (SANITARY) UNDISTRIBUTED
Update	20335	ABANDON SEWER PIPE WITH SLURRY
ADDED	90020	RELOCATE/REPAIR WATER LATERAL SERVICE (UNDISTRUBUTED)
ADDED	90036	CONSTRUCTION OBSERVER

SPECIAL PROVISIONS

- SECTION 107.12 RAILROAD-HIGHWAY GRADE SEPERATIONS AND APPROACHES, NEW RAILROAD CROSSINGS, OPERATIONS ON RAILROAD RIGHT-OF-WAY.

Add two new superseding sections after the first paragraph of “**107.12(A) GENERAL**” for additional permit requirements for working within Canadian Pacific Railway Company (CPKC) (1894 E Johnson St.) Right of Way (ROW). They both will precede the second paragraph.

It shall be the responsibility of the Contractor to obtain a Right of Entry permit from CPKC for execution of the Issued Utility Permit as a condition of this contract. It shall be the responsibility of the Contractor to compensate the CPKC for the permit fees, and this compensation is considered incidental to this contract and relative bid items. This permit can be applied for at the website:

<https://jll-permitting.360works.com/login>.

CPKC may require a Construction Observer requirement as part of the conditions of the issued Utility Permit. Should this be required, it shall be the responsibility of the Contractor to compensate the CPKC Railroad for the Construction Observer requirements, and this compensation shall be paid for as BID ITEM 90036 – CONSTRUCTION OBSERVER.. Prior to any work within Railroad Right-of-Way, the Contractor shall provide to CPKC an estimate of the time required to perform necessary work within right-of-way. The Contractor shall pay all personnel costs consistent with railroad requirements and policies, which may require pre-payment by the Contractor to CPKC of estimated cost for compensation for a Construction Observer based on the estimated time required to perform all work right-of-way and the current rate of compensation charged by CPKC for a Construction Observer. In the event that the pre-paid amount for Construction Observer compensation exceeds the actual cost required for the compensation of the engineer person, any excess pre-paid amount will be refunded to the Contractor. In the event that actual cost for compensation of the Construction Observer exceeds the pre-paid estimate, the Contractor shall submit an additional pre-payment for the estimated additional cost for compensation of a Construction Observer, prior to any work continuing within right-of-way.

- SECTION 108.2 **PERMITS**

Add one new superseding section after the third paragraph for additional permit requirements for working within Canadian Pacific Railway Company (CPKC) (1894 E Johnson St.) Right of Way (ROW). This will precede the third paragraph.

The Contractor shall obtain a Right of Entry Permit from CPKC for work within CPKC property at 1894 E Johnson St. as a condition of the issued utility permit. This permit can be applied for at the website: <https://jll-permitting.360works.com/login>. Should CPKC require a Construction Observer during construction, it shall be the Contractor's responsibility to follow all Construction Observer requirements set forth by CPKC.

- **BID ITEM 20314 – REMOVE PIPE (SANITARY) UNDISTRIBUTED**

There is an undistributed amount of REMOVE PIPE included in this contract.

- **BID ITEM 90020 – RELOCATE/REPAIR WATER LATERAL SERVICE (UNDISTRUBUTED)**
Add a new section of the contract titled “**RELOCATE/REPAIR WATER LATERAL SERVICE (UNDISTRUBUTED)**”. The new section shall include the following text:

BID ITEM 90020 – RELOCATE/REPAIR WATER LATERAL SERVICE (UNDISTRUBUTED)

DESCRIPTION

This work shall include, but not be limited to, installation of vertical to go beneath or above the proposed sewer utilities, or horizontal offsets to go around the proposed sewer utilities. This work under this item shall also include the repair of any damaged due to construction activities. The lengths of pipe to be relocated shall be limited to the immediate crossing of the proposed sewer utilities. Any new piping shall appropriately match the existing size of the water services being offset. Prior to construction, all ULOs and any necessary redesigns shall be completed in order to avoid potential conflicts.

All finished work must be inspected and approved by the Water Utility Construction Supervisor and shall conform to all relevant sections of the City of Madison Standards Specifications for Public Works Construction, Latest Edition.

Contact Jeff Belshaw (jbelshaw@madisonwater.org). (608) 261-9835) for coordination if water

service relocation may be necessary.

This contract includes 1 additional undistributed RELOCATE/REPAIR WATER LATERAL SERVICE to be performed as directed by the City of Madison Construction Engineer.

METHOD OF MEASUREMENT

RELOCATE/REPAIR WATER LATERAL SERVICE shall be measured per each specific instance as identified in the field.

BASIS OF PAYMENT

RELOCATE/REPAIR WATER LATERAL SERVICE shall be paid for at the contract unit price, which shall be full compensation for all excavation, disposal of removed material, preparation of subgrade including sub-base, furnishing materials, backfilling and trench restoration, insulation installation, fill, topsoil, and for all labor, tools, equipment and incidentals necessary to complete the work.

- **BID ITEM 90036 – CONSTRUCTION OBSERVER**
Add a new section of the contract titled “**BID ITEM 90036 - CONSTRUCTION OBSERVER**”. The new section shall include the following text:

BID ITEM 90035 – CONSTRUCTION OBSERVER

DESCRIPTION

This work shall include scheduling/coordinating with Canadian Pacific Railway Company (CPKC) to schedule a Construction Observer to be present while working within the CPKC right-of-way as a condition of the utility permit. The contractor shall follow the stipulations listed in SECTION 107.12 - RAILROAD-HIGHWAY GRADE SEPERATIONS AND APPROACHES, NEW RAILROAD CROSSINGS, OPERATIONS ON RAILROAD RIGHT-OF-WAY of this contract regarding the Construction Observer.

This item includes:

Mobilization/Demobilization for the Construction Observer - \$1500.00
8-hr day rate Construction Observer - \$1500.00/Day
Hourly rate for each hour beyond 8-hr shift - \$190/HR

METHOD OF MEASUREMENT

CONSTRUCTION OBSERVER shall be measured as a lump sum.

BASIS OF PAYMENT

CONSTRUCTION OBSERVER shall be paid for at the contract lump sum price which shall be full compensation for all coordination, Mobilization/Demobilization, daily and hourly rates.

- **BID ITEM 90051 – EXCAVATION AND HAULING OF CONTAMINATED SOIL (UNDISTRIBUTED)**
Add a new superseding section to “C Construction” in the contract documents for special item “**EXCAVATION AND HAULING OF CONTAMINATED SOIL (UNDISTRIBUTED)**” after the last paragraph under section “C Construction”.

In the event soils cannot be sufficiently dewatered for direct landfill disposal, the Madison Metropolitan Sewerage District dewatering beds may be used to dry soil before bringing it to the


landfill. The City of Madison has conditional approval to use the drying beds for these soils. If the Contractor chooses to use the MMSD drying beds, all hauling, handling, drying and cleanup work at MMSD is included with this bid item.

Please acknowledge this addendum on page E1 of the contract documents and/or in Section E: Bidder's Acknowledgement on Bid Express.

Electronic version of these documents can be found on the Bid Express website at:

<http://www.bidexpress.com>

If you are unable to download plan revisions associated with the addendum, please contact the Engineering office at 608-266-4751 receive the material by another route.

 For:
James M. Wolfe, City Engineer

CC:

Todd Chojnowski
City of Madison Engineering

Jim Wolfe
City of Madison Engineering

Mark Moder
City of Madison Engineering

Angela Wilcox-Hull
City of Madison Engineering

To request interpretation, translation or a disability-related accommodation at no cost to you, contact the Engineering Division, (608) 266-4751, or email engineer@cityofmadison.com.

Para solicitar interpretación, traducción o una adaptación especial relacionada con alguna discapacidad sin costo alguno para usted, comuníquese al (608) 266-4751 o al correo engineer@cityofmadison.com.

如需免費提供口譯、筆譯或殘疾相關的便利服務，請聯系 (608) 266-4751 或 engineer@cityofmadison.com.

Koj muaj txoj cai tau txais kev txhais lus, kev pes lus los sis kev pab cuam txhawm rau kev tsis taus uas tsis muaj nqi rau koj: Xav paub ntxiv tiv tauj rau (608) 266-4751 los sis engineer@cityofmadison.com.