

Single, straight, main trunk.
Lower branches may require
removal for height clearance

Remove transit guard

Root flare to be level
with the finished grade

3"-4" of woody mulch:
Shredded or Ground
hardwood bark mulch

Remove wire baskets; or cut top and
fold down in pit after positioned for
backfill planting. Cut and remove or
fold down burlap from upper 1/2
of ball.

Cut and remove all poly ties and burlap !!

Water thoroughly to eliminate air pockets,
and to settle the surrounding soil

Finish Grade

Soil under ball undisturbed
to support root ball
and reduce settling

Break down sides of
hole when backfilling

3 times ball diameter

Backfill: Excavated soil or amended
as specified. Do Not Tamp !!!

2004

CITY OF MADISON
PARKS DIVISION

STANDARD PLANTING
TECHNIQUE FOR TREES
IN TURF AREAS

STANDARD DETAIL DRAWING 2.01