

CITY OF MADISON

CITY ENGINEERING DIVISION

DEPARTMENT OF PUBLIC WORKS

PLAN OF PROPOSED IMPROVEMENT

PUBLIC IMPROVEMENT PROJECT
APPROVED

MARCH 30, 2021

BY THE COMMON COUNCIL
OF MADISON, WISCONSIN

PUBLIC IMPROVEMENT DESIGN
APPROVED BY:

Greg Fries

Jan 13, 2022

City Engineer

Date

INDEX OF SHEETS


SHEET NO.	D1	STANDARD NOTES
SHEET NO.	D2-D3	TYPICAL SECTION
SHEET NO.	P1-P5	PLAN & PROFILE
SHEET NO.	U1-U4	UTILITIES PLAN & PROFILE
SHEET NO.	USAN	SANITARY SEWER SCHEDULE
SHEET NO.	USTM	STORM SEWER SCHEDULE
SHEET NO.	C2.0	GRADING & EROSION CONTROL
SHEET NO.	D1.1-D1-2	POND DETAILS
SHEET NO.	W1-W4	WATER PLAN AND PROFILE
SHEET NO.	W5	WATER IMPACT PLAN
SHEET NO.	W6	WATER ESTIMATE OF MATERIALS
SHEET NO.	MN-1	MAINTENANCE PLAN

4800 VOGES ROAD

CITY PROJECT NO. 12582

CONTRACT NO. 9025

PROJECT LOCATION



STORMWATER MANAGEMENT
DESIGNED BY:


SEE INDIVIDUAL SHEETS

STREET
DESIGNED BY:



Jan 13, 2022

GEOMETRY
DESIGNED BY:




Jan 13, 2022

SANITARY SEWER
DESIGNED BY:




Jan 13, 2022

WATER
DESIGNED BY:



Jan 13, 2022

STORM SEWER
DESIGNED BY:




Jan 13, 2022

PLOT SCALE: 1:1000, X-REF

PLOT NAME: -----

REV. DATE: 12/14/2021 6:00 PM

ORIGINATOR: CITY_OF_MADISON

D-1	12582	
STANDARD NOTES 4800 VOGES ROAD MADISON, WI CONTRACT NO: 9025 MA:\DESIGN\Projects\12582\CAD\Streets\12582EN-Details.dwg		
12582		
		BY
--	--	DATE
--	--	REVISION
--	--	MARK
Designed By: ###		Date: 1/7/2022 2:15 PM
		Scales: #####
12582		D-1

DATE	BY
17/2022	11/2022
REVISION	Scale: #####
MARK	12582
Designed By: ###	
Date: 17/2022 2:09 PM	
	D-2

12582

MADISON, WI

9025

CONTRACT NO:

TYPICAL SECTION


4800 VOGES ROAD

M:\DESIGN\Projects\12582\CAD\Streets\12582EN-Details.dwg




12582

D-2



TYPICAL SECTION
GALLEON RUN
STA 99+75 TO STA 101+00




TYPICAL SECTION
GALLEON RUN
STA 101+00 TO STA 115+15

NOTES:

* GALLEON RUN SHALL BE CONSTRUCTED AS TYPE 'C' PAVEMENT PER CITY OF MADISON MINIMUM PAVEMENT DESIGN. THE CITY SHALL BE RESPONSIBLE FOR ALL BINDER (EXCEPT FROM STA 99+75 TO 101+00) AND ALL SURFACE PAVING UNDER THE CITY'S RESURFACING CONTRACT. THE DEVELOPER SHALL COORDINATE PAVING WORK WITH CITY ENGINEERING AND SHALL PROVIDE THE RESURFACING PROJECT CONTRACTOR A TWO WEEK NOTICE WHEN FINISH GRADING WORK IS COMPLETED AND THE STREET IS SET FOR PAVING.

**TYPE 'C' PAVEMENT PER CITY OF MADISON MINIMUM PAVEMENT DESIGN. THE DEVELOPER SHALL BE RESPONSIBLE FOR BINDER PAVING.

CITY OF MADISON MINIMUM PAVEMENT DESIGN						
TYPE	CRUSHED AGGREGATE BASE COURSE		ASPHALTIC CONCRETE PAVEMENT			
	LOWER LAYER GRADATION 1	UPPER LAYER GRADATION 2	LOWER LAYER		UPPER LAYER	
			TYPE	THICKNESS	TYPE	THICKNESS
A	6"	6"	4 LT 58-28 S	1.75"	4 LT 58-28 S	1.75"
B	6"	6"	3 LT 58-28 S	2.50"	4 LT 58-28 S	2.00"
C	6"	6"	3 MT 58-28 S/H	3.50"	4 MT 58-28 S/H	2.00"



TYPICAL SECTION
RUSTY PATCH ROAD

NOTES:

* RUSTY PATCH ROAD SHALL BE CONSTRUCTED AS TYPE 'C' PAVEMENT PER CITY OF MADISON MINIMUM PAVEMENT DESIGN. THE CITY SHALL BE RESPONSIBLE FOR ALL BINDER AND SURFACE PAVING UNDER THE CITY'S RESURFACING CONTRACT. THE DEVELOPER SHALL COORDINATE PAVING WORK WITH CITY ENGINEERING AND SHALL PROVIDE THE RESURFACING PROJECT CONTRACTOR A TWO WEEK NOTICE WHEN FINISH GRADING WORK IS COMPLETED AND THE STREET IS SET FOR PAVING.

CITY OF MADISON MINIMUM PAVEMENT DESIGN						
TYPE	CRUSHED AGGREGATE BASE COURSE		ASPHALTIC CONCRETE PAVEMENT			
	LOWER LAYER GRADATION 1	UPPER LAYER GRADATION 2	LOWER LAYER		UPPER LAYER	
			TYPE	THICKNESS	TYPE	THICKNESS
A	6"	6"	4 LT 58-28 S	1.75"	4 LT 58-28 S	1.75"
B	6"	6"	3 LT 58-28 S	2.50"	4 LT 58-28 S	2.00"
C	6"	6"	3 MT 58-28 S/H	3.50"	4 MT 58-28 S/H	2.00"

12582


MADISON, WI

CONTRACT NO: 9025

TYPICAL SECTION

4800 VOGES ROAD

M:\DESIGN\Projects\12582\CAD\Streets\12582EN-Details.dwg



12582

D-3

MARK

REVISION

DATE

BY

12582



17/2022 2:09 PM

###



###

12582

D-3





12582	MADISON, WI	9025	CONTRACT NO:
PLAN & PROFILE - GALLEON RUN			12582
4800 VOGES ROAD			
M:\DESIGN\Projects\12582\CAD\Streets\12582 - P Sheets.dwg			P-1
CITY OF MADISON WISCONSIN			



12582	MADISON, WI	9025	CONTRACT NO:
PLAN & PROFILE - GALLEON RUN			4800 VOGES ROAD
12582			P-2

M:\DESIGN\Projects\12582\CAD\Streets\12582 - P Sheets.dwg





	12582					P-3
	P-3					
	PLAN & PROFILE - GALLEON RUN		12582			
	4800 VOGES ROAD		MADISON, WI			
	CONTRACT NO:		9025			
	MA\DESIGN\Projects\12582\CAD\Streets\12582 - P Sheets.dwg					
MARK	REVISION	DATE	BY			
Designed By, ##	Date: 1/7/2022 1:40 PM	Scale: 1" = 40'				
12582				P-3		

REVISED 5 / 6 / 2022 - FBEG

1. DELETED BOTH DRIVEWAY APRONS FOR LOT 3.
2. ADDED CONCRETE TERRACE WATERWAYS
3. REVISED DIMENSIONS FOR LOT 1 DRIVEWAY APRON.

LEGEND:

- = SAWCUT
- = SIDEWALK DRAINAGE PATH
- = DETECTABLE WARNING FIELD



MARK	REVISION	DATE	BY
12582		5/6/2022 5:48 PM	P-4

12582

MADISON, WI

CONTRACT NO: 9025



PLAN & PROFILE - RUSTY PATCH ROAD

4800 VOGES ROAD

M:\DESIGN\Projects\12582\CAD\Streets\12582 - P Sheets.dwg

12582

P-4



*NOTE:
CONTACT RAY SCHNEIDER OF MM5D 5 DAYS PRIOR FOR THE MANHOLE ADJUST
AND THE TAP CONNECTION TO ARRANGE FOR INSPECTION & PERMITTING.
ALL WORK ON MM5D MANHOLE NEEDS TO CONFIRM WITH MM5D SPECIFICATIONS.
rays@madsewer.org (608) 347-3628

*NOTE:
PIPE SHALL CONFORM TO
ASTM D3034 SDR-26

12582

MADISON, WI

CONTRACT NO: 9025

UTILITIES PLAN AND PROFILE - GALLEON RUN



4800 VOGES ROAD CSM

12582



U-1

MARK	REVISION	DATE	BY
12582	U-1	1/4/2022 3:26 PM	U-1

M:\DESIGN\Projects\12582\CAD\Sewers\12582SWR-PipeNetwork.dwg



12582		MADISON, WI		9025		U-2	
CONTRACT NO:		12582		12582		U-2	
UTILITIES PLAN AND PROFILE - GALLEON RUN		4800 VOGES ROAD CSM		M:\DESIGN\Projects\12582\CAD\Sewers\12582SWR-PipeNetwork.dwg			
		12582		U-2			



12582		MADISON, WI		CONTRACT NO: 9025	
UTILITIES PLAN AND PROFILE - GALLEON RUN		4800 VOGES ROAD CSM		M:\DESIGN\Projects\12582\CAD\Sewers\12582SWR-PipeNetwork.dwg	
		12582		U-3	
MARK		REVISION		DATE	
Designed By: EEA		Date: 3/16/2022 10:37 AM		Scale: 1" = 40'	
12582		9025		U-3	

SANITARY SEWER SCHEDULE

* REVISED 1/28/2022 - EEA

4800 VOGES ROAD CSM	SHEET NO.
PROJECT NO. 12582	U-SAN
SANITARY SEWER SCHEDULE	
CITY OF MADISON	

PROPOSED SANITARY						
SAS NO.	STATION	LOCATION (OFFSET)	TOP OF CASTING	E.I.	DEPTH (FT)	NOTES
GALLEON RUN						
SAS#1	102+87.04	CL	861.77	845.81	15.96	(1)
SAS#2	104+00.00	CL	861.07	847.96	13.11	(1)
SAS#3	105+00.00	CL	860.46	848.98	11.48	(1); (2)
RUSTY PATCH ROAD						
SAS#4	53+00.00	CL	861.42	846.23	15.19	(1); (2)
* SAS#5	50+15.50	CL	861.40	847.47	13.93	(1)

PROPOSED SANITARY PIPES								
FROM (DNSTM)	TO (UPSTM)	DWNSTRM E.I.	UPSTRM E.I.	PLAN LGTH (FT)	SLOPE (%)	PIPE SIZE	PVC TYPE	NOTES
GALLEON RUN								
EX MH07-224	SAS#1	844.87	845.81	188	0.50%	8"	SDR-26	(3)
SAS#1	SAS#2	845.91	847.96	112	1.83%	8"	SDR-26	-
SAS#2	SAS#3	848.06	848.46	100	0.40%	8"	SDR-26	-
RUSTY PATCH ROAD								
SAS#1	SAS#4	845.91	846.23	81	0.40%	8"	SDR-26	-
SAS#4	SAS#5	846.33	847.47	285	0.40%	8"	SDR-26	-

SPECIFIC NOTES:
(1) INSTALL EXTERNAL RUBBERIZED JOINT WRAPP PER S.D.D. 5.7.2
(2) INSTALL INTERNAL CHIMNEY SEAL PER S.D.D. 5.7.17
(3) CONTACT RAY SCHNEIDER OF MMSD AT rays@madsewer.org or (608) 347-3628, 5 DAYS PRIOR FOR THE MANHOLE ADJUST AND THE TAP CONNECTION TO ARRANGE FOR INSPECTION & PERMITTING.
ALL WORK ON MMSD MANHOLE NEEDS TO CONFIRM WITH MMSD SPECIFICATIONS.

NOTES:
- ALL STRUCTURES SHALL BE SUBMITTED TO CITY ENGINEERING FOR APPROVAL. CONTACT ELIA E ACOSTA OF CITY ENGINEERING AT (608) 266-4096 FOR PRECAST APPROVALS, FAX SHOP DRAWINGS TO (608)264-9275, OR EMAIL SHOP DRAWINGS TO EACOSTA@CITYOFMADISON.COM.

STORM SEWER SCHEDULE

* REVISED 1/28/2022 - EEA
++ REVISED 3/16/2022 - EEA

4800 VOGES ROAD CSM	SHEET NO.
PROJECT NO. 12582	U-STM
STORM SEWER SCHEDULE	
CITY OF MADISON	

PROPOSED STORM STRUCTURES

STRUC. NO.	STATION	LOCATION (OFFSET)	TYPE	TOP OF CASTING	E.I.	DEPTH	NOTES
GALLEON RUN							
S-0	107+50.00	RT-77.85	24" RCP APRON END	-	854.00	-	W/ GATE
S-1	107+50.00	RT-19.50	4X4 SAS	859.07	854.29	4.78	LP; W/ R-3067-7004-VB
S-1A	107+50.00	LT-19.50	H INLET	859.07	855.85	3.22	LP; W/ R-3067-7004-VB
S-2	106+75.00	RT-19.50	4X4 SAS	859.45	854.82	4.63	W/ R-3067-7004-V
S-3	103+92.30	RT-19.50	4X4 SAS	861.15	856.22	4.93	W/ R-3067-7004-V
S-4	103+19.45	RT-19.50	4X4 SAS	861.59	856.84	4.75	W/ R-3067-7004-V
S-4A	103+05.00	LT-19.50	H INLET	861.68	858.08	3.60	W/ R-3067-7004-V
++ S-8	108+27.33	LT-59.72	18" RCP APRON END	-	854.00	-	-
++ S-8A	108+41.59	RT-66.67	18" RCP APRON END	-	855.00	-	-
S-9	110+40.38	RT-70.06	12" RCP APRON END	-	854.50	-	W/ GATE
S-9A	110+25.00	RT-19.50	H INLET	859.45	856.25	3.20	LP; W/ R-3067-7004-VB
S-9B	110+25.00	LT-19.50	H INLET	859.45	856.45	3.00	LP; W/ R-3067-7004-VB
S-10	113+79.46	LT-54.25	12" RCP APRON END	-	854.00	-	W/ GATE
++ S-10A	114+11.21	RT-42.78	5X5 SAS	859.50	855.00	4.50	W/ R-1550
S-10B	114+22.77	RT-59.43	12" RCP APRON END	-	855.00	-	W/ GATE
* S-11	115+35.84	LT-20.13	STORM TAP	-	854.02	-	TAP EX IN 6863-005; (1)
S-11A	115+10.84	LT-19.50	H INLET	857.50	854.26	3.24	LP; W/ R-3067-7004-VB
S-11B	115+10.84	RT-19.50	H INLET	857.50	854.46	3.04	LP; W/ R-3067-7004-VB

RUSTY PATCH ROAD

S-5	53+35.86	RT-16.50	4X4 SAS	861.35	857.00	4.35	LP; W/ R-3067-7004-VB
S-5A	53+35.86	LT-16.50	H INLET	861.35	857.66	3.69	LP; W/ R-3067-7004-VB
S-6	51+00.00	RT-16.50	3X3 SAS	861.96	858.18	3.78	FP; LP; W/ R-3067-7004-VB
S-6A	51+00.00	LT-16.50	H INLET	861.96	858.84	3.12	LP; W/ R-3067-7004-VB
S-6B	50+26.73	LT-16.50	H INLET	862.32	859.19	3.13	W/ R-3067-7004-V

PROPOSED STORM PIPES

PIPE NO.	FROM (DNSTM)	TO (UPSTM)	DISCH. E.I.	INLET E.I.	PLAN (PAY) LGTH (FT)	PIPE LGTH (FT)	SLOPE (%)	PIPE SIZE	TYPE	NOTES
GALLEON RUN										
P-0	S-0	S-1	854.00	854.29	58	57	0.51%	24"	TYPE II	-
P-1	S-1	S-2	854.29	854.82	69	65	0.82%	21"	TYPE II	NCM
P-1A	S-1	S-1A	855.24	855.85	39	36	1.69%	12"	TYPE I	-
P-2	S-2	S-3	854.82	856.22	283	279	0.50%	21"	TYPE II	-
P-3	S-3	S-4	856.47	856.84	78	74	0.50%	18"	TYPE I	-
P-4	S-4	S-5	856.84	857.00	37	32	0.50%	18"	TYPE II	-
P-4A	S-4	S-4A	857.34	858.08	42	38	1.95%	12"	TYPE I	-
++ P-8	S-8	S-8A	854.00	855.00	127	127	0.79%	18"	TYPE I	-
P-9	S-9	S-9A	854.50	856.25	53	52	3.37%	12"	TYPE II	-
P-9A	S-9A	S-9B	856.25	856.45	39	37	0.54%	12"	TYPE I	-
++ P-10	S-10	S-10A	854.25	855.00	102	101	0.74%	18"	TYPE I	-
++ P-10A	S-10A	S-10B	855.00	855.00	20	19	0.00%	18"	TYPE II	-
* P-11	S-11	S-11A	854.02	854.26	25	24	1.00%	12"	TYPE II	NCM
P-11A	S-11A	S-11B	854.26	854.46	39	37	0.54%	12"	TYPE I	-

RUSTY PATCH ROAD

P-5	S-5	S-6	857.00	858.18	239	236	0.50%	18"	TYPE I	-
P-5A	S-5	S-5A	857.50	857.66	33	30	0.53%	12"	TYPE I	-
P-6	S-6	S-6A	858.68	858.84	33	31	0.52%	12"	TYPE I	-
P-6A	S-6A	S-6B	858.84	859.19	73	70	0.50%	12"	TYPE II	-

SPECIFIC NOTES:

(1) REMOVE EXISTING R-3067 CASTING; REBUILD ROOF TO ACCEPT R-1550 CASTING

STANDARD NOTES:

- PLAN LENGTH (PAY LENGTH) IS FROM CENTER OF STRUCTURE TO CENTER OF STRUCTURE. PIPE LENGTH IS ACTUAL LENGTH OF PIPE FROM STRUCTURE WALL TO STRUCTURE WALL. SLOPE CALCULATED USING PIPE LENGTH.
- ABBREVIATIONS: AE = APRON ENDWALL; RCP = REINFORCED CONCRETE PIPE; HERCP = HORIZONTAL ELLIPTICAL REINFORCED CONCRETE PIPE; DNA = DOES NOT APPLY; SAS = SEWER ACCESS STRUCTURE; LP = LOW POINT INLET STRUCTURE; FP = FIELD POURED STRUCTURE; TR = TOP OF CONCRETE ROOF; NCM = NO CROWN MATCH FOR PIPES; UD = UNDERDRAIN
- APPROXIMATE DISCHARGE E.I. GIVEN, ADJUST E.I. AND PIPE SLOPE IN THE FIELD.
- TOP OF CASTING GRADE GIVEN IS THE TOP OF CURB FOR INLET STRUCTURES AND THE FLOWLINE OF THE CLOSED CASTING FOR SAS's.
- ALL REINFORCED CONCRETE PIPES TO BE CLASS III UNLESS OTHERWISE NOTED.
- SURVEYOR TO CONFIRM THAT ALL INLET STATION / OFFSETS LINE UP WITH PROPOSED CURB AND GUTTER.

- ALL FIELD POURED SAS STORM STRUCTURES SHALL BE CONSTRUCTED IN ACCORDANCE WITH STANDARD DETAIL DRAWING 5.7.3. ALL PRECAST SAS STORM STRUCTURES SHALL BE CONSTRUCTED IN ACCORDANCE WITH STANDARD DETAIL DRAWING 5.7.5.
- ALL STRUCTURES CALLED OUT AS FIELD POURED SHALL BE FIELD POURED. ALL OTHER STRUCTURES (NOT INDICATED AS FIELD POURED) SHALL BE SUBMITTED TO CITY ENGINEERING FOR APPROVAL IF PRECAST STRUCTURES ARE PREFERRED. CONTACT ELIA E ACOSTA OF CITY ENGINEERING AT (608) 266-4096 FOR STORM SEWER PRECAST APPROVALS, FAX SHOP DRAWINGS TO (608)264-9275, OR EMAIL SHOP DRAWINGS TO EACOSTA@CITYOFMADISON.COM.
- FOR SWM PRECAST APPROVALS CONTACT PHIL GAEBLER AT (608) 266-4059 OR EMAIL SWM SHOP DRAWINGS TO PGAEBLER@CITYOFMADISON.COM

SANITARY SEWER SCHEDULE

4800 VOGES ROAD CSM	SHEET NO.
PROJECT NO. 12582	U-SAN
SANITARY SEWER SCHEDULE	
CITY OF MADISON	

PROPOSED SANITARY						
SAS NO.	STATION	LOCATION (OFFSET)	TOP OF CASTING	E.I.	DEPTH (FT)	NOTES
GALLEON RUN						
SAS#1	102+87.04	CL	861.77	845.81	15.96	(1)
SAS#2	104+00.00	CL	861.07	847.96	13.11	(1)
SAS#3	105+00.00	CL	860.46	848.98	11.48	(1); (2)
RUSTY PATCH ROAD						
SAS#4	53+00.00	CL	861.42	846.23	15.19	(1); (2)
SAS#5	50+15.50	CL	857.77	847.47	10.30	(1)

PROPOSED SANITARY PIPES								
FROM (DNSTM)	TO (UPSTM)	DWNSTRM E.I.	UPSTRM E.I.	PLAN LGTH (FT)	SLOPE (%)	PIPE SIZE	PVC TYPE	NOTES
GALLEON RUN								
EX MH07-224	SAS#1	844.87	845.81	188	0.50%	8"	SDR-26	(3)
SAS#1	SAS#2	845.91	847.96	112	1.83%	8"	SDR-26	-
SAS#2	SAS#3	848.06	848.46	100	0.40%	8"	SDR-26	-
RUSTY PATCH ROAD								
SAS#1	SAS#4	845.91	846.23	81	0.40%	8"	SDR-26	-
SAS#4	SAS#5	846.33	847.47	285	0.40%	8"	SDR-26	-

SPECIFIC NOTES:
(1) INSTALL EXTERNAL RUBBERIZED JOINT WRAPP PER S.D.D. 5.7.2
(2) INSTALL INTERNAL CHIMNEY SEAL PER S.D.D. 5.7.17
(3) CONTACT RAY SCHNEIDER OF MMSD AT rays@madsewer.org or (608) 347-3628, 5 DAYS PRIOR FOR THE MANHOLE ADJUST AND THE TAP CONNECTION TO ARRANGE FOR INSPECTION & PERMITTING.
ALL WORK ON MMSD MANHOLE NEEDS TO CONFIRM WITH MMSD SPECIFICATIONS.

NOTES:
- ALL STRUCTURES SHALL BE SUBMITTED TO CITY ENGINEERING FOR APPROVAL. CONTACT ELIA E ACOSTA OF CITY ENGINEERING AT (608) 266-4096 FOR PRECAST APPROVALS, FAX SHOP DRAWINGS TO (608)264-9275, OR EMAIL SHOP DRAWINGS TO EACOSTA@CITYOFMADISON.COM.

STORM SEWER SCHEDULE

PROPOSED STORM STRUCTURES

STRUC. NO.	STATION	LOCATION (OFFSET)	TYPE	TOP OF CASTING	E.I.	DEPTH	NOTES
GALLEON RUN							
S-0	107+50.00	RT-77.85	24" RCP APRON END	-	854.00	-	W/ GATE
S-1	107+50.00	RT-19.50	4X4 SAS	859.07	854.29	4.78	LP; W/ R-3067-7004-VB
S-1A	107+50.00	LT-19.50	H INLET	859.07	855.85	3.22	LP; W/ R-3067-7004-VB
S-2	106+75.00	RT-19.50	4X4 SAS	859.45	854.82	4.63	W/ R-3067-7004-V
S-3	103+92.30	RT-19.50	4X4 SAS	861.15	856.22	4.93	W/ R-3067-7004-V
S-4	103+19.45	RT-19.50	4X4 SAS	861.59	856.84	4.75	W/ R-3067-7004-V
S-4A	103+05.00	LT-19.50	H INLET	861.68	858.08	3.60	W/ R-3067-7004-V
S-8	108+27.33	LT-59.72	24" RCP APRON END	-	854.00	-	-
S-8A	108+41.59	RT-66.67	24" RCP APRON END	-	855.00	-	-
S-9	110+40.38	RT-70.06	12" RCP APRON END	-	854.50	-	W/ GATE
S-9A	110+25.00	RT-19.50	H INLET	859.45	856.25	3.20	LP; W/ R-3067-7004-VB
S-9B	110+25.00	LT-19.50	H INLET	859.45	856.45	3.00	LP; W/ R-3067-7004-VB
S-10	113+79.46	LT-54.25	12" RCP APRON END	-	854.00	-	W/ GATE
S-10A	114+11.21	RT-42.78	3X3 SAS	859.50	854.80	4.70	W/ R-1550
S-10B	114+22.77	RT-59.43	12" RCP APRON END	-	855.00	-	W/ GATE
S-11	114+82.73	LT-62.43	12" RCP APRON END	-	854.00	-	W/ GATE
S-11A	115+10.84	LT-19.50	H INLET	857.50	854.26	3.24	LP; W/ R-3067-7004-VB
S-11B	115+10.84	RT-19.50	H INLET	857.50	854.46	3.04	LP; W/ R-3067-7004-VB
RUSTY PATCH ROAD							
S-5	53+35.86	RT-16.50	4X4 SAS	861.35	857.00	4.35	LP; W/ R-3067-7004-VB
S-5A	53+35.86	LT-16.50	H INLET	861.35	857.66	3.69	LP; W/ R-3067-7004-VB
S-6	51+00.00	RT-16.50	3X3 SAS	861.96	858.18	3.78	FP; LP; W/ R-3067-7004-VB
S-6A	51+00.00	LT-16.50	H INLET	861.96	858.84	3.12	LP; W/ R-3067-7004-VB
S-6B	50+26.73	LT-16.50	H INLET	862.32	859.19	3.13	W/ R-3067-7004-V

PROPOSED STORM PIPES

PIPE NO.	FROM (DNSTM)	TO (UPSTM)	DISCH. E.I.	INLET E.I.	PLAN (PAY) LGTH (FT)	PIPE LGTH (FT)	SLOPE (%)	PIPE SIZE	TYPE	NOTES
GALLEON RUN										
P-0	S-0	S-1	854.00	854.29	58	57	0.51%	24"	TYPE II	-
P-1	S-1	S-2	854.29	854.82	69	65	0.82%	21"	TYPE II	NCM
P-1A	S-1	S-1A	855.24	855.85	39	36	1.69%	12"	TYPE I	-
P-2	S-2	S-3	854.82	856.22	283	279	0.50%	21"	TYPE II	-
P-3	S-3	S-4	856.47	856.84	78	74	0.50%	18"	TYPE I	-
P-4	S-4	S-5	856.84	857.00	37	32	0.50%	18"	TYPE II	-
P-4A	S-4	S-4A	857.34	858.08	42	38	1.95%	12"	TYPE I	-
P-8	S-8	S-8A	854.00	855.00	127	127	0.79%	24"	TYPE I	-
P-9	S-9	S-9A	854.50	856.25	53	52	3.37%	12"	TYPE II	-
P-9A	S-9A	S-9B	856.25	856.45	39	37	0.54%	12"	TYPE I	-
P-10	S-10	S-10A	854.00	854.80	102	101	0.79%	12"	TYPE I	-
P-10A	S-10A	S-10B	854.80	855.00	20	19	1.05%	12"	TYPE II	-
P-11	S-11	S-11A	854.00	854.26	51	50	0.52%	12"	TYPE II	-
P-11A	S-11A	S-11B	854.26	854.46	39	37	0.54%	12"	TYPE I	-
RUSTY PATCH ROAD										
P-5	S-5	S-6	857.00	858.18	239	236	0.50%	18"	TYPE I	-
P-5A	S-5	S-5A	857.50	857.66	33	30	0.53%	12"	TYPE I	-
P-6	S-6	S-6A	858.68	858.84	33	31	0.52%	12"	TYPE I	-
P-6A	S-6A	S-6B	858.84	859.19	73	70	0.50%	12"	TYPE II	-

SPECIFIC NOTES:

STANDARD NOTES:

- PLAN LENGTH (PAY LENGTH) IS FROM CENTER OF STRUCTURE TO CENTER OF STRUCTURE. PIPE LENGTH IS ACTUAL LENGTH OF PIPE FROM STRUCTURE WALL TO STRUCTURE WALL. SLOPE CALCULATED USING PIPE LENGTH.

- ABBREVIATIONS: AE = APRON ENDWALL; RCP = REINFORCED CONCRETE PIPE; HERCP = HORIZONTAL ELLIPTICAL REINFORCED CONCRETE PIPE; DNA = DOES NOT APPLY; SAS = SEWER ACCESS STRUCTURE; LP = LOW POINT INLET STRUCTURE; FP = FIELD POURED STRUCTURE; TR = TOP OF CONCRETE ROOF; NCM = NO CROWN MATCH FOR PIPES; UD = UNDERDRAIN

- APPROXIMATE DISCHARGE E.I. GIVEN, ADJUST E.I. AND PIPE SLOPE IN THE FIELD.

- TOP OF CASTING GRADE GIVEN IS THE TOP OF CURB FOR INLET STRUCTURES AND THE FLOWLINE OF THE CLOSED CASTING FOR SAS's.

- ALL REINFORCED CONCRETE PIPES TO BE CLASS III UNLESS OTHERWISE NOTED.

- SURVEYOR TO CONFIRM THAT ALL INLET STATION / OFFSETS LINE UP WITH PROPOSED CURB AND GUTTER.
- ALL FIELD POURED SAS STORM STRUCTURES SHALL BE CONSTRUCTED IN ACCORDANCE WITH STANDARD DETAIL DRAWING 5.7.3. ALL PRECAST SAS STORM STRUCTURES SHALL BE CONSTRUCTED IN ACCORDANCE WITH STANDARD DETAIL DRAWING 5.7.5.

- ALL STRUCTURES CALLED OUT AS FIELD POURED SHALL BE FIELD POURED. ALL OTHER STRUCTURES (NOT INDICATED AS FIELD POURED) SHALL BE SUBMITTED TO CITY ENGINEERING FOR APPROVAL IF PRECAST STRUCTURES ARE PREFERRED. CONTACT ELIA E ACOSTA OF CITY ENGINEERING AT (608) 266-4096 FOR STORM SEWER PRECAST APPROVALS, FAX SHOP DRAWINGS TO (608)264-9275, OR EMAIL SHOP DRAWINGS TO EACOSTA@CITYOFMADISON.COM.

-FOR SWM PRECAST APPROVALS CONTACT PHIL GAEBLER AT (608) 266-4059 OR EMAIL SWM SHOP DRAWINGS TO PGAEBLER@CITYOFMADISON.COM

NOTE: EROSION CONTROL PLAN ONLY INCLUDES PUBLIC IMPROVEMENTS AND LOT 1 IMPROVEMENTS. LOT 2 AND 3 IMPROVEMENTS TO BE COMPLETED AT A LATER DATE.

1. UNDERSIDE SITE CONTOURS AND INFORMATION BASED ON TOPOGRAPHIC & UTILITY DATA AS PROVIDED BY WYSER ENGINEERING. WYSER ENGINEERING SHALL NOT BE HELD RESPONSIBLE FOR ANY ERRORS OR OMISSIONS THAT MAY BE IDENTIFIED AS INACCURATE OR INCOMPLETE INFORMATION PROVIDED BY OTHERS. CONTRACTOR TO CONFIRM ALL ELEVATIONS, GENERAL DRAINAGE AND EARTHWORK REQUIREMENTS PRIOR TO CONSTRUCTION.
2. THE BENCHMARK LOCATIONS ARE SHOWN FOR REFERENCE ONLY ON THIS PLAN. THE BENCHMARK SHALL BE VALIDATED BY LICENSED LAND SURVEYOR PRIOR TO CONSTRUCTION. CONTRACTOR ASSUMES RISK ASSOCIATED WITH BENCHMARK ELEVATIONS UNTIL CONFIRMED.
3. CONTRACTOR TO OBTAIN APPROPRIATE PERMITS FOR STREET OPENINGS & TO WORK WITHIN THE CITY'S LAND IF REQUIRED.
4. WYSER ENGINEERING SHALL BE HELD HARMLESS AND DOES NOT WARRANT ANY DEVIATIONS BY THE OWNER OR CONTRACTOR FROM THE APPROVED CONSTRUCTION PLANS THAT MAY RESULT IN DISCIPLINARY ACTIONS BY REGULATORY AGENCIES.
5. IF ANY ERRORS, DISCREPANCIES, OR OMISSIONS WITHIN THE PLAN BECOME APPARENT, IT SHALL BE BROUGHT TO THE ATTENTION OF THE ENGINEER PRIOR TO CONSTRUCTION SO THAT CLARIFICATION OR REDESIGN MAY OCCUR.
6. ALL MUNICIPAL UTILITY CONNECTIONS, WORK IN ROW, PUBLIC OUTLOTS AND PUBLIC EASEMENTS SHALL BE IN ACCORDANCE WITH CITY OF MADISON STANDARD SPECIFICATIONS FOR PUBLIC WORKS CONSTRUCTION.



	PROPERTY BOUNDARY
	EASEMENT
	BUILDING FOOTPRINT
	18" CURB AND GUTTER
	ASPHALT PAVEMENT
	CONCRETE PAVEMENT
	PROPOSED MAJOR CULVERT
	PROPOSED MINOR CULVERT
	PROPOSED STORM SEWER
	STM
	SILT FENCE
	INLET PROTECTION
	DITCH CHECK



1"=60' ON 24'X36'
NTS ON 11'X17'

POST WDRN CERTIFICATE OF PERMIT COVERAGE AND MUNICIPAL EROSION CONTROL PERMITS ON SITE AND MAINTAIN UNTIL CONSTRUCTION ACTIVITIES HAVE CEASED. THE SITE IS STABILIZED, AND A NOTICE OF TERMINATION IS FILED.

2. KEEP A COPY OF THE CURRENT EROSION CONTROL PLAN ON SITE THROUGHOUT THE DURATION OF THE PROJECT.

3. ENGINEER / CITY OF MADISON / WDRN HAS THE RIGHT TO REQUIRE CONTRACTOR TO IMPLEMENT ADDITIONAL EROSION CONTROL MEASURES AS NECESSARY. CONTRACTOR MUST NOTIFY THE CITY OF MADISON IMMEDIATELY UPON THE REQUEST TO SCHEDULE A SITE MEETING A MINIMUM OF TWO (2) WORKING DAYS IN ADVANCE OF ANY SOIL DISTURBANCE ACTIVITIES.

4. SUBMIT PLAN REVISIONS OR AMENDMENTS TO THE WDRN AT LEAST 5 DAYS PRIOR TO FIELD IMPLEMENTATION.

5. THE SITE CONTRACTOR IS RESPONSIBLE FOR ROUTINE SITE INSPECTIONS AT LEAST EVERY 7 DAYS AND WITHIN 24 HOURS OF A RAIN EVENT OF 0.5 INCHES OR GREATER. KEEP INSPECTION REPORTS ON-SITE AND MAKE THEM AVAILABLE UPON REQUEST.

6. INSPECT AND MAINTAIN ALL INSTALLED EROSION CONTROL PRACTICES UNTIL THE CONTRIBUTING DRAINAGE AREA HAS BEEN STABILIZED.

7. WHEN POSSIBLE, PRESERVE EXISTING VEGETATION (ESPECIALLY ADJACENT TO SURFACE WATERS), MINIMIZE LAND-DISTURBING CONSTRUCTION ACTIVITY ON SLOPES OF 20% OR MORE, MINIMIZE SOIL COMPACTION, AND PRESERVE TOPSOIL.

8. REFER TO THE WDRN STORMWATER CONSTRUCTION TECHNICAL STANDARDS AT http://dnr.wis.gov/topic/stormwater/standards/const_standards.html

9. INSTALL PERIMETER EROSION CONTROLS AND ROCK TRACKING PAD CONSTRUCTION ENTRANCE(S) PRIOR TO ANY LAND-DISTURBING ACTIVITIES, INCLUDING CLEARING AND GRUBBING. USE WDRN TECHNICAL STANDARD SIDE TRACKING PAD AND TIE WASHING #10SF FOR ROCK CONSTRUCTION ENTRANCE(S).

10. INSTALL INLET PROTECTION PRIOR TO LAND-DISTURBING ACTIVITIES IN THE CONTRIBUTING DRAINAGE AREA AND/OR IMMEDIATELY UPON THE INITIAL INSTALLATION. COMPLY WITH WDRN TECHNICAL STANDARD STORM DRAIN INLET PROTECTION FOR CONSTRUCTION SITES #1060 AND DADE COUNTY REQUIREMENTS FOR FRAMED INLET PROTECTION.

11. CONTRACTOR TO PROVIDE SOLID LID OR METAL PLATE ON ALL OPEN MANHOLES DURING CONSTRUCTION TO MINIMIZE SEDIMENT FROM ENTERING THE STORM SEWER SYSTEM.

12. STAGE CONSTRUCTION GRADING ACTIVITIES TO MINIMIZE THE CUMULATIVE EXPOSED AREA. CONDUCT TEMPORARY GRADING FOR EROSION CONTROL PER WDRN TECHNICAL STANDARD TEMPORARY GRADING PRACTICES FOR EROSION CONTROL #1067.

13. PERMITTING OF GROUNDWATER DETERIORATION IS THE RESPONSIBILITY OF THE CONTRACTOR. GROUNDWATER DETERIORATION IS SUBJECT TO A DNR WATERWATER DISCHARGE PERMIT AND A DNR HIGH CAPACITY WELL APPROVAL. IF CUMULATIVE PUMP CAPACITY IS TO GPM OR MORE.

14. PROVIDE ANTI-SOUP PROTECTION AND MAINTAIN NON-EROSIVE FLOW DURING DETERIORATION. PERFORM DETERIORATING OF CONTAMINATED SURFACE RUNOFF IN ACCORDANCE WITH WDRN TECHNICAL STANDARD DRAINAGE #1061.

15. COMPLETE AND STABILIZE SEDIMENT BASINS/TRAPS OR WET PONDS PRIOR TO MASS LAND DISTURBANCE TO MAINTAIN STABLE DRAINAGE DURING CONSTRUCTION. REMOVE SEDIMENT AS NEEDED TO MAINTAIN 3 FEET OF DEPTH TO THE OUTLET, AND PROPERLY DISPOSE OF SEDIMENT REMOVED DURING MAINTENANCE (REFER TO NR 528). CONSTRUCT AND MAINTAIN THE SEDIMENT BASIN PER WDRN TECHNICAL STANDARD SEDIMENT BASIN #1064 AND SEDIMENT TRAP #1065.

16. CONSTRUCT AND PROTECT THE BIORETENTION BASIN AND VEGETATION FROM RUNOFF AND SEDIMENT DURING CONSTRUCTION. REFERENCE THE WDRN TECHNICAL STANDARD BIORETENTION FOR INFILTRATION #1064.

17. COMPLETE AND STABILIZE SLOPE SILENCING PER WDRN TECHNICAL STANDARD SLOPE SILENCING #1056. REMOVE SEDIMENT FROM BEHIND SLOPE SILENCING AND SEDIMENT BARRIERS BEFORE SEDIMENT REACHES A DEPTH THAT IS EQUAL TO ONE-HALF OF THE FENCE AND/OR BARRIER HEIGHT.

18. REPAIR BREAKS AND GAPS IN SLOPE SILENCING AND BARRIERS IMMEDIATELY. REPLACE DECOMPOSING STRAW BALES (TYPICAL BAILE LIFE IS 3 MONTHS). LOCATE, INSTALL, AND MAINTAIN STRAW BALES PER WDRN TECHNICAL STANDARD DITCH CHANNELS #1062.

19. INSTALL AND MAINTAIN FILTER SOCKS IN ACCORDANCE WITH WDRN TECHNICAL STANDARD INTERIM MANUFACTURED PERIMETER CONTROL AND SLOPE INTERRUPTION PRODUCTS # 1071.

20. IMMEDIATELY STABILIZE STOCKPILES AND SURROUNDING STOCKPILES AS NEEDED WITH SLOPE OR OTHER PERIMETER CONTROL IF STOCKPILES WILL REMAIN INACTIVE FOR 7 DAYS OR LONGER.

21. IMMEDIATELY STABILIZE ALL DISTURBED AREAS THAT WILL REMAIN INACTIVE FOR 14 DAYS OR LONGER. BETWEEN SEPTEMBER 15TH AND OCTOBER 15TH: STABILIZE WITH MULCH, TACKIFIER, AND A PERENNIAL SEED MIXED WITH WINTER SEEDS. AFTER OCTOBER 15TH: STABILIZE WITH MULCH, TACKIFIER, AND A PERENNIAL SEED MIXED WITH WINTER SEEDS. AFTER OCTOBER 15TH: STABILIZE WITH MULCH, TACKIFIER, AND A PERENNIAL SEED MIXED WITH WINTER SEEDS. AFTER OCTOBER 15TH: STABILIZE WITH A POLYMER AND DORMANT SEED MIX, AS APPROPRIATE FOR REGION AND SOIL TYPE.

22. STABILIZE AREAS OF FINAL GRADING WITHIN 7 DAYS OF REACHING FINAL GRADE.

23. SWEEP/CLEAN UP ALL SEDIMENT/TRASH THAT MOVES OFF-SITE DUE TO CONSTRUCTION ACTIVITY OR STORM EVENTS BEFORE THE END OF THE SAME WORKDAY OR AS DIRECTED BY THE AUTHORITIES WITH JURISDICTION. SEPARATE SWEEP MATERIALS (SOILS AND TRASH) AND DISPOSE OF APPROPRIATELY.

24. THE CONTRACTOR IS RESPONSIBLE FOR CONTROLLING DUST PER WDRN TECHNICAL STANDARD DUST CONTROL ON CONSTRUCTION SITES # 1068.

25. PROPERLY DISPOSE OF ALL WASTE AND UNUSED BUILDING MATERIALS INCLUDING GARBAGE, DEBRIS, CLEANING WASTES, OR OTHER CONSTRUCTION MATERIALS) AND DO NOT ALLOW THESE MATERIALS TO BE CARRIED BY RUNOFF INTO THE RECEIVING CHANNEL.

26. COORDINATE WITH THE AUTHORITIES WITH JURISDICTION TO UPDATE THE LAND DISTURBANCE PERMIT TO INDICATE THE LOCATION OF ANY REMEDIATION LOCATIONS FOR ANY EXCAVATED SOILS OR CONSTRUCTION DEBRIS THAT WILL BE HAULED OFF-SITE FOR DISPOSAL. THE DEPOSITED OR STOCKPILED MATERIAL NEEDS TO INCLUDE PERIMETER SEDIMENT CONTROL MEASURES (SUCH AS SLOPE FENCE, HAY BALES, FILTER SOCKS, OR COMPACTED EARTHEN BERM).

27. FOR NON-CHANNELIZED FLOW ON DISTURBED OR CONSTRUCTED SLOPES, PROVIDE CLASS I TYPE I EROSION CONTROL MATTING. INSTALL AND MAINTAIN PER WDRN TECHNICAL STANDARD NON-CHANNEL EROSION MAT #1052.

28. FOR CHANNELIZED FLOW ON DISTURBED OR CONSTRUCTED AREAS, PROVIDE CLASS II TYPE II EROSION CONTROL MATTING UNLESS OTHERWISE SPECIFIED ON THE PLAN. INSTALL AND MAINTAIN PER WDRN TECHNICAL STANDARD CHANNEL EROSION MAT #1053.

29. MAKE PROVISIONS FOR WATERING DURING THE FIRST 8 WEEKS FOLLOWING SEEDING OR PLANTING OF DISTURBED AREAS WHENEVER MORE THAN 7 CONSECUTIVE DAYS OF DRY WEATHER OCCUR.

30. THE CONTRACTOR IS RESPONSIBLE FOR COMPLYING WITH ALL APPLICABLE WDRN REMEDIATION AND WASTE MANAGEMENT AND/OR REMEDIATION, LOCATIONS FOR ANY EXCAVATED SOILS OR CONSTRUCTION DEBRIS THAT WILL BE HAULED OFF-SITE FOR DISPOSAL. THE DEPOSITED OR STOCKPILED MATERIAL NEEDS TO INCLUDE PERIMETER SEDIMENT CONTROL MEASURES (SUCH AS SLOPE FENCE, HAY BALES, FILTER SOCKS, OR COMPACTED EARTHEN BERM).

31. FOR CHANNELIZED FLOW ON DISTURBED OR CONSTRUCTED AREAS, PROVIDE CLASS II TYPE II EROSION CONTROL MATTING UNLESS OTHERWISE SPECIFIED ON THE PLAN. INSTALL AND MAINTAIN PER WDRN TECHNICAL STANDARD CHANNEL EROSION MAT #1053.

32. MAKE PROVISIONS FOR WATERING DURING THE FIRST 8 WEEKS FOLLOWING SEEDING OR PLANTING OF DISTURBED AREAS WHENEVER MORE THAN 7 CONSECUTIVE DAYS OF DRY WEATHER OCCUR.

33. THE CONTRACTOR IS RESPONSIBLE FOR COMPLYING WITH ALL APPLICABLE WDRN REMEDIATION AND WASTE MANAGEMENT AND/OR REMEDIATION, LOCATIONS FOR ANY EXCAVATED SOILS OR CONSTRUCTION DEBRIS THAT WILL BE HAULED OFF-SITE FOR DISPOSAL. THE DEPOSITED OR STOCKPILED MATERIAL NEEDS TO INCLUDE PERIMETER SEDIMENT CONTROL MEASURES (SUCH AS SLOPE FENCE, HAY BALES, FILTER SOCKS, OR COMPACTED EARTHEN BERM).

34. FOR CHANNELIZED FLOW ON DISTURBED OR CONSTRUCTED AREAS, PROVIDE CLASS II TYPE II EROSION CONTROL MATTING UNLESS OTHERWISE SPECIFIED ON THE PLAN. INSTALL AND MAINTAIN PER WDRN TECHNICAL STANDARD CHANNEL EROSION MAT #1053.

35. MAKE PROVISIONS FOR WATERING DURING THE FIRST 8 WEEKS FOLLOWING SEEDING OR PLANTING OF DISTURBED AREAS WHENEVER MORE THAN 7 CONSECUTIVE DAYS OF DRY WEATHER OCCUR.

36. THE CONTRACTOR IS RESPONSIBLE FOR COMPLYING WITH ALL APPLICABLE WDRN REMEDIATION AND WASTE MANAGEMENT AND/OR REMEDIATION, LOCATIONS FOR ANY EXCAVATED SOILS OR CONSTRUCTION DEBRIS THAT WILL BE HAULED OFF-SITE FOR DISPOSAL. THE DEPOSITED OR STOCKPILED MATERIAL NEEDS TO INCLUDE PERIMETER SEDIMENT CONTROL MEASURES (SUCH AS SLOPE FENCE, HAY BALES, FILTER SOCKS, OR COMPACTED EARTHEN BERM).

37. FOR CHANNELIZED FLOW ON DISTURBED OR CONSTRUCTED AREAS, PROVIDE CLASS II TYPE II EROSION CONTROL MATTING UNLESS OTHERWISE SPECIFIED ON THE PLAN. INSTALL AND MAINTAIN PER WDRN TECHNICAL STANDARD CHANNEL EROSION MAT #1053.

38. MAKE PROVISIONS FOR WATERING DURING THE FIRST 8 WEEKS FOLLOWING SEEDING OR PLANTING OF DISTURBED AREAS WHENEVER MORE THAN 7 CONSECUTIVE DAYS OF DRY WEATHER OCCUR.

39. THE CONTRACTOR IS RESPONSIBLE FOR COMPLYING WITH ALL APPLICABLE WDRN REMEDIATION AND WASTE MANAGEMENT AND/OR REMEDIATION, LOCATIONS FOR ANY EXCAVATED SOILS OR CONSTRUCTION DEBRIS THAT WILL BE HAULED OFF-SITE FOR DISPOSAL. THE DEPOSITED OR STOCKPILED MATERIAL NEEDS TO INCLUDE PERIMETER SEDIMENT CONTROL MEASURES (SUCH AS SLOPE FENCE, HAY BALES, FILTER SOCKS, OR COMPACTED EARTHEN BERM).

40. FOR CHANNELIZED FLOW ON DISTURBED OR CONSTRUCTED AREAS, PROVIDE CLASS II TYPE II EROSION CONTROL MATTING UNLESS OTHERWISE SPECIFIED ON THE PLAN. INSTALL AND MAINTAIN PER WDRN TECHNICAL STANDARD CHANNEL EROSION MAT #1053.

41. MAKE PROVISIONS FOR WATERING DURING THE FIRST 8 WEEKS FOLLOWING SEEDING OR PLANTING OF DISTURBED AREAS WHENEVER MORE THAN 7 CONSECUTIVE DAYS OF DRY WEATHER OCCUR.

42. THE CONTRACTOR IS RESPONSIBLE FOR COMPLYING WITH ALL APPLICABLE WDRN REMEDIATION AND WASTE MANAGEMENT AND/OR REMEDIATION, LOCATIONS FOR ANY EXCAVATED SOILS OR CONSTRUCTION DEBRIS THAT WILL BE HAULED OFF-SITE FOR DISPOSAL. THE DEPOSITED OR STOCKPILED MATERIAL NEEDS TO INCLUDE PERIMETER SEDIMENT CONTROL MEASURES (SUCH AS SLOPE FENCE, HAY BALES, FILTER SOCKS, OR COMPACTED EARTHEN BERM).

43. FOR CHANNELIZED FLOW ON DISTURBED OR CONSTRUCTED AREAS, PROVIDE CLASS II TYPE II EROSION CONTROL MATTING UNLESS OTHERWISE SPECIFIED ON THE PLAN. INSTALL AND MAINTAIN PER WDRN TECHNICAL STANDARD CHANNEL EROSION MAT #1053.

44. MAKE PROVISIONS FOR WATERING DURING THE FIRST 8 WEEKS FOLLOWING SEEDING OR PLANTING OF DISTURBED AREAS WHENEVER MORE THAN 7 CONSECUTIVE DAYS OF DRY WEATHER OCCUR.

45. THE CONTRACTOR IS RESPONSIBLE FOR COMPLYING WITH ALL APPLICABLE WDRN REMEDIATION AND WASTE MANAGEMENT AND/OR REMEDIATION, LOCATIONS FOR ANY EXCAVATED SOILS OR CONSTRUCTION DEBRIS THAT WILL BE HAULED OFF-SITE FOR DISPOSAL. THE DEPOSITED OR STOCKPILED MATERIAL NEEDS TO INCLUDE PERIMETER SEDIMENT CONTROL MEASURES (SUCH AS SLOPE FENCE, HAY BALES, FILTER SOCKS, OR COMPACTED EARTHEN BERM).

46. FOR CHANNELIZED FLOW ON DISTURBED OR CONSTRUCTED AREAS, PROVIDE CLASS II TYPE II EROSION CONTROL MATTING UNLESS OTHERWISE SPECIFIED ON THE PLAN. INSTALL AND MAINTAIN PER WDRN TECHNICAL STANDARD CHANNEL EROSION MAT #1053.

47. MAKE PROVISIONS FOR WATERING DURING THE FIRST 8 WEEKS FOLLOWING SEEDING OR PLANTING OF DISTURBED AREAS WHENEVER MORE THAN 7 CONSECUTIVE DAYS OF DRY WEATHER OCCUR.

48. THE CONTRACTOR IS RESPONSIBLE FOR COMPLYING WITH ALL APPLICABLE WDRN REMEDIATION AND WASTE MANAGEMENT AND/OR REMEDIATION, LOCATIONS FOR ANY EXCAVATED SOILS OR CONSTRUCTION DEBRIS THAT WILL BE HAULED OFF-SITE FOR DISPOSAL. THE DEPOSITED OR STOCKPILED MATERIAL NEEDS TO INCLUDE PERIMETER SEDIMENT CONTROL MEASURES (SUCH AS SLOPE FENCE, HAY BALES, FILTER SOCKS, OR COMPACTED EARTHEN BERM).

49. FOR CHANNELIZED FLOW ON DISTURBED OR CONSTRUCTED AREAS, PROVIDE CLASS II TYPE II EROSION CONTROL MATTING UNLESS OTHERWISE SPECIFIED ON THE PLAN. INSTALL AND MAINTAIN PER WDRN TECHNICAL STANDARD CHANNEL EROSION MAT #1053.

50. MAKE PROVISIONS FOR WATERING DURING THE FIRST 8 WEEKS FOLLOWING SEEDING OR PLANTING OF DISTURBED AREAS WHENEVER MORE THAN 7 CONSECUTIVE DAYS OF DRY WEATHER OCCUR.

51. THE CONTRACTOR IS RESPONSIBLE FOR COMPLYING WITH ALL APPLICABLE WDRN REMEDIATION AND WASTE MANAGEMENT AND/OR REMEDIATION, LOCATIONS FOR ANY EXCAVATED SOILS OR CONSTRUCTION DEBRIS THAT WILL BE HAULED OFF-SITE FOR DISPOSAL. THE DEPOSITED OR STOCKPILED MATERIAL NEEDS TO INCLUDE PERIMETER SEDIMENT CONTROL MEASURES (SUCH AS SLOPE FENCE, HAY BALES, FILTER SOCKS, OR COMPACTED EARTHEN BERM).

52. FOR CHANNELIZED FLOW ON DISTURBED OR CONSTRUCTED AREAS, PROVIDE CLASS II TYPE II EROSION CONTROL MATTING UNLESS OTHERWISE SPECIFIED ON THE PLAN. INSTALL AND MAINTAIN PER WDRN TECHNICAL STANDARD CHANNEL EROSION MAT #1053.

53. MAKE PROVISIONS FOR WATERING DURING THE FIRST 8 WEEKS FOLLOWING SEEDING OR PLANTING OF DISTURBED AREAS WHENEVER MORE THAN 7 CONSECUTIVE DAYS OF DRY WEATHER OCCUR.

54. THE CONTRACTOR IS RESPONSIBLE FOR COMPLYING WITH ALL APPLICABLE WDRN REMEDIATION AND WASTE MANAGEMENT AND/OR REMEDIATION, LOCATIONS FOR ANY EXCAVATED SOILS OR CONSTRUCTION DEBRIS THAT WILL BE HAULED OFF-SITE FOR DISPOSAL. THE DEPOSITED OR STOCKPILED MATERIAL NEEDS TO INCLUDE PERIMETER SEDIMENT CONTROL MEASURES (SUCH AS SLOPE FENCE, HAY BALES, FILTER SOCKS, OR COMPACTED

ALL GRADES SHOWN ARE FINAL FINISHED SURFACE GRADES.

AREAS TO BE SEEDDED SHALL HAVE A MINIMUM 6 INCHES TOPSOIL UNLESS OTHERWISE NOTED.

AREAS NOT RESTORED WITH EROSION MATTING OR OTHER STABILIZATION MEASURES SHALL BE STABILIZED WITH MULCH.

APPLY ANIONIC POLYMER TO DISTURBED AREAS IF EROSION BECOMES PROBLEMATIC.

CONTRACTOR SHALL CHISEL-PLOW OR DEEP TILL WITH DOUBLE TIMES THE STORMWATER MANAGEMENT FACILITY JUST PRIOR TO SEEDING AND MULCHING TO PROMOTE INFILTRATION.

MULCH SHALL BE WEEF-FREE STRAW AND SHALL BE INSTALLED AT THE RATE OF 2 TONS PER ACRE PER SECTION 627 OF "STANDARD SPECIFICATIONS FOR HIGHWAY AND STRUCTURE CONSTRUCTION" (WISDOT 2014)

PERMANENT SEEDING SHALL NOT OCCUR BETWEEN SEPTEMBER 15TH AND APRIL 15TH. ALTERNATE SEEDING/PLANTING METHOD AND/OR EROSION PROTECTION MAY BE NECESSARY FOR SEEDING/PLANTING THAT OCCURS DURING THAT TIME. COORDINATE WITH THE OWNER AS NECESSARY.

TEMPORARY STABILIZATION SHALL CONSIST OF ONE OR MORE OF THE FOLLOWING OPTIONS:

1. TEMPORARY SEEDING CONSISTING OF ANNUAL RYE GRASS APPLIED AT A RATE OF 1.5 LBS PER 1000 SQUARE FEET.
2. WISDOT PAL CLASS I TYPE B URBAN EROSION CONTROL MAT.

DIGGERS HOTLINE

Toll Free (800) 242-8511 -or- 811

Hearing Impaired TDD (800) 542-2289

www.DiggersHotline.com



**RUEDEBUSCH
DEVELOPMENT &
CONSTRUCTION**

DEVELOPMENT • CONSTRUCTION • BROKERAGE • CONSULTING
4605 DOVETAIL DRIVE MADISON, WI 53704
PHONE 608.249.2012 FAX 608.249.2032

608.843.3388
www.wyserengineering.com

PROPOSED WYOMING PROJECT

PROPOSED BUILDING - WEST
OF FUTURE GALLEON RUN
4800 VOGES RD.
MADISON, WISCONSIN 53718



NO.	REVISION:	DATE:
	SITE ZONING UPDATES	12.06.21
	PUBLIC PLAN UPDATES	01.05.22

SHEET TITLE:
GRADING & EROSION CONTROL PLAN

JOB NUMBER:	19032
DESIGNED BY:	DOS/AJW
DRAWN BY:	DOS/AJW
CHECKED BY:	-


SHEET NO.

C2.0



WET DETENTION BASIN OUTLET
24-INCH DIA RCP PIPE @ 0.5%
UPSTREAM I.E. = 855.0
DOWNSTREAM I.E. = 854.5
PLATE WITHIN 60" OUTLET MANHOLE
6" HOLE IN PLATE AT ELEVATION 855.0
RECTANGULAR SHAPED CUT IN PLATE WITH
4-FOOT WIDE OPEN AREA AT ELEVATION 856.5
OVERFLOW WEIR = 20.0' LONG AND 5.0' WIDE AT
ELEVATION 858.0

STORMWATER TREATMENT FACILITY SECTION: WET DETENTION POND 1



WET DETENTION BASIN OUTLET
18-INCH DIA RCP PIPE @ 0.71%
UPSTREAM I.E. = 855.0
DOWNSTREAM I.E. = 854.0
OVERFLOW WEIR = 20.0' LONG AND 5.0'
WIDE AT ELEVATION 859.5

STORMWATER TREATMENT FACILITY SECTION: WET DETENTION POND 2



PROPOSED WYOMING
PROJECT

PROPOSED BUILDING - WEST
OF FUTURE GALLEON RUN
4800 VOGES RD.
MADISON, WISCONSIN 53718



NO.	REVISION	DATE
1	SITE ZONING UPDATES	12.06.21
2	PUBLIC PLAN UPDATES	01.05.22

SHEET TITLE:
DETAILS



JOB NUMBER:	19032
DESIGNED BY:	DOS/AJW
DRAWN BY:	DOS/AJW
CHECKED BY:	-
DATE:	11.04.2021

SHEET NO:

DI.1



- GENERAL REQUIREMENTS - WATER MAIN PROFILES:**
- MAINTAIN 6-FT BURY DEPTH UNLESS OTHERWISE INDICATED.
 - INSULATE ALL STORM X-INGS AND AREAS WITH < 5-FT COVER.
 - WM X-INGS OVER SEWERS REQUIRE 6-IN CLEARANCE (MIN.)
 - WM X-INGS UNDER SEWERS REQUIRE 18-IN CLEARANCE (MIN.)



SCALE: 1" = 40'



DESIGNED BY: TDP
MADISON WATER UTILITY
119 E OLIN AVE, MADISON, WI 53713
PRINTING DATE: 3/24/22

4800 VOGES ROAD CSM

PLAN & PROFILE GALLEON RUN WATER


CITY OF MADISON, WISCONSIN

12582
W-3



4800 VOGES ROAD CSM

PLAN & PROFILE RUSTY PATCH RD WATER

**CITY OF MADISON, WISCONSIN**

12582

W-4

SCALE: 1" = 40'


DESIGNED BY: TDP

MADISON WATER UTILITY

119 E OLIN AVE, MADISON, WI 53713

PRINTING DATE: 3/24/22

CONTRACT NO: 9025



WN20 W1 CONNECT TO EX. 10IN TEE AT GALLEON RUN, REMOVE PLUG AND CONNECT WITH 10-IN VALVE & BOX
ISOLATION VALVES: V-4 AT GALLEON RUN
NOTIFY: N/A

WN21 W3 CONNECT TO EX. 12IN AT VOGES ROAD, CUT-IN 12-IN X10-IN TEE
ISOLATION VALVES: V-2 AT VOGES & DUTCHMILL AND V-5 & SV-6 AT VOGES ROAD
NOTIFY: 4800 VOGES ROAD



DISCLAIMER NOTE:
THE WATER IMPACT PLAN IS PROVIDED FOR REFERENCE PURPOSES TO AID PLANNING CONNECTION POINT ISOLATION AND PREPARING NOTIFICATION LISTS DURING PLANNED OUTAGES. REQUEST ANY ALTERNATIVE CONNECTION METHODS IN WRITING, PER SPECS.

SCALE: 1"=120'
DESIGNED BY: ARW/TDP
MADISON WATER UTILITY
119 E OLIN AVE, MADISON, WI 53713
PRINTING DATE: 12/17/21

4800 VOGES ROAD
WATER IMPACT PLAN GALLEON RUN AND VOGES ROAD
CITY OF MADISON, WISCONSIN
CONTRACT NO: 9025



12582
W-5



CONSTRUCTION NOTES:

- | | | | |
|----|---|--------|---|
| 1. | CONSTRUCT NEW WATER MAIN 6.0' BELOW FINISHED GRADE, UNLESS OTHERWISE NOTED. INSULATE MAIN WITH POLYSTYRENE BOARD AT UTILITY CROSSINGS OR OTHER AREAS IDENTIFIED BY ENGINEER AS HAVING INADEQUATE COVER. | WN-1 | REPLACE THE EXISTING LEAD SERVICE WITH A NEW COPPER SERVICE. |
| 2. | VERIFY SIZE OF EXISTING WATER SERVICES AND RECONNECT SERVICES AS INDICATED. | WN-2 | EXTEND AND RECONNECT THE EXISTING COPPER SERVICE TO THE NEW WATER MAIN. |
| 3. | MINIMIZE DISRUPTION OF SERVICE TO CUSTOMERS. NOTIFY PER CONTRACT REQUIREMENTS OF ANY PLANNED WATER OUTAGE. | WN-3 | EXISTING SERVICE TO BE ABANDONED WHEN THE WATER MAIN IS CUT OFF. |
| 4. | THE EXISTING UTILITIES SHOWN ON THIS REPRESENT THE BEST INFORMATION AVAILABLE TO THE WATER UTILITY AT THE TIME OF PLAN PREPARATION. CONTRACTOR IS RESPONSIBLE FOR HAVING EACH UTILITY LOCATED PRIOR TO COMMENCING WORK. | WN-4 | DISCONNECT FROM THE OLD WATER MAIN AND RECONNECT THE EXISTING COPPER WATER SERVICE LATERAL TO THE NEW WATER MAIN. |
| | | WN-5 | RELOCATE THE EXISTING FIRE HYDRANT. |
| | | WN-6 | ABANDON WATER VALVE ACCESS STRUCTURE. |
| | | WN-7 | FURNISH AND INSTALL THE NEW TOP SECTION FOR THE WATER ACCESS STRUCTURE. |
| | | WN-8 | ABANDON THE VALVE BOX. |
| | | WN-9 | FURNISH THE DITCH, COMPACTION, AND ALL MATERIALS AND LABOR FOR THE INSTALLATION OF NEW SERVICE LATERAL. |
| | | WN-10 | REMOVE AND SALVAGE EXISTING HYDRANT |
| | | WN-11 | REPLACE THE EXISTING COPPER SERVICE WITH A COPPER SERVICE |
| | | WN-20+ | SEE WATER IMPACT PLAN FOR CONNECTION POINT ISOLATION AND WATER SHUT-OFF NOTIFICATION INFORMATION. |

WATER UTILITY ULO SCHEDULE

ULO UTILITY STATION OFFSET SHEET

*ESTIMATE OF MATERIALS SUPPLIED BY CONTRACTOR:


<u>PAY_ITEM_ID</u>	<u>DESCRIPTION</u>	<u>QUANTITY</u>	<u>UNIT</u>
70002	FURNISH AND INSTALL 6-INCH PIPE & FITTINGS	55	LNFT
70003	FURNISH AND INSTALL 8-INCH PIPE & FITTINGS	470	LNFT
70004	FURNISH AND INSTALL 10-INCH PIPE & FITTINGS	1600	LNFT
70031	FURNISH AND INSTALL 6-INCH WATER VALVE	3	EACH
70032	FURNISH AND INSTALL 8-INCH WATER VALVE	2	EACH
70033	FURNISH AND INSTALL 10-INCH WATER VALVE	5	EACH
70040	FURNISH AND INSTALL AND SALVAGE HYDRANT	4	EACH
70101	FURNISH AND INSTALL STYROFOAM	10	EACH
71002	8-IN MJ CAP	1	EACH
71003	10-IN MJ CAP	1	EACH
71014	8-IN MJ PLUG	1	EACH
71044	10X8-IN CROSS	1	EACH
71136	10-IN 22-1/2° BEND	2	EACH
71148	10-IN 11-1/4° BEND	1	EACH
71147	8-IN 11-1/4° BEND	1	EACH
71159	8X6-IN REDUCER	1	EACH
71210	8X6-IN TEE	1	EACH
71213	10X6-IN TEE	2	EACH
71214	10X8-IN TEE	1	EACH
71215	10X10-IN TEE	1	EACH
71219	12X10-IN TEE	1	EACH
71343	10X18-IN OFFSET	3	EACH

*ESTIMATE OF MATERIALS IS FOR INFORMATION ONLY. ENGINEER DOES GUARANTEE THE ACCURACY OF THE MATERIAL TAKE OFF.

TO OBTAIN LOCATION OF
PARTICIPANTS' UNDERGROUND
FACILITIES BEFORE YOU
DIG IN WISCONSIN

CALL DIGGERS HOTLINE
TOLL FREE
811 OR 1-800-242-8511
FAX-A-LOCATE 1-800-338-3860
TDD (FOR HEARING IMPAIRED) 1-800-542-2289

WIS. STATUTE 182.0175 (1974)
REQUIRES MIN. OF 3 WORK DAYS
NOTICE BEFORE YOU EXCAVATE.




DISCLAIMER NOTE: UTILITY LOCATIONS SHOWN ARE APPROXIMATE ONLY. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO DETERMINE THE EXACT HORIZONTAL AND VERTICAL LOCATION OF ALL EXISTING UNDERGROUND AND OVERHEAD UTILITIES PRIOR TO COMMENCING WORK.

PART VII - WATER MAINS AND SERVICE LATERALS

DETAIL DRAWING NO. **7.04**

REVISÉ: 01/18/2020



SCALE: N/A

DESIGNED BY: TDP
MADISON WATER U

119 E OLIN AVE, MADISON, WI 53713
PRINTING DATE: 12/10/21

CONTRACT NO: 9025

4800 VOGES ROAD CSM

WATER ESTIMATE OF MATERIALS


CITY OF MADISON, WISCONSIN



12582

W-6

M:\DESIGN\PROJECTS\12582\CADIWATER\12582 WU MATERIALS.DWG



MARK	REVISION	DATE	BY
12582	1	12/14/2021 9:03 AM	Scale: #####
			MIN-1

12582

MADISON, WI

9025

CONTRACT NO:

MAINTENANCE MAP

4800 VOGES RD

M:\DESIGN\Projects\12582\CAD\Streets\12582EN-Maintenance.dwg



12582

MN-1