

## CITY OF MADISON CITY ENGINEERING DIVISION DEPARTMENT OF PUBLIC WORKS PLAN OF PROPOSED IMPROVEMENT


**INDEX OF SHEETS** 

SHEET NO. U1 SHEET NO. L1 UTILITY PLAN LANDSCAPE PLAN

NO MAINTENANCE PLAN REQUIRED

823 E WASHINGTON AVE - MOXY HOTEL UTILITIES ONLY

CITY PROJECT NO. 13275 CONTRACT NO. 8980



PUBLIC IMPROVEMENT PROJECT APPROVED

DECEMBER 7, 2021

BY THE COMMON COUNCIL OF MADISON, WISCONSIN

PUBLIC IMPROVEMENT DESIGN APPROVED BY:

N- Greg Fries

Aug 16, 2022

City Engineer

Date

SANITARY SEWER DESIGNED BY:

LATERAL ONLY

STORM SEWER DESIGNED BY:


LATERAL ONLY

WATER DESIGNED BY:

LATERAL ONLY

FILE NAME: M:\DESIGN\Projects\13275\CAD\Streets\13275EN-TitleSheet.dwg

DATE: 8/10/2022 12:45 PM



THE RIGHT-OF-WAY IS THE SOLE
JURISDICTION OF THE CITY OF MADISON
AND IS SUBJECT TO CHANGE AT ANY TIME
PER THE RECOMMENDATION/PLAN OF
TRAFFIC ENGINEERING AND CITY
ENGINEERING DEPARTMENTS.

ALL WORK WITHIN THE CITY RIGHT-OF-WAY AND ALL PUBLIC IMPROVEMENTS TO SERVE THE PROJECT SHALL BE COMPLETED PER THE CITY OF MADISON ISSUED PLANS (CONTRACT 8980, PROJECT 13275)



PLANT SCHEDULE					
UPRIGHT EVERGREEN SHRUB (10 POINTS EACH)	BOTANICAL NAME	COMMON NAME	SIZE		QTY
JT TH2	Juniperus chinensis 'Trautman' Taxus x media 'Hicksii'	Trautman Juniper Hicks Yew	4' Ht 4' Ht		7 15
DECIDUOUS SHRUBS (3 POINTS EACH)	BOTANICAL NAME	COMMON NAME	SIZE		QTY
DC HB	Diervilla sessilifolia `Cool Splash` Hydrangea paniculata `Bobo`	Cool Splash False Honeysuckle Bobo Hydrangea	3 gal. 3 gal.		3
EVERGREEN SHRUBS (4 POINTS EACH) TE	BOTANICAL NAME	COMMON NAME	SIZE		QTY
	Taxus x media `Everlow`	Yew	3 gal.		3
ORNAMENTAL GRASSES (2 POINTS EACH)	BOTANICAL NAME	COMMON NAME	SIZE		QTY
PN3 PH5	Panicum virgatum `Northwind` Pennisetum alopecuroides 'Hameln'	Switch Grass Hameln Dwarf Fountain Grass	1 gal. 1 gal.		15 17
PERENNIALS (2 POINTS EACH)	BOTANICAL NAME	COMMON NAME	SIZE	SPACING	QTY
GR SA	Geranium x `Rozanne` TM Sedum x Autumn Joy'	Hybrid Cranesbi <b>ll</b> Autumn Joy Sedum	1 gal. 1 gal.	24" o.c. 30" o.c.	9 4
GROUND COVERS	BOTANICAL NAME	COMMON NAME		QTY	
	Stone Mulch			788 sf	
	Sod	Drought Tolerant Fescue Blend		244 sf	

LANDSCAPING POINTS REQUIREMENTS

DEVELOPED AREA ON SITE: 20,124 SF REQUIRED POINTS: (20,124 / 300) X 5 = 336 POINTS PROVIDED POINTS WITH PLANTS: 340 POINTS

## NOTES

- ALL PLANTINGS ADJACENT TO BICYCLE PARKING LOCATIONS SHALL BE MAINTAINED TO PROVIDE A 2 FOOT BUFFER ZONE.
- 2. EXISTING 20" HONEY LOCUST STREET TREE TO BE PRESERVED AND PROTECTED.
- 2. EXISTING 20" HONEY LOCUST STREET TREE TO BE PRESERVED AND PROTECTED.
  3. AS DEFINED BY SECTION 107.13 OF CITY OF MADISON STANDARD SPECIFICATIONS FOR PUBLIC WORKS CONSTRUCTION. DO EXCAVATION IS PERMITTED WITHIN 5 FEET OF THE TRUNK OF THE STREET TREE OR WHEN CUTTING ROOTS OVER 3" DIAMETER. IF EXCAVATION IS NECESSARY, THE CONTRACTOR SHALL CONTACT MADISON CITY FORESTRY (268-461) PRIOR TO EXCAVATION. CITY OF MADISON FORESTRY PERSONNEL SHALL ASSESS THE IMPACT TO THE TREE AND TO ITS ROOT SYSTEM PRIOR TO WORK COMMENCING. TREE PROTECTION SPECIFICATIONS CAN BE FOUND ON THE FOLLOWING WESSITE: HITELY WWW.clipformacion.com/business/pw/specs.cfm
  4. CONTRACTOR SHALL TAKE PRECAUTIONS DURING CONSTRUCTION TO NOT DISFIGURE, SCAR, OR IMPAIR THE HEALTH OF ANY STREET TREE. CONTRACTOR SHALL OPERATE EQUIPMENT IN A MANNER AS TO NOT DAMAGE THE BRANCHES OF THE STREET TREES, THIS MAY REQUIRE USING SMALLER EQUIPMENT AND LOADING AND UNLOADING MATERIALS IN A DESIGNATED SPACE AWAY FROM TREES ON THE CONSTRUCTION SITE. ANY DAMAGE OR INJURY TO EXISTING STREET TREES, CHITHER ABOVE OR BELOW GROUND) SHALL BE REPORTED IMMEDIATELY TO CITY FORESTRY AT 266-4816. PENALTIES AND REMEDIATION SHALL BE REPOURED.

  5. SECTION 107, 1976-196. CELTY OF MADISON, TAXANDRA SECREPICATIONS OF DE BIRD IN GROUND SHALL BE REPORTED IMMEDIATELY.

PINNACLE ENGINEERING GROUP

- TO CITY FORESTRY AT 266-4816. PENALTIES AND REMEDIATION SHALL BE REQUIRED.

  SECTION 1071.3(G) OF CITY OF MADISON STANDARDS SPECIFICATIONS FOR PUBLIC WORKS CONSTRUCTION ADDRESSES SOIL COMPACTION NEAR STREET TREES AND SHALL BE FOLLOWED BY CONTRACTOR. THE STORAGE OF PARKED VEHICLES, CONSTRUCTION EQUIPMENT, BUILDING MATERIALS, REFUSE, EXCAVATED SPOILS OR DUMPING OF POISONOUS MATERIALS ON OR AROUND TREES AND ROOTS WITHIN FIVE (6) FEET OF THE TREE OR WITHIN THE PROTECTION ZONE IS PROHIBITED.

  ON THIS PROJECT, STREET TREE PROTECTION ZONE FENCING IS REQUIRED. THE FENCING SHALL BE ERECTED BEFORE THE DEMOLITION, GRADING OR CONSTRUCTION BEGINS. THE FENCE SHALL INCLUDE THE ENTIRE WIDTH OF TERRACE AND, EXTEND AT LEAST 6 FEET ON BOTH SIDES OF THE OUTSIDE EDGE OF THE TREE TRUNK. DO NOT REMOVE THE FENCING TO ALLOW FOR DELIVERIES OR EQUIPMENT ACCESS THROUGH THE TREE PROTECTION ZONE.
- STREET TREE PRUNING SHALL BE COORDINATED WITH MADISON FORESTRY AT A MINIMUM OF TWO WEEKS PRIOR TO THE START OF CONSTRUCTION FOR THIS PROJECT. ALL PRUNING SHALL FOLLOW THE AMERICAN NATIONAL STANDARDS INSTITUTE (ANS) A3009 PART I STANDARDS FOR PRUNING.

