

Davies St & Dempsey Rd Reconstruction 2023

Public Information Meeting
City of Madison Engineering Division
January 31st, 2023

Thank you for attending. We will begin shortly...



Meeting Technical Housekeeping


- This meeting will be <u>recorded</u> and posted to the project page.
- All attendees should be <u>muted</u> to keep background noise to a minimum.
- Use the <u>"chat"</u> button for technical issues with meeting to troubleshoot with staff to assist.
- Use the <u>"Q and A"</u> button to type questions about presentation.
 Questions will be answered live after the presentation.
- Inappropriate questions may be dismissed.
- Use the "raise your hand" button to verbally ask your question. You will be prompted to unmute when it is your turn.




This meeting is being recorded. It is a public record subject to disclosure.

By continuing to be in the meeting, you are consenting to being recorded and consenting to this record being released to public record requestors.








Raise your hand to be unmuted For comments or ask additional questions.






Use chat if you have technical issues or a question for the panelists








Use Q/A if you have questions. We will answer after the presentation






To leave the meeting click here



Presentation Outline

- ➤ Project Location
- ➤ Scope of Work
- ➤ Utility Work
- ➤ Existing Street Conditions & Use
- ➤ Previous Street Design Discussions
- ➤ Proposed Street Design
 - Complete Green Streets Guidelines
- **≻**Forestry
- ➤ Maintenance Responsibilities
- ➤ Construction & Access
- ➤ Assessment Policy & Costs
- ➤ Project Schedule
- ➤ Contact Information & Resources
- ≽Q&A





Project Location



Scope of Work

- **➤**Utility Work
 - ➤ Replace Sanitary Sewer Main & Laterals
 - ➤ Setup Backyard Sewer Lines for Front Connection
 - ➤ Replace & Upgrade Storm Sewer
 - ➤ Replace Water Main & Services
 - ➤ MG&E will also replace gas main within project limits
- ➤ Street Work
 - ➤ Asphalt Pavement & Rock Base
 - ➤ Curb & Gutter
 - ➤ Sidewalk (as approved)
 - ➤ Shared-Use Path (as approved)






Utility Work: Sanitary Sewer

- ➤ Existing Sanitary Main Dempsey Rd
 - ➤ Cottage Grove Rd to Davidson St = 8" VCP (1952)
 - ➤ Davidson St to Gary St = 8" VCP (1952) = CIP Lined in 2014
 - ➤ Backyard Main Laterals to Back of Lots
 - ➤ Gary St to Pinchot Ave = 8" VCP (1952)
- ➤ Existing Sanitary Main Davies St
 - ➤ Maher Ave to Drexel Ave = 8" VCP (1952)
- ➤ Proposed Sanitary Sewer
 - ➤ Replace all sanitary sewer main with min. 8" PVC Pipe
 - ➤ Replace all sanitary sewer laterals with 6" PVC Pipe
 - > Lateral replacement from new main to property line








Utility Work: Sanitary Sewer Laterals

Utility Work: Sanitary Sewer – Backyard Main

- ➤ City evaluating installation of sanitary sewer main on Dempsey Rd from Gary St to Davidson St in order to eventually abandon backyard main
 - ➤ Basement floor elevation survey still needed from 3910 Dempsey & 4006 Dempsey
 - ➤ Please contact Kyle Frank (<u>kfrank@cityofmadison.com</u>) to schedule survey
- New sanitary laterals will be installed from new main to property line and plugged.
 - ➤ Assessed per City Policy
- ➤ Owners will NOT be required to connect to new lateral stubs until future Claire St reconstruction (not scheduled)
 - Letters will be sent out when reconnection is required. More information will be provided, including lateral reimbursement policy.




Utility Work: Water Main

- ➤ Existing Water Main Dempsey Rd
 - Cottage Grove Rd to Maher Ave = 6" Spun Cast Iron (1950)
 - > 15 water main breaks recorded
- ➤ Existing Water Main Davies St
 - ➤ Maher Ave to Buckeye Rd = No Water Main, Only through intersections
- ➤ Proposed Water Main & Services
 - > Replace all water main with new ductile iron pipes
 - > Reconnect all water services to the new main
 - ➤ Replace old Fire Hydrants with 600' max spacing
- ➤ Impacts from Water Installation
 - > 2-3 Planned Water Service Outages (~6 hrs) for Residents along Davies & Dempsey
 - > All planned service disruptions will have 2 days advance notice, typically Contractor puts up door hangers
 - > Potential Unplanned Water Service Outages, Contractor will notify Residents and Repair Damages ASAP
 - ➤ Construction may cause Temporary Discolored Water Events. Please see link for more info https://www.cityofmadison.com/water/water-quality/discolored-water https://www.cityofmadison.com/water/water-quality/discolored-water

Utility Work: Storm Sewer

- ➤ Existing Storm Sewer Dempsey Rd
 - ➤ Storm Sewer at Cottage Grove & Dempsey
 - ➤ No Storm Sewer Main along Dempsey Rd
- ➤ Existing Storm Sewer Davies St
 - ➤ Drexel Ave to Major Ave = 30" RCP (1981)



- ➤ Proposed Storm Sewer
 - Install and upgrade new storm sewer pipes and inlets throughout project limits
 - Future project to route stormwater down Gary St to Retention Pond off US 51 (Stoughton Rd) Ramp



Existing Street Conditions – Davies & Dempsey

- ➤ Pavement Rating = 3-4 out of 10
- ➤ No Curb & Gutter/No Sidewalk
- ➤ Street Surface Width:
 - ➤ Dempsey Rd = 36-Ft
 - ➤ Davies St = 32-Ft
- ➤ City Right-of-Way Width
 - ➤ Dempsey Rd = 66-Ft (Typical), 61-Ft, 56-Ft
 - ➤ Davies St = 60-Ft
- ➤ On-Street Parking on Both Sides of Streets
 - ➤ No Parking on Dempsey Rd along Lake Edge Park
- ➤ No On-Street Bike Lanes = Monona Lake Loop Route
- ➤ Metro Transit Route (39) = Will Continue to have Transit after Metro Redesign is implemented June 2023 CITY OF MADISON





Existing Street Conditions – Davies & Dempsey



Davies Street (westbound)


Dempsey Road and Park Ct.




Existing Conditions: On-Street Parking

Parking Study

- Between 0 and 4 vehicles parked per block
- Counts taken during mid morning & mid evening





Existing Conditions: Speed & Volume Data




Existing Conditions: Crashes

Crashes along Dempsey Rd & Davies St

- 5 crashes within last 5 years
- No vehicle vs pedestrian crashes
- No vehicle vs bicycle crashes

Crashes at Dempsey Rd & Cottage Grove Rd Intersection

- 1 Vehicle vs. Bicycle Crash (2021)
 - NB Bicyclist & SB-LT Vehicle
- 4 Vehicle vs. Vehicle Crash (since 2017)
 - (1) NB Vehicle & SB-LT Vehicle
 - (2) EB Vehicle & WB-LT Vehicle
 - (1) EB Vehicle Lane Merge






Previous Street Design Discussions

> Recordings of previous public meetings are available on project webpage


+ 2' Gutter

- ➤ December 14, 2020 (Included Maher Ave)
- ➤ January 6, 2022 (Davies-Dempsey Only)
- Previous Design Options (sidewalk on both sides)
 - ➤On-street, buffered bike lanes = 38-Ft wide street (typical section below)
 - ➤On-street, painted (no buffer) bike lanes = 34-Ft wide street



City of Madison


Complete Green Streets Guide



STREET VALUES



MODAL HIERARCHY



Approved January 6, 2023



Principles of Complete Green Streets

- Streets are for everyone, no matter who they are or how they travel.
- There is no one design but instead each design considers the specific context of the neighborhood and street.
- Streets are designed and operated to prioritize safety, comfort and access for all users.
- Green infrastructure integrates sustainability in the right of way to help our City be more resilient and helps provide a welcoming public place.


Dempsey Rd & Davies St

Street Type: Neighborhood Street

Context: Residential neighborhood

Description: Wider neighborhood streets that allow two drivers to pass each other without needing to stop. Includes some higher-traffic streets and transit routes. Designed to prioritize neighborhood quality of life.

Target Speed: 20 mph or less








Dempsey Rd & Davies St


Complete Green Streets Guide: All Ages & Ability Bike Network

- Streets and paths that are critical to have a complete bike network of safe, low stress bikeways.
- Provide connections between neighborhoods, important destinations in Madison and to adjacent communities.
- Provide facilities needed for increasing the number of people choosing to bike.



Proposed Street Design – Davies St & Dempsey Rd

Davies St (Maher Ave to Buckeye Rd) – Looking North Dempsey Rd (Cottage Grove Rd to Maher Ave) – Looking North



Side-Path

(Bikes & Pedestrians) Terrace

Terrace

CITY OF MADISO

Proposed Street Design - Davies St & Dempsey Rd

- ➤ After previous public input meetings and recommendations from the Complete Green Streets Guidelines City staff propose:
 - ➤ Narrowed, 26-Ft wide street Two, 11-ft Travel Lanes Accommodate Transit
 - ➤ Remove ALL on-street parking on Davies St & Dempsey Rd (Buckeye to Cottage Grove)
 - ➤ 10-Ft Shared-Use, Asphalt Side-Path on the westerly-side for Bikes (all ages & abilities) and Pedestrians
 - ➤ Monona Lake Loop Route, Connects Frank Allis Elementary School & Pinney Library
 - ➤ 5-Ft Concrete Sidewalk on the easterly-side for Pedestrians
- ➤ Advantages vs Previous Designs
 - ➤ Narrower footprint allows for less tree impacts & less grading impacts
 - ➤ Narrower street with only two travel lanes creates traffic calming to slow car traffic
 - > Other traffic calming features (speed humps, traffic circles) not allowed due to bus route
 - ➤ Provides All Ages & Abilities Bike Facility on a Transit Route



Review Plan



Forestry Information

- ➤ No Tree Removals due to Poor Condition
- ➤ Anticipated Tree Removals due to Street Work
 - ➤ 4" Arborvitae (3902 Dempsey Rd)
 - ➤ 21" Norway Maple (3906 Dempsey Rd)
 - ➤ 15" Crab Apple (4008 Maher Ave)
 - ➤ Adjacent to 'Lake Edge Park' Sign, Sign to be relocated
 - ➤ 4" Hackberry (405 Davies St)
 - ➤ 4" Hackberry (405 Davies St)
 - ➤ 1" Cypress (4301 Drexel Ave)
 - ➤ 20" Linden (4215 Major Ave)
 - ≥ 25" Linden (4215 Major Ave)
 - ➤ 27" Honeylocust (4300 Hegg Ave)
 - ➤ 4" Select Pear (101 Davies St)
 - ➤ 9" Tatarian Maple (101 Davies St)
 - ➤ 6" Japanese Lilac (101 Davies St)





Forestry Information

➤ Shrubs and Bushes within Right-of-Way potentially removed

➤ Tree Pruning prior to Construction = Spring 2023

- ➤ Private Trees with limbs hanging into ROW will need to be pruned prior to construction = property owner's responsibility (per city ordinance)
 - > 24" Spruce (4301 Drexel Ave)
 - ➤ 20" Norway Maple (4212 Dempsey)
 - ➤ 30" Bur Oak (4217 Hegg Ave)
 - ➤ 14" Honeylocust (4217 Hegg Ave)
 - ➤ 28" Linden (4217 Hegg Ave)
 - ➤ 26" Bur Oak (4217 Hegg Ave)





Maintenance Responsibilities

- ➤ Westerly-Side 10-ft Asphalt, Shared-Use Path
 - ➤ City will be responsible for snow removal of path
 - ➤ Will NOT be a priority snow removal route for maintenance (like the Cap City Trail for instance)
 - Fronting residents will be responsible for maintaining grass terrace b/w path and curb
 - Fronting residents will be responsible for snow removal of driveway apron b/w path & curb
- ➤ Easterly-side 5-ft Concrete Sidewalk
 - Fronting residents will be responsible for snow removal of sidewalk and driveway aprons
 - Fronting residents will be responsible for maintaining grass terrace b/w sidewalk and curb





Construction & Access

- ➤ Dempsey Rd & Davies St (Cottage Grove Rd to Buckeye Rd) will be closed to thru-traffic during construction
- ➤On-Street Parking will not be allowed during construction hours
- ➤ Standard work hours 7am-7pm Mon-Sat; 10am-7pm Sun
 - Limited weekend work anticipated
- ➤ Residential driveways may be closed for up to 20 days (including overnight) for installation of concrete items and curing time
 - > In addition, driveway access may be limited during utility installation
- ➤ Project will require, on average, 2 temporary water shut-offs to each property
- >Contractor may need to pump ground water to keep utility trenches dry and safe
 - > If needed, pumps will likely need to run over night
- ➤ Best guess construction timeframe: June 2023 thru October 2023
 - > MG&E's work could extend construction timeframe



Construction & Access

- >Any existing landscaping within Right-of-Way will likely be disturbed
- ➤ Please remove any plantings, raised beds, structures, stone landscaping, retaining walls, pavers, railings, etc... that you wish to save from the terrace prior to construction.
 - > Contractor will not replace/reinstall these items after construction
- Fences within City Right-of-Way will need to be removed prior to Construction
 - ➤ Property Owner's responsibility to remove
- Encroaching Fences at the following addresses:
 - ➤ 4008 Dempsey
 - > 4212 Maher Ave
- ➤ Grading on Private Property will likely be needed at specific locations
 - > Project Engineer to coordinate Right-of-Entry with property owner's as needed
- > Disturbed bare ground will be restored with topsoil, grass seed, and erosion matting
- > Residents will be notified by mail 2 weeks prior to the start of construction ADISON



Assessment Policy & Costs

- Updated Street Assessment Policy (Fall 2022)
 - Properties assessed for pavement replacement (10' width) based on property frontage
 - Essentially eliminates assessments for Curb & Sidewalk
 - Properties assessed for sewer lateral and driveway apron replacement based on specific dimensions measured during construction
 - Assessed costs for specific items are based on an average of bid prices from the last 3
 years of projects = standardizes costs, removes bidding variability
 - Unit Prices for Driveways, Pavement Reconstruction, and Terrace Walks will be set rates
 - Unit Prices for Sanitary Laterals and Private Storm Connections will be based on final bid prices
- Final assessments are calculated and final billing sent the summer after Construction (2024 for this project)
- Assessments are payable in lump sum or in up to 8 installments at the current interest rate (4% in 2023)

Assessment Policy & Costs

Item	Property Owner Share	City Share
Replace 10-ft width of Asphalt Pavement*	100%	0%
Remainder of Pavement width	0%	100%
Replace Driveway Apron & Terrace Walk	50%	50%
Install New Sidewalk	0%	100%
Install New Curb & Gutter	0%	100%
Sanitary Sewer Main	0%	100%
Sanitary Sewer Laterals to Property Line	25%	75%
Storm Sewer Main	0%	100%
Private Storm Connects, if any	100%	0%
Water Main & Services	0%	100%
Street Trees Removals & Plantings	0%	100%

^{*}Based on LF Frontage of Individual Properties

A reduction factor will be applied to single/two-family residential corner lots



Project Schedule

- ➤ Public Informational Meeting: January 31st, 20223
- ➤ Transportation Commission: February 8th, 2023
- ➤ Mail Estimated Assessments/BPW Notice: February 10th, 2023
- ➤ Board of Public Works Public Hearing: February 22nd, 2023
- ➤ Common Council Public Hearing: March 7th, 2023
- ➤ Advertise Contract for Bids: March 23rd, 2023
- ➤ Start of Construction: Summer 2023
- ► End of Construction: Fall 2023



Contact Information & Resources

- Project Manager/Streets & Paths, Aaron Canton, (608) 242-4763, acanton@cityofmadison.com
- Sanitary & Storm Sewer, Kyle Frank, (608) 266-4098, kfrank@cityofmadison.com
- Water Utility, Adam Wiederhoeft, (608) 266-9121, awiederhoeft@cityofmadison.com
- Traffic Engineering, Jeremy Nash, (608) 266-6585, jnash@cityofmadison.com
- Traffic Engineering Bike-Ped Coordinator, Renee Callaway, (608) 266-6225, recallaway@cityofmadison.com
- Project Webpage: https://www.cityofmadison.com/engineering/projects/davies-street-and-dempsey-road-reconstruction
 - Sign-up for updates on road closures & work progress
 - Presentation recording & slides posted to project page
- Project Survey available on Project Webpage through February 8th, 2023
- Facebook City of Madison Engineering
- Twitter @MadisonEngr
- Everyday Engineering Podcast search "Everyday Engineering" on Apple iTunes or GooglePlay




Q&A



Davies St & Dempsey Rd

Street Zone Priorities: Neighborhood Street



Complete Green Streets Process

