Monroe Street Reconstruction

Final Corridor Design Presentation & Open House

August 16, 2017





Tonight's Agenda

Thank you to Wingra School!

- 1. Project Overview
- 2. Design Proposal & Preparing for Reconstruction
- 3. Open House

Project Team

Engineering

- Christy Bachmann, P.E., Principal Engineer
- Jim Wolfe, Project Engineer
- Phil Gaebler, Water Resources Specialist

Economic Development

- Ruth Rohlich, Business Development Specialist
- Mike Miller, Business Development Specialist

Traffic Engineering

Yang Tao, Ph.D., P.E., Assistant City Traffic Engineer

Planning

- Rebecca Cnare, PLA, Urban Design Planner
- Benjamin Zellers, Transportation Planner

Madison Metro

Tim Sobota, Metro Transit Planner

Key Dates

- July 20-October 6: Public engagement for Crazylegs Plaza and Wingra Park entrance design
 - Public art, green infrastructure, connectivity
- September-October: Public assessment hearings (Board of Public Works & Common Council)
- November: Project out to bid
- Starting in February 2018: Public information meetings on what to expect during construction

Key Dates: Crazylegs Plaza & Wingra Park Entrance

- September 14: Design alternatives presentation
 - · Wingra School, 6:00-7:30PM
 - Landscape, public art, green infrastructure, multimodal connectivity, activity spaces
- October: Final plans submitted for city review
- November: Project out to bid
 - Final presentation, date TBD



Public Input & Engagement

Where We've Been

- Engagement Resource Team
- Community survey
- Kickoff meeting
- 2 business focus groups
- 2 green infrastructure focus groups
- Ped, Bike, Transit World Café
- Green Infrastructure World Café
- Cross Section Workshop
- Cross Section Open House
- Wingra Park Entrance Workshop
- Preliminary Design Workshop



Meeting Ground Rules

- Ask clarifying questions as we go (e.g., to explain a term or repeat a statement).
- Save longer discussion questions for the end.




Project Overview

Jim Wolfe Project Engineer, City of Madison



Project Scope & Timeline

- Reconstruction will occur within nine months:
 - March-November 2018



- Utilities
- Street

2018 Project Budget

- Total project budget: ~ \$17 million
- Street: \$9.8 million
 - Infrastructure replacement (pavement, curb, sidewalk)
 - Lighting and signal replacement
 - Pavement markings
 - Other pedestrian improvements
 - Some storm sewer (inlets & leads)
 - Placemaking (including Crazylegs Triangle & public art)
 - Undergrounding in business districts









2018 Project Budget

- Sanitary Sewer: \$4 million
 - Replacement of sewer main & laterals
- Water Main: \$2.2 million
 - Replacement of main & reconnection of services
- Storm Sewer: \$750,000
 - Replacement & installation of new main
- Water Quality: \$200,000
 - Catch basins & treatment structure
- Rain Gardens: \$20,000


Proposed Design

Jim Wolfe, Project Engineer Phil Gaebler, Water Resources Specialist



Approved Cross Section

- Existing configuration with numerous modifications
- How do we improve the pedestrian environment, enhance the sense of place and support the "green street" vision?



Maintain and Support What's Working


- Healthiest local street retail outside of downtown Madison
- Thriving restaurant scene
- High property values
- Anchor institutions (UW, Edgewood)
- Numerous local and regional community amenities (Wingra Park, Arboretum, SW Commuter Path, Glenwood Park, etc.)
- Frequent Metro service
- Easy access to Downtown, east side and west side



Install a Coordinated Mix of Improvements

- Pedestrian infrastructure
- Bicycle infrastructure
- Green infrastructure

- Bus stops
- Parking meters
- Placemaking "nodes"



Pedestrian Infrastructure

- Rectangular rapid flashing beacons at six intersections
- Pedestrian countdown timers
- Leading pedestrian intervals at some intersections
 - "Walk" signal appears <u>before</u> green light
 - Already installed at Grant Street







Pedestrian Infrastructure

- High-visibility crosswalks at key locations
- Crossing islands
 - Coordinate with bus stops
- Pedestrianscale/decorative lighting in business districts
- Raised intersections at:
 - Harrison
 - Leonard
 - Knickerbocker
 - Glenway
- Narrowing from Edgewood to Regent





Bike Infrastructure


- Improved signage along the SW Commuter Path
 - Will be completed before or during project
- On-street bike parking
 - Attached to parking meter markers
 - Post-and-ring
- Side street parking:
 - At corners where there is space and property owners request







Green Infrastructure



Proposed Treatment Options

- Wingra Park Screen Structure
- Side Street Bioretention/Rain Gardens
- Bed Load Trap/Catchbasin
- Rock Infiltration Trench
- Expanded Tree Grates

Wingra
Park
Screen
Structure



Side Street Rain Gardens Constructed as Bioretention

- 20 suitable locations
- Property owner has right of refusal
- Can be maintained by others
- Construction cost can be absorbed by the city




Rock Trench



4' x 12' Tree Grates and Soil Improvements

- Reduce soil compaction
- More soil volume for trees
- Terrace excavated from curb to sidewalk
- No filtering of street water
- Less risk of tree mortality
- Suitable where terrace is concrete from building to curb or existing soil is highly compacted





Where does this get us?

Wingra Screen 36 lb / year
Rain Gardens 4.6 lb/ year
Bed Load Traps 0.5 lb/ year
Rock Trenches 1.5 lb/ year
Total 42.6 lb total phosphorus/year

 Added to existing reduction, total phosphorus reduction will be at 22% for the watersheds draining across Monroe Street.

Green Infrastructure Support Policy

- Policy recommendation to support stormwater management in the Wingra and Monona Bay Watersheds
 - These waterbodies do not benefit from adaptive management
 - Policy would support the installation of stormwater treatment in the adjacent commercial properties.

Additional Placemaking + Green Infrastructure

- Crazy Legs Triangle –
 opportunities for:
 - Public art
 - Bus stop
 - Seating
 - Bikes
 - Green design & education



- Smaller-scale public art
- Bus stop
- Landscape design
- Design alternatives meeting on September 14th



Parking Meters and Bus Stops

- Multi-space smart meters
- Bus stop amenities







Bus Stops



- New locations adopted by Transit & Parking Commission on 8/9
- Total of 9 fewer stops than today
 - Improves on-time performance
- Average distance is 1,100 feet
- Most stops located after intersections
 - Improves pedestrian safety and driver visibility
- For more information: <u>www.cityofmadison.com/metro/monroe/index.cfm</u>

Preliminary Corridor Design

Design Updates


- Street width between Harrison & Regent now proposed 45 ft.
 - Westbound (uphill) biking spacing
- Width from Edgewood to Prospect narrowed to 42 ft.
- Changed corner of Prospect RRFB location
- RRFB moved from Knickerbocker to Sprague
- RRFB moved from Western to Chapman
- Updated bus stop locations based on TPC

Street Lighting

- Install new street lighting throughout corridor
- Pedestrian scale lighting in business districts
 - Prospect to Regent
 - Crandall to east of Commonwealth
 - Lewis Court to east of Glenway
- All intersections will have tall poles and areas without ped lights will have mid-block tall poles








Glenway thru Copeland GLENWAY STREET PEDESTRIAN SCALE LIGHTING PEDESTRIAN SCALE LIGHTING COPELAND STREET BUS STOP MONROE STREET


-BUS STOP

RAISED INTERSECTION
WITH COLORED CROSS WALKS


Western Ave to Chapman




Baltzell to Pickford




Crandall to Sprague







Woodrow to Edgewood College Drive/Leonard




Edgewood Ave to Lincoln Street




Prospect Ave to Harrison Street



Spooner/Grant to Garfield





Preparing for the Reconstruction

Utility Work

- Project includes replacement of utilities
- Sanitary sewer main & laterals to property line
 - Existing mains from 1905, 1911, 1922, 1932
- Replace water main & reconnect services
- Replace storm sewer as necessary
- Street light & traffic signal infrastructure
- Coordinate with private utilities
 - Replacement of existing facilities
 - Undergrounding work

Construction & Access

- Construction expected to last from end of March until early November
- Work hours 7am to 7pm
- Average of 2 planned water shut-offs
 - Minimum 48 hrs notice prior to shut-offs; more notice given when possible
 - Emergency shut-offs possible, notify affected properties ASAP
- One lane of traffic, moving inbound
 - No signed detour planned
 - Metro detoured
- Review final design for possible phasing

Construction & Access

- No on-street parking during work hours
- Access maintained to all commercial driveways during construction
 - Brief delays when working at each driveway
- Residential driveways closed up to 20 days
- Residents in 2 hour parking zones may apply for free residential parking permits
- Review side streets for suspension of street sweeping parking restrictions

Construction & Access

- During construction, sidewalks will remain open on at least one side at all times
- Sidewalk access open to all businesses, but may be from only 1 end of block
 - Laterals & concrete work
- Temporary crosswalks installed as necessary

Trees

- 28 planned tree removals, currently
 - Tree health, preemptive ash removals, traffic island installation
 - Locations to be noted on website & in future mailings
- Additional removals may be necessary as street
 & utility design is completed
- Tree protection specifications enforced for all trees that are planned to remain
- Review with Forestry for new plantings wherever possible during detailed design

Assessment Policy

 Project will include assessments to adjacent property owners

ltem	Property Owner Share	City Share
Curb and Gutter	50%	50%
Pavement	0%	100%
Replace Sidewalk/Apron	50%	50%
Place Making	0%	100%
Storm Sewer	0%	100%
Private Storm Connections	100%	0%
Sanitary Sewer Main	0%	100%
Sanitary Sewer Laterals	25%	75%
Water main & services	o%	100%
Street Lights (tall poles)	100%	0%
Pedestrian Scale Lighting	100%	0%

Assessments

- Mail estimated assessments: 9/08/17
- BPW public hearing: 9/20/17
- Common Council public hearing: 10/03/17
- Assessments can be paid in lump sum or over 8 years with 3% interest
- Final assessments will be mailed in the summer of 2019, following the project completion
- Final assessments will be calculated based on bid prices and measured quantities

Questions?

Next Steps

Key Dates: Monroe Street

- September-October: Public assessment hearings
 - 9/8: Estimated assessments mailed
 - 9/20: Board of Public Works public hearing
 - 10/3: Common Council public hearing
- November: Project out to bid
- Starting in February 2018: Public information meetings on what to expect during construction

Key Dates: Crazylegs Plaza & Wingra Park Entrance

- September 14: Design alternatives presentation for Crazylegs Plaza and Wingra Park entrance
 - Wingra School, 6:00-7:30PM
 - Landscape design, public art, green infrastructure, multimodal connectivity, activity spaces
- October: Final plans submitted for city review
- November: Project out to bid
 - Final design presentation, date TBD

More Information

- All background materials are posted online on the City's Monroe Street Reconstruction project page:
 - www.cityofmadison.com/engineering/projects/monroe-street
 - Subscribe to email updates.
 - Share comments.
- Alder Eskrich, District 13: www.cityofmadison.com/council/district13/
 - Subscribe to email updates.
 - Share comments.