6:00 – 6:10	Welcome
6:10 – 6:45	Presentation
6:45 – 7:15	Presentation Q & A
7:15 – 8:00	Small Group Discussions





# Buckeye Road Reconstruction 2019

Public Preconstruction Meeting by City of Madison Engineering Division June 10, 2019



#### **Evening Overview**

#### Thank You to Frank Allis Elementary!

- Welcome (Hannah Mohelnitzky, City of Madison)
- Presentation (Andrew Zwieg, City of Madison)
- Q&A (facilitated by Hannah Mohelnitzky, City of Madison)
- Wrap Up (Hannah Mohelnitzky, City of Madison)
- Breakout to Small Groups (City of Madison, Capitol Underground, & Strand Associates Staff)



#### **Presentation Overview**

- Project Location
- Existing Conditions
- Proposed Design
- Public Right-Of-Way
- Construction & Access
- City/County Funding
- Assessment Policy & Costs
- Project Schedule
- Contact Information & Resources



## **Project Location**






# **Existing Conditions**

Item	Existing Condition		
Last Surfaced	1977 (New Pavement)		
Pavement Surface Evaluation & Rating	4/10 – Structural Improvement Required, Over 50% of Pavement is Cracked & Deteriorated		
Curb Rating	No Curb & Gutter		
Width	44'	4	
Surface	Asphalt		
Sidewalk	North Side, Partial South Side		
Sanitary	8" Clay 1952	A TIP	
Water	16" & 6" Cast Iron 1949/1950	在一个人	
Storm	None		




- Proposed Street Improvements
  - New asphalt pavement, gravel base
  - New 6" curb & gutter and driveway aprons
  - On-street bike lanes
  - Spot replace sidewalk as needed north side
  - Sidewalk will be added to south side where it does not exist
  - Curb ramps for accessing sidewalks will be improved
  - Bus pads will be installed






- Proposed Street Improvements
  - Parking lanes in select areas



- Proposed Street Improvements
  - New retaining walls will replace the existing walls
  - New retaining wall at Buckeye/Camden Intersection



**Proposed Railing Type/Look - Black** 



**Proposed Retaining Wall – Texture Cobblestone** 



Pedestrian Crossing with Flasher


- Proposed Street Improvements
  - Pedestrian activated flashing yellow lights
    - Along Frank Allis
       Elementary between

      Jerome & Davies
    - At the intersection of Maher





- Proposed Street Improvements
  - Street lighting will be added
  - Fixture type ComfortView Neighborhood LED
    - Lower color temperature 2,700K
    - Majority of fixtures 29 watts 3,460 Lumens
      - 82 watt bulb used at Monona Drive, Frank Allis Elementary, & Shaffer Avenue






- Proposed Utility Improvements
  - Sanitary sewer main will be replaced
    - Replace laterals from the new main to the property line
  - Existing water main from Spaanem to Stoughton will be replaced
    - Reconnect services to the new main but not replaced unless they are broken or in poor condition
  - Storm sewer will be added














#### **Public Right-Of-Way**

- Space of property that extends typically from the curb into the homeowner's yard
- Homeowners are responsible for maintaining the public rightof-way
- The City uses this portion of the yard to improve utilities or other infrastructure the public uses
- Right-of-way & temporary limited easements were purchased






- Begins June 17, lasts until November 15
  - Monona to Davies complete by August 30
- Work hours 7 am to 7 pm
  - No on-street parking during work hours
- Residential driveways
  - Closed up to a cumulative total of 20 days
  - Residents notified 48 hours before
  - Not accessible when contractor is working directly in front
  - Closed when curb & gutter installed & driveway apron installed



- Average of 2 planned water shut-offs
  - Minimum 48 hours notice prior to shut-offs; more notice given when possible
  - Emergency shut-offs possible, notify affected properties ASAP
  - Up to 8 hours, usually 4 hours each
  - Connecting new main to existing
  - Connecting existing service to new main
- No disruptions to sewer service
- Contractor to provide access for garbage & recycling pick-up
  - Have cart out by 5 am on day of pick-up or put out the night before
  - Mark address on cart in case contractor needs to move to allow for pick-up
  - Depending on access, collection may be at side streets
  - Properties on corners, put carts on side street
- Contractor to provide access for mail delivery



- Road closed during project, local traffic only
  - Signed detour provided
  - Pedestrian access maintained on one side of the street
    - Access maintained across Lakeview to accommodate Lake Loop route
- Staggered side street closures
- Periodic closures of Frontage Road intersection






▶ Route 31, regular route

▶ Route 16, 38, & 39 partial detours

► More info: <u>cityofmadison.com/metro/detours</u>







## **City/County Funding**

- Funded using City & County funds
- County will pay 43%
- City will pay 57%
- Property owners adjacent to the project will be assessed for certain items of work
- All maintenance will stay as it currently exists
  - Except the City will plow the road



## **Assessment Policy & Costs**

Special charge for work being done that has a direct benefit to the property

Item	Property Owner Share	City Share	County Share
Curb & Gutter*	25%	37.5%	37.5%
Sidewalk Replacement	25%	37.5%	37.5%
Driveway Aprons	25%	75%	0%
New Sidewalk	50%	25%	25%
New Street (4' Pvmt & Curb)*	50%	25%	25%
Intersect Curb & Pvmt	0%	50%	50%
Sanitary Sewer Main	0%	100%	0%
Sanitary Laterals to Property Line	25%	75%	0%

<sup>\*</sup>Curb & pavement assessed per linear ft. of frontage



# **Assessment Policy & Costs**

ltem	Property Owner Share	City Share	County Share
Water Main	0%	100%	0%
Water Main Laterals	0%	100%	0%
Storm Sewer Main	0%	50%	50%
Private Storm Connects	50%	50%	0%
Retaining Wall	25%	37.5%	37.5%
Railing	25%	37.5%	37.5%
Remove & Replace Steps	50%	50%	0%
Street Lighting	50%	50%	0%



## **Assessment Policy & Costs**

- Final Assessment Bill
  - Calculated based on bid prices, measured quantities
  - Mailed Summer of 2020
- Payment Options
  - Pay in lump sum
  - Pay over 15 years with 4% interest



## **Project Schedule**

- April 18, 2019: Advertise for Bids
- April 26, 2019: Mail Estimated Assessments, Public Hearing Notice
- May 8, 2019: BPW Public Hearing
- May 21, 2019: Common Council Hearing
- ▶ June 17, 2019: Begin Construction
- November 15, 2019: End Construction



#### **Contact Information & Resources**

- Engineering
  - Project Manager, Andrew Zwieg, 266-9219, azwieg@cityofmadison.com
  - Construction Inspector, Eric Hoel, 520-2384, ehoel@cityofmadison.com
  - Water Inspector, Brian McNeary, 267-8647, <a href="mailto:bmcneary@madisonwater.org">bmcneary@madisonwater.org</a>
- Project Website: <u>cityofmadison.com/engineering/projects/buckeye-rd</u>
  - Sign-up for project email updates on the website
  - Updates on closures & work progress will be posted to the project website
- Facebook City of Madison Engineering



6:00 – 6:10	Welcome
6:10 – 6:45	Presentation
6:45 – 7:15	Presentation Q & A
7:15 – 8:00	Small Group Discussions

