

Department of Public Works

Engineering Division

Fact and Details Sheet: PROPOSED OLD MIDDLETON ROAD RESURFACING

Project Details – Proposed Work

PROJECT CONTACTS

- » Project Manager: Fadi El Musa (608) 243-5214, felmusagonzalez@cityofmadison.com
- » Storm and Sanitary Sewer: Matt Allie (608) 266-4058, mallie@cityofmadison.com
- » Water: Kelly Miess
- (608) 261-9640, kmiess@madisonwater.org
- » Traffic: Jeremy Nash
 - (608) 266-6585, jnash@cityofmadison.com
- Construction: Steve Armstrong
 (608) 520-2360, sarmstrong@cityofmadison.com
- » Contractor: Speedway Sand & Gravel, Inc. (608) 836-2983, <u>dakota@speedwaysg.com</u>

Sanitary Sewer: Replace the existing sanitary sewer mains with new PVC pipes and replace existing laterals from the new main to the property line.

Water Main: Will not be replaced with this project except at locations in conflict with new storm sewer.

Storm Sewer: Replace existing storm sewer pipes, inlets, and access structures in poor condition. Install new storm sewer pipes and inlets as needed to improve street drainage.

Street & Sidewalk: Replace all the existing pavement, and replace curb, gutter, driveway aprons, and sidewalks in poor condition or as needed to replace sanitary sewer laterals. Installation of new sidewalk along the north side of 5372 Old Middleton Rd and the south side of 5414 Gettle Ave. Installation of buffered bike lanes along Old Middleton Road within the project limits.

Parking: All parking will be permanently removed from Old Middleton Rd. in order to install buffered bike lanes except at a section on the south side of the 5300 block.

Trees: Tree removals due to poor health condition are planned at the following addresses: 510 Merrill, 5315 Old Middleton, 5317 Old Middleton, 1509 Capital (3 trees).

Terrace Areas: Owners must remove any plantings, structures, or any special landscaping features from the terrace area and public Right of Way prior to the start of construction, including raised planting beds, stone landscaping, retaining walls, railings, pavers, planters, etc. If left in place, these items will be removed by the contractor. The contractor will not replace these items following completion of the project. Owners are invited to contact the project manager to evaluate the impacts of construction in the terrace area.

Bus Pad: Will be installed at current bus stop locations where there is no concrete pad.

Project Website: www.cityofmadison.com/OldMiddletonCraig

Construction Schedule & Impacts

Construction Schedule: Construction is expected to begin in April 18, 2022 and be finished by the end of October 2022. The allowed work hours are 7:00 a.m. – 7:00 p.m. Mondays – Saturdays, and 10:00 a.m. – 7:00 p.m. Sundays.

Traffic Impacts: One lane of westbound traffic will be maintained at all times from N. Eau Claire Ave. to Old Sauk Rd. Two-way traffic between Old Sauk Rd. and N. Rosa Rd. will be maintained at all times. During the time in which the N. Rosa Rd. and Old Middleton Rd. intersection is closed due to construction activities, two-way traffic will be maintained from Old Sauk Rd. to Glen Hwy. Two-way traffic from Old Sauk Rd. to Capital Ave. will be maintained at all times before June 9th and after September 1st. Between June 9th and September 1st, Old Middleton Rd. will be closed to through traffic but will remain open to local and emergency traffic. Eastbound traffic at Capital Ave. will be maintained at all times. Two-way traffic on Whitney Way will be maintained at all times. Some residential driveways may be closed for up to 20 days. Advance notice of such closures will be provided by the contractor.

Refuse Collection: It will be the contractor's responsibility to allow for refuse collection to continue during construction. Please mark your address on your cart to make sure it is returned if moved. We ask that you place your carts at the street the evening prior to or at the very latest 6:00 a.m. the morning of your scheduled refuse/recycling day.

