



155



LOCATION MAP
NW 1/4 OF SECTION 15,
T 7 N, R 10 E

BEARINGS REFERENCED TO THE
WEST LINE OF ANDERSON ESTATES,
RECORDED AS S 00°35'06" E

LEGEND

- 7/8" IRON ROD FOUND
- 1-1/4" x 18" SOLID IRON RE-ROD SET, WT. 4.30 lbs./ft.
- ALL OTHER LOT AND OUTLOT CORNERS MARKED BY A 3/4" x 18" SOLID IRON RE-ROD, WT. 1.50 lbs./ft.
- () INDICATES RECORDED AS
- DISTANCES ARE MEASURED TO THE NEAREST HUNDREDTH OF A FOOT.
- UTILITY EASEMENTS. NO POLES OR BURIED CABLES ARE TO BE PLACED SUCH THAT THE INSTALLATION WOULD DISTURB ANY SURVEY STAKE, OR OBSTRUCT VISION ALONG ANY LOT LINE. THE DISTURBANCE OF A SURVEY MONUMENT BY ANYONE IS A VIOLATION OF SECTION 236.32 OF WISCONSIN STATUTES. UTILITY EASEMENTS AS HEREIN SET FORTH ARE FOR THE USE OF PUBLIC BODIES AND PRIVATE PUBLIC UTILITIES HAVING THE RIGHT TO SERVE THE AREA.

SURVEYOR'S CERTIFICATE

I, Michael J. Ziehr, registered land surveyor, hereby certify: That the foregoing preliminary plat was prepared under my direction and control and that to the best of my knowledge and belief is in compliance with the City of Madison's Land Division and Subdivision Ordinance.

Dated this _____ day of _____ 2005.


Michael J. Ziehr
Registered Land Surveyor S-2401

W 1/4 CORNER OF SECTION 15,
T7N, R10E, FOUND BRASS
CAP IN CONCRETE MONUMENT,
WISCONSIN STATE PLANE
COORDS: (SOUTH ZONE) ARE:
N 390,610.89
E 2,185,396.38
AS PUBLISHED BY THE CITY
OF MADISON.

CENTER OF SECTION 15,
T7N, R10E, FOUND BRASS
CAP IN CONCRETE MONUMENT,
WISCONSIN STATE PLANE
COORDS: (SOUTH ZONE) ARE:
N 390,671.72
E 2,188,034.02
AS PUBLISHED BY THE CITY
OF MADISON.

OWNER/SUBDIVIDER:
MILLER CONSTRUCTION INC.
2318 VONDON ROAD
MADISON, WI 53718

ENGINEER/SURVEYOR:
CALKINS ENGINEERING, LLC
5010 VOGES ROAD
MADISON, WI 53718
608-638-0444



TOTAL PLAT AREA = 373,250 SQ. FT.
(8.5686 ACRES)

CURRENT ZONING: R3

DATE: JULY 8, 2005

PRELIMINARY PLAT OF BUCKEYE MEADOWS

ALL OF LOTS 1 & 2, CERTIFIED SURVEY MAP NUMBER 4448, AS RECORDED IN VOLUME 5980 OF CERTIFIED SURVEY MAPS, ON PAGES 60-61, AS DOCUMENT NUMBER 1846598, DANE COUNTY REGISTRY, ALSO LOCATED IN THE SOUTHWEST QUARTER OF THE NORTHWEST QUARTER OF SECTION 15, TOWNSHIP 7 NORTH, RANGE 10 EAST, CITY OF MADISON, DANE COUNTY, WISCONSIN