

Madison, Wisconsin

CITY OF MADISON

CITY ENGINEERING DIVISION

DEPARTMENT OF PUBLIC WORKS

PLAN OF PROPOSED IMPROVEMENT


INDEX OF SHEETS

SHEET NO.	D1	STANDARD NOTES
SHEET NO.	D2-D3	TYPICAL SECTIONS
SHEET NO.	O1	OVERVIEW PLAN
SHEET NO.	P1-P5	PLAN & PROFILE
SHEET NO.	U1-U3	UTILITIES PLAN & PROFILE
SHEET NO.	USTM	STORM SCHEDULE
SHEET NO.	L1-L3	LANDSCAPING PLAN
SHEET NO.	X1-X11	CROSS SECTIONS
SHEET NO.	MN1	MAINTENANCE PLAN (CITY USE ONLY)

WESTWIND - PHASE 2

CITY PROJECT NO. 14931
CONTRACT NO. 9386

PHASE LIMITS



PUBLIC PONDS
SEE PROJECT
NO. 13921

PUBLIC IMPROVEMENT PROJECT
APPROVED

JUNE 9, 2026

BY THE COMMON COUNCIL
OF MADISON, WISCONSIN

PUBLIC IMPROVEMENT DESIGN
APPROVED BY:

08/12/2026

City Engineer

Date

STREET
DESIGNED BY:




08/11/2026

GEOMETRY
DESIGNED BY:



08/11/2026

STORM SEWER
DESIGNED BY:



08/11/2026

REVISION 1 - 08/27/2026
- REPLACED SHEETS: L1-L3

PLOT SCALE: 1"=0' = 1"=0' XREF

PLOT NAME: ---

REV. DATE: 7/27/2026 10:12 AM

ORIGINATOR: CITY_OF_MADISON

FILE NAME: M:\DESIGN\Projects\14931\CAD\Streets\14931EN+TitleSheet.dwg

DATE: 7/27/2026 10:12 AM

NO TREES IN THE RIGHT OF WAY OR ON PUBLIC LANDS SHALL BE TRIMMED, PRUNED, REMOVED OR ADVERSELY AFFECTED IN ANY WAY UNTIL THE DEVELOPER HAS RECEIVED WRITTEN PERMISSION FROM THE CITY ENGINEER OR CITY FORESTER. SAID WRITTEN PERMISSION SHALL INCLUDE LANGUAGE INDICATING THAT SECTION 10.101 OF THE MADISON GENERAL ORDINANCES AND ADMINISTRATIVE PROCEDURE MEMORANDUM NO. 6-2, REFERRING TO NOTIFICATION OF PROPERTY OCCUPANTS AND/OR OWNERS, HAS BEEN COMPLIED WITH.

THE CONTRACTOR MUST CONTACT CITY FORESTRY AT 608-266-4816 OR FORESTRY@CITYOFMADISON.COM TO CONFIRM LAYOUT AND MARK LOCATION OF TERRACE EXCAVATION SITES AT LEAST 24 HOURS BEFORE EXCAVATION.

DEVELOPER MUST SUBMIT A TRAFFIC CONTROL PLAN TO CITY TRAFFIC ENGINEERING AT LEAST 14 DAYS PRIOR TO THE START OF WORK. WORK SHALL NOT PROCEED UNTIL AN APPROVED TRAFFIC CONTROL PLAN IS IN PLACE.

CONTACT THE PROJECT ENGINEER AND DESIGNER, GRECIA C. IZQUIERDO
TORRES, AT GIZQUIERDO@CITYOFMADISON.COM FOR CAD FILES AND
ALIGNMENT DATA PRIOR TO STAKING

CONTACT THE CITY CONSTRUCTION ENGINEER, KYLE FRANK, AT
KFRANK@CITYOFMADISON.COM FOR PRECONSTRUCTION SCHEDULING,
COORDINATION, AND INSPECTION

ALL PAVEMENT IN THE GOLDEN EAGLE DRIVE, RED PINE DRIVE, AND EMERALD ELM ROAD RIGHTS-OF-WAY SHALL BE TYPE A PAVEMENT PER STANDARD DETAIL DRAWING 4.02.

UNDERDRAINS SHALL BE INSTALLED PER STANDARD DETAIL DRAWING 4.05 FOR 75' ON EACH SIDE OF THE LOW POINT, OR TO THE NEAREST CURB HIGH POINT. ALL UNDERDRAIN SHALL BE WRAPPED.

ALL GUTTERS SHALL DRAIN WITH A MINIMUM GRADE OF 0.5% TOWARD STORM SEWER INLETS.

ALL DITCHES SHALL DRAIN WITH A MINIMUM GRADE OF 0.5%

THE CROSS SLOPE OF SIDEWALKS AND BARRIER FREE SIDEWALK CURB RAMPS SHALL TYPICALLY BE 1.5%. THE LONGITUDINAL GRADE OF BARRIER FREE SIDEWALK CURB RAMPS SHALL NOT EXCEED 8.33%. ALL SIDEWALK RAMPS SHALL BE CONSTRUCTED ACCORDING TO S.D.D. 3.04. AT ALL OTHER LOCATIONS THE LONGITUDINAL GRADE OF SIDEWALKS SHALL NOT EXCEED 5.0 % OR THE ADJACENT STREET GRADE WHICHEVER IS GREATER NOR BE LESS THAN 0.5% AND SHALL DRAIN TOWARD STORM SEWER INLETS. SIDE SLOPES WITHIN TEN FEET OF A PUBLIC SIDEWALK SHALL NOT EXCEED 4:1. ALL SIDEWALK AND SIDEWALK RAMP ELEVATIONS AND GRADES SHALL BE FIELD VERIFIED AND SET TO COMPLY WITH THE CITY OF MADISON STANDARD SPECIFICATIONS AND THE A.D.A. GUIDELINES.

CURB STATION AND OFFSETS SHALL BE TO THE EDGE OF PAVEMENT UNLESS OTHERWISE INDICATED. CURB ELEVATIONS SHALL BE TO THE EDGE OF PAVEMENT UNLESS OTHERWISE INDICATED.

POWER POLES AND OTHER OBSTRUCTIONS SHALL BE MOVED TO PROVIDE 2 FEET MINIMUM OF CLEAR DISTANCE FROM ANY FACE OF CURB OR EDGE OF SIDEWALK UNLESS OTHERWISE INDICATED ON THE PLANS.

ANY INFORMATION SHOWN ON THIS PLAN, WHICH IS NOT PART OF THIS RIGHT-OF-WAY PROJECT, IS PRELIMINARY AND NOT FOR CONSTRUCTION.

THERE MAY BE EXISTING UTILITIES OR OTHER FEATURES WHICH ARE EITHER NOT SHOWN OR SHOWN INCORRECTLY ON THIS PLAN. IT IS THE RESPONSIBILITY OF THE DEVELOPER TO LOCATE AND IDENTIFY ALL UTILITIES AND TOPOGRAPHY WHICH MAY AFFECT THE CONSTRUCTION OF THESE IMPROVEMENTS.

ALL PERMANENT SIGNING AND POSTING WILL BE DETERMINED AND PROVIDED BY THE TRAFFIC ENGINEERING DIVISION, FOLLOWING CONSTRUCTION OF THESE IMPROVEMENTS.

THE DEVELOPER SHALL PROVIDE, INSTALL AND MAINTAIN ALL STREET END BARRICADES, SIGNING AND TRAFFIC CONTROL, AS REQUIRED BY THE CITY TRAFFIC ENGINEER.

PAVEMENT SAWCUTS SHALL BE AS DIRECTED BY THE CITY CONSTRUCTION ENGINEER. SAWCUTS SHOWN ON THE PLAN ARE APPROXIMATE.

CURB ON CUL DE SACS SHALL BE INSTALLED ACCORDING TO S.D.D. 3.05.

ALL WORK IN THE RIGHT OF WAY AND PUBLIC EASEMENTS SHALL BE IN ACCORDANCE WITH THE CITY OF MADISON STANDARD SPECIFICATIONS FOR PUBLIC WORKS CONSTRUCTION LATEST EDITION.

ALL PROPOSED IMPROVEMENTS IN THE RIGHT-OF-WAY ARE BASED ON SURVEY DATA PROVIDED BY THE DEVELOPER OR ITS CONSULTANT. IN THE CASE THAT THE PROPOSED IMPROVEMENTS CAN NOT BE INSTALLED PER THESE PLANS OR THE CITY OF MADISON STANDARD SPECIFICATION FOR PUBLIC WORKS CONSTRUCTION, LATEST EDITION, THE DEVELOPER SHALL BE RESPONSIBLE FOR THE COST OF EXTRA WORK DUE TO INACCURACIES OF THE SURVEY.

ALL UTILITY VERIFICATIONS AND ACCURACY OF THE DRAWINGS ARE THE RESPONSIBILITY OF THE DEVELOPER. ANY CONFLICTS THAT ARISE FROM MISSING OR ERRONEOUS INFORMATION WILL BE AT THE EXPENSE OF THE DEVELOPER. NO PRECAST STRUCTURES WILL BE APPROVED FOR STORM OR SANITARY SEWER UNTIL ALL POTENTIAL UTILITY CONFLICTS ARE RESOLVED.

CONVENTIONAL SIGNS

FIELD VERIFY ALL UTILITY LOCATIONS

GAS — G —

STORM SEWER ——— ST ———

SANITARY SEWER ——— SAN ———

WATER ——— W ———

BURIED ELECTRIC ————— F —————

OVERHEAD ELECTRIC 241

OVERHEAD ELECTRIC	OFF
POWER POLE	1

POWER POLE □

ADA COMPLIANT RAMP W/
DETECTABLE WARNING FIELD

DETECTABLE WARNING FIELD

COMBUSTIBLE FLUIDS 



MARK	REVISION	DATE	BY
Designed By: ###	Date: 7/27/2026 10:11 AM	Scale: #####	D-1
14931			

14931	MADISON, WI
CONTRACT NO: 9386	

STANDARD NOTES


WESTWIND - PHASE 2

M:\DESIGN\Projects\14931\CAD\Streets\14931\EN-Details.dwg



14931


D-1



SPECIAL NOTES:

- * SEE SHEETS P-1 AND X-1 TO X-3 FOR CROSS SLOPES
- ** SEE SHEET O-1 FOR SURFACE PAVING RESPONSIBILITY
- *** PERMANENT LIMITED EASEMENT FOR PUBLIC STREET PURPOSES PER DOC# 5849301
- **** TEMPORARY LIMITED EASEMENT FOR GRADING AND STORM WATER DRAINAGE PER DOC# 5849304

- 1 POINT REFERRED TO ON PROFILE
- 2 1.75" H.M.A. PAVEMENT- TYPE 4 LT 58-28 S**
- 3 6.00" CRUSHED AGGREGATE BASE COURSE GRADATION 2
- 4 6.00" CRUSHED AGGREGATE BASE COURSE GRADATION 1
- 5 3.50" CRUSHED AGGREGATE BASE COURSE GRADATION 3
- 6 CONCRETE CURB AND GUTTER TYPE 'A'.
- 7 FILL
- 8 6" TOPSOIL, SEED AND MAT
- 9 5" CONCRETE SIDEWALK
- 10 6" TOPSOIL, SEED, & EROSION MAT CLASS II URBAN TYPE B




SPECIAL NOTES:

- * SEE SHEETS P-1 AND X-1 TO X-3 FOR CROSS SLOPES
- ** SEE SHEET O-1 FOR SURFACE PAVING RESPONSIBILITY

- 1 POINT REFERRED TO ON PROFILE
- 2 1.75" H.M.A. PAVEMENT- TYPE 4 LT 58-28 S**
- 3 6.0" CRUSHED AGGREGATE BASE COURSE GRADATION 2
- 4 6.0" CRUSHED AGGREGATE BASE COURSE GRADATION 1
- 5 CONCRETE CURB AND GUTTER TYPE 'A'.
- 6 FILL
- 7 6.0" TOPSOIL, SEED AND MAT
- 8 5.0" CONCRETE SIDEWALK

14931	MADISON, WI	9386	CONTRACT NO:
TYPICAL SECTIONS			
WESTWIND - PHASE 2			
M:\DESIGN\Projects\14931\CAD\Streets\14931\EN-Details.dwg			
14931			
D-2			




SPECIAL NOTES:

- * SEE SHEETS P-3 TO P-4 AND X-8 TO X-11 FOR CROSS SLOPES
- ** SEE SHEET O-1 FOR SURFACE PAVING RESPONSIBILITY

TYPICAL SECTION
EMERALD ELM ROAD

- 1 POINT REFERRED TO ON PROFILE
- 2 1.75" H.M.A. PAVEMENT- TYPE 4 LT 58-28 S**
- 3 6.0" CRUSHED AGGREGATE BASE COURSE GRADATION 2
- 4 6.0" CRUSHED AGGREGATE BASE COURSE GRADATION 1
- 5 CONCRETE CURB AND GUTTER TYPE 'A'.
- 6 FILL
- 7 6.0" TOPSOIL, SEED AND MATTING
- 8 5.0" CONCRETE SIDEWALK



SPECIAL NOTES:

- * SEE SHEETS P-2 AND X-4 TO X-7 FOR CROSS SLOPES
- ** SEE SHEET O-1 FOR SURFACE PAVING RESPONSIBILITY


TYPICAL SECTION
RED PINE DRIVE

- 1 POINT REFERRED TO ON PROFILE
- 2 1.75" H.M.A. PAVEMENT- TYPE 4 LT 58-28 S**
- 3 6.0" CRUSHED AGGREGATE BASE COURSE GRADATION 2
- 4 6.0" CRUSHED AGGREGATE BASE COURSE GRADATION 1
- 5 CONCRETE CURB AND GUTTER TYPE 'A'.
- 6 FILL
- 7 6.0" TOPSOIL, SEED AND MATTING
- 8 5.0" CONCRETE SIDEWALK

DATE	BY
7/27/2026	10:12 AM
REVISION	###
14931	14931
MARK	14931

14931	MADISON, WI	9386
CONTRACT NO:		
TYPICAL SECTIONS		
WESTWIND - PHASE 2		
M:\DESIGN\Projects\14931\CAD\Streets\14931\EN-Details.dwg		





PERMANENT LIMITED EASEMENT
FOR PUBLIC WATER MAIN
SEE DOC. NO. 5849303

PERMANENT LIMITED EASEMENT
FOR PUBLIC SANITARY SEWER
SEE DOC. NO. 5849302

TEMPORARY LIMITED EASEMENT FOR
GRADING AND STORM WATER DRAINAGE
SEE DOC. NO. 5849304

PERMANENT LIMITED EASEMENT
FOR PUBLIC SANITARY SEWER
SEE DOC. NO. 5483522

PERMANENT LIMITED EASEMENT
FOR PUBLIC SANITARY SEWER
SEE DOC. NO. 5849302

PLAT BOUNDARY

PERMANENT LIMITED EASEMENT
FOR PUBLIC STREET RIGHT-OF-WAY
SEE DOC. NO. 5849301

PERMANENT LIMITED EASEMENT
FOR PUBLIC SANITARY SEWER
SEE DOC. NO. 5849302



PERMANENT LIMITED EASEMENT
FOR PUBLIC SANITARY SEWER
SEE DOC. NO. 5849302



LEGEND

SURFACE PAVING BY DEVELOPER
PER CONTRACT NO. 9387

OVERVIEW PLAN		14931	14931
WESTWIND - PHASE 2		MADISON, WI	9386
M:\DESIGN\Projects\14931\CAD\Streets\14931EN-OverviewPlan.dwg		CONTRACT NO:	
		14931	O-1
		DESIGNED BY: ###	DATE: ###/###/###
		REVISION	BY
		14931	O-1
		Date: 7/16/2026 2:22 PM	Scale: #####



LEGEND



- [A] TYPE 'A' CONCRETE CURB AND GUTTER
- [RW] RIGHT OF WAY
- [5"CS] 5" CONCRETE SIDEWALK
- [6"GT] 6" GRASS TERRACE
- [7"CONC] 7" CONCRETE RAMP
- [2X5] 2'X5' DETECTABLE WARNING FIELDS
- [END OF ROAD] END OF ROAD SINGING PER S.D.D. 6.29A
- [DITCH] DITCH BOTTOM
- [SAWCUT] SAWCUT PAVEMENT

- NOTES:**
- 5FT ASPHALT TRANSITION FROM BACK OF CURB TO EDGE OF PAVEMENT. CONSTRUCT ASPHALT CURB HEAD AND FLOWLINE TO MATCH CONCRETE CURB.
 - CURB RAMP SHALL HAVE NON-TRAVERSABLE FLARE WITH GRASS AND A 3FT CURB TAPER TO FULL CURB HEAD. INSTALL A 2-INCH CONCRETE BORDER ALONG ALL SIDES OF DETECTABLE WARNING FIELDS
 - 5" CONCRETE TERRACE - 2FT WIDE
 - CURB & GUTTER END SECTION

14931		MADISON, WI		CONTRACT NO: 9386	
PLAN & PROFILE - GOLDEN EAGLE DRIVE		WESTWIND - PHASE 2		14931	
P-1		CITY OF MADISON WISCONSIN		M:\DESIGN\Projects\14931\CAD\Streets\14931-EN-PnP.dwg	

LEGEND

- [A] TYPE 'A' CONCRETE CURB AND GUTTER
- [R/W] RIGHT OF WAY
- [6"GT] 6" GRASS TERRACE
- [7" CONCRETE RAMP]
- [2'X5' DETECTABLE WARNING FIELDS]
- [END OF ROAD SINGING PER S.D.D. 6.29A]



14931	MADISON, WI	9386	CONTRACT NO:
PLAN & PROFILE - BLUE INDIGO STREET			M:\DESIGN\Projects\14931\CAD\Streets\14931-EN-PnP.dwg
WESTWIND - PHASE 2			
14931			
P-2			

14931

MADISON, WI

9386

CONTRACT NO:


PLAN & PROFILE - BLUE INDIGO STREET

WESTWIND - PHASE 2

M:\DESIGN\Projects\14931\CAD\Streets\14931-EN-PnP.dwg

14931

P-2



	14931			P-3
	P-3			
	PLAN & PROFILE - RED PINE DRIVE			
	14931			
	WESTWIND - PHASE 2			
	MADISON, WI			
CONTRACT NO:		9386		
M:\DESIGN\Projects\14931\CAD\Streets\14931EN-PnP.dwg				
MARK	REVISION	DATE	BY	
Designed By: GCIT	Date: 8/4/2026 8:58 AM	Scale: 1" = 40'		P-3
14931				

LEGEND

A

TYPE 'A' CONCRETE CURB AND GUTTER

R/W

RIGHT OF WAY


5"CS

5" CONCRETE SIDEWALK

6"GT

6" GRASS TERRACE


END OF ROAD SINGING PER S.D.D. 6.29A



- NOTES:
1.

5FT ASPHALT TRANSITION FROM BACK OF CURB TO BACK OF CURB. CONSTRUCT ASPHALT CURB HEAD AND FLOWLINE TO MATCH CONCRETE CURB.
2.

5" CONCRETE TERRACE - 2FT WIDE



14931

MADISON, WI

CONTRACT NO: 9386

PLAN & PROFILE - EMERALD ELM ROAD

WESTWIND - PHASE 2

CITY OF MADISON WISCONSIN

14931

P-5

DESIGNED BY: GCIT



DATE: 8/4/2026 8:58 AM

REVISION



MARK

BY



P-5



14931		MADISON, WI		9386	
CONTRACT NO:		14931		U-1	
UTILITIES PLAN & PROFILE - BLUE INDIGO STREET					
WESTWIND - PHASE 2					
M:\DESIGN\Projects\14931\CAD\Sewers\14931SWR-PipeNetwork.dwg					
14931					
U-1					



14931		MADISON, WI		CONTRACT NO: 9386	
UTILITIES PLAN & PROFILE - GOLDEN EAGLE DRIVE		WESTWIND - PHASE 2		M:\DESIGN\Projects\14931\CAD\Sewers\14931SWR-PipeNetwork.dwg	
		14931		U-2	
MARK		REVISION		DATE	
Designed By: ##		Date: 7/16/2026 2:24 PM		Scale: 1" = 40'	
U-2					



MARK	REVISION	DATE	BY
14931	U-3	7/16/2026 2:42 PM	U-3

14931
MADISON, WI
CONTRACT NO: 9386
U-3

UTILITIES PLAN & PROFILE - EMERALD ELM ROAD
WESTWIND - PHASE 2

M:\DESIGN\Projects\14931\CAD\Sewers\14931SWR-PipeNetwork.dwg

CITY OF MADISON
WISCONSIN

14931
U-3

STORM SEWER SCHEDULE

WESTWIND PHASE 2	SHEET NO.
PROJECT NO. 14931	U-STM
STORM SEWER SCHEDULE	
CITY OF MADISON	

PROPOSED STORM STRUCTURES

STRUC. NO.	STATION	LOCATION (OFFSET)	TYPE	TOP OF CASTING	E.I.	DEPTH	NOTES
GOLDEN EAGLE DRIVE							
S-1	163+00.00	LT-22.00	12" RCP APRON END	-	1083.50	-	W/ GATE

PROPOSED STORM PIPES

PIPE NO.	FROM (DNSTM)	TO (UPSTM)	DISCH. E.I.	INLET E.I.	PLAN (PAY) LGTH (FT)	PIPE LGTH (FT)	SLOPE (%)	PIPE SIZE	TYPE	NOTES
GOLDEN EAGLE DRIVE										
P-1	1353-030	S-1	1081.74	1083.50	7	6	29.33%	12"	TYPE II	(1)

SPECIFIC NOTES:

(1) TAP EXISTING INLET

STANDARD NOTES:

- PLAN LENGTH (PAY LENGTH) IS FROM CENTER OF STRUCTURE TO CENTER OF STRUCTURE. PIPE LENGTH IS ACTUAL LENGTH OF PIPE FROM STRUCTURE WALL TO STRUCTURE WALL. SLOPE CALCULATED USING PIPE LENGTH.

- ABBREVIATIONS: AE = APRON ENDWALL; RCP = REINFORCED CONCRETE PIPE; HERCP = HORIZONTAL ELLIPTICAL REINFORCED CONCRETE PIPE; DNA = DOES NOT APPLY; SAS = SEWER ACCESS STRUCTURE; LP = LOW POINT INLET STRUCTURE; FP = FIELD POURED STRUCTURE; TR = TOP OF CONCRETE ROOF; NCM = NO CROWN MATCH FOR PIPES; UD = UNDERDRAIN

- APPROXIMATE DISCHARGE E.I. GIVEN, ADJUST E.I. AND PIPE SLOPE IN THE FIELD.

- TOP OF CASTING GRADE GIVEN IS THE TOP OF CURB FOR INLET STRUCTURES AND THE FLOWLINE OF THE CLOSED CASTING FOR SAS's.


- ALL REINFORCED CONCRETE PIPES TO BE CLASS III UNLESS OTHERWISE NOTED.

- SURVEYOR TO CONFIRM THAT ALL INLET STATION / OFFSETS LINE UP WITH PROPOSED CURB AND GUTTER.
- ALL FIELD POURED SAS STORM STRUCTURES SHALL BE CONSTRUCTED IN ACCORDANCE WITH STANDARD DETAIL DRAWING 5.7.3. ALL PRECAST SAS STORM STRUCTURES SHALL BE CONSTRUCTED IN ACCORDANCE WITH STANDARD DETAIL DRAWING 5.7.5.

- ALL STRUCTURES CALLED OUT AS FIELD POURED SHALL BE FIELD POURED. ALL OTHER STRUCTURES (NOT INDICATED AS FIELD POURED) SHALL BE SUBMITTED TO CITY ENGINEERING FOR APPROVAL IF PRECAST STRUCTURES ARE PREFERRED. CONTACT ELIA E ACOSTA OF CITY ENGINEERING AT (608) 266-4096 FOR STORM SEWER PRECAST APPROVALS, FAX SHOP DRAWINGS TO (608)264-9275, OR EMAIL SHOP DRAWINGS TO EACOSTA@CITYOFMADISON.COM.

-FOR SWM PRECAST APPROVALS CONTACT PHIL GAEBLER AT (608) 266-4059 OR EMAIL SWM SHOP DRAWINGS TO PGAEBLER@CITYOFMADISON.COM

REVISION 1 - GCIT - 08/27/2026
- UPDATED TREE PLANTING SITES LAYOUT



LEGEND

- SN — EXISTING SANITARY SEWER MAIN
- ST — EXISTING STORM SEWER
- W — EXISTING WATER MAIN



PRELIMINARY POLE LOCATION
TO BE DETERMINED ON-SITE



TERRACE EXCAVATION SITE FOR TREE
PLANTINGS PER S.D.D. 2.18

NOTES:

- CONTRACTOR MUST CONTACT CITY FORESTRY AT
608-266-4816 OR FORESTRY@CITYOFMADISON.COM TO
CONFIRM LAYOUT AND MARK AT LEAST 24 HOURS BEFORE
EXCAVATION BEGINS

LANDSCAPING PLAN - GOLDEN EAGLE DRIVE

14931

WESTWIND - PHASE 2

MADISON, WI

M:\DESIGN\Projects\14931\CAD\Streets\14931-EN-LandscapingPlan.dwg

CONTRACT NO:

9386



14931

L-1

REVISION	DATE	BY
REV1	08/27/26	GCIT
MARK	14931	14931
DESIGNED BY	GCIT	14931
DATE	08/27/2026	9:13 AM
SCALE	###	###

REVISION 1 - GCIT - 08/27/2026
- UPDATED TREE PLANTING SITES LAYOUT

CLEAR POND WAY

RED PINE DRIVE

OUTLOT 5
DEDICATED TO THE
PUBLIC FOR
STORMWATER
MANAGEMENT AND
DRAINAGE
PURPOSED

OUTLOT 4
DEDICATED TO THE
PUBLIC FOR
STORMWATER
MANAGEMENT AND
DRAINAGE
PURPOSED

OUTLOT 4

LEGEND

- SN — EXISTING SANITARY SEWER MAIN
- ST — EXISTING STORM SEWER
- W — EXISTING WATER MAIN



PRELIMINARY POLE LOCATION
TO BE DETERMINED ON-SITE



TERRACE EXCAVATION SITE FOR TREE
PLANTINGS PER S.D.D. 2.18

NOTES:

1. CONTRACTOR MUST CONTACT CITY FORESTRY AT
608-266-4816 OR FORESTRY@CITYOFMADISON.COM TO
CONFIRM LAYOUT AND MARK AT LEAST 24 HOURS BEFORE
EXCAVATION BEGINS

REV#	DATE	BY
1	08/27/26	GCIT
2	08/27/26	GCIT
3	08/27/26	GCIT
4	08/27/26	GCIT
5	08/27/26	GCIT
6	08/27/26	GCIT
7	08/27/26	GCIT
8	08/27/26	GCIT
9	08/27/26	GCIT
10	08/27/26	GCIT
11	08/27/26	GCIT
12	08/27/26	GCIT
13	08/27/26	GCIT
14	08/27/26	GCIT
15	08/27/26	GCIT
16	08/27/26	GCIT
17	08/27/26	GCIT
18	08/27/26	GCIT
19	08/27/26	GCIT
20	08/27/26	GCIT
21	08/27/26	GCIT
22	08/27/26	GCIT
23	08/27/26	GCIT
24	08/27/26	GCIT
25	08/27/26	GCIT
26	08/27/26	GCIT
27	08/27/26	GCIT
28	08/27/26	GCIT
29	08/27/26	GCIT
30	08/27/26	GCIT
31	08/27/26	GCIT
32	08/27/26	GCIT
33	08/27/26	GCIT
34	08/27/26	GCIT
35	08/27/26	GCIT
36	08/27/26	GCIT
37	08/27/26	GCIT
38	08/27/26	GCIT
39	08/27/26	GCIT
40	08/27/26	GCIT
41	08/27/26	GCIT
42	08/27/26	GCIT
43	08/27/26	GCIT
44	08/27/26	GCIT
45	08/27/26	GCIT
46	08/27/26	GCIT
47	08/27/26	GCIT
48	08/27/26	GCIT
49	08/27/26	GCIT
50	08/27/26	GCIT
51	08/27/26	GCIT
52	08/27/26	GCIT
53	08/27/26	GCIT
54	08/27/26	GCIT
55	08/27/26	GCIT
56	08/27/26	GCIT
57	08/27/26	GCIT
58	08/27/26	GCIT
59	08/27/26	GCIT
60	08/27/26	GCIT
61	08/27/26	GCIT
62	08/27/26	GCIT
63	08/27/26	GCIT
64	08/27/26	GCIT
65	08/27/26	GCIT
66	08/27/26	GCIT
67	08/27/26	GCIT
68	08/27/26	GCIT
69	08/27/26	GCIT
70	08/27/26	GCIT
71	08/27/26	GCIT
72	08/27/26	GCIT
73	08/27/26	GCIT
74	08/27/26	GCIT
75	08/27/26	GCIT
76	08/27/26	GCIT
77	08/27/26	GCIT
78	08/27/26	GCIT
79	08/27/26	GCIT
80	08/27/26	GCIT
81	08/27/26	GCIT
82	08/27/26	GCIT
83	08/27/26	GCIT
84	08/27/26	GCIT
85	08/27/26	GCIT
86	08/27/26	GCIT
87	08/27/26	GCIT
88	08/27/26	GCIT
89	08/27/26	GCIT
90	08/27/26	GCIT
91	08/27/26	GCIT
92	08/27/26	GCIT
93	08/27/26	GCIT
94	08/27/26	GCIT
95	08/27/26	GCIT
96	08/27/26	GCIT
97	08/27/26	GCIT
98	08/27/26	GCIT
99	08/27/26	GCIT
100	08/27/26	GCIT


14931
MADISON, WI
CONTRACT NO: 9386

LANDSCAPING PLAN - RED PINE DRIVE
WESTWIND - PHASE 2
M:\DESIGN\Projects\14931\CAD\Streets\14931-EN-LandscapingPlan.dwg



14931
L-2

REVISION 1 - GCIT - 08/27/2026
- UPDATED TREE PLANTING SITES LAYOUT



LEGEND

- SN — EXISTING SANITARY SEWER MAIN
- ST — EXISTING STORM SEWER
- W — EXISTING WATER MAIN
- PRELIMINARY POLE LOCATION TO BE DETERMINED ON-SITE
- TERRACE EXCAVATION SITE FOR TREE PLANTINGS PER S.D.D. 2.18

NOTES:







1. CONTRACTOR MUST CONTACT CITY FORESTRY AT 608-266-4816 OR FORESTRY@CITYOFMADISON.COM TO CONFIRM LAYOUT AND MARK AT LEAST 24 HOURS BEFORE EXCAVATION BEGINS

14931		MADISON, WI		9386	
LANDSCAPING PLAN - EMERALD ELM ROAD		WESTWIND - PHASE 2		CONTRACT NO:	
14931					
L-3					

REV#	DATE	BY	REVISION
01	08/27/26	GCIT	UPDATED PLANTING SITES LAYOUT

Designed By: ## 14931
Scale: #####
L-3

M:\DESIGN\Projects\14931\CAD\Streets\14931-EN-LandscapingPlan.dwg









CROSS SECTIONS - GOLDEN EAGLE DRIVE
WESTWIND - PHASE 2

14931
MADISON, WI
CONTRACT NO: 9386

MARK	REVISION	DATE	BY
14931	7/27/2026 10:09 AM	14931	X-1

14931
X-1








14931
X-2

CROSS SECTIONS - GOLDEN EAGLE DRIVE
WESTWIND - PHASE 2

14931
MADISON, WI
CONTRACT NO: 9386

MARK	REVISION	DATE	BY
14931	Designed By: GCIT	Date: 7/27/2026 10:09 AM	Scale: 1" = 20'
			X-2



14931

K-3

CROSS SECTIONS - GOLDEN EAGLE DRIVE

WESTWIND - PHASE 2

M:\DESIGN\Projects\14931\CAD\Streets\14931EN-Xsections.dwg







14931

MADISON, WI

CONTRACT NO:

MARK	REVISION	DATE	BY
0.0000	0.0000	0.0000	0.0000
0.0000	0.0000	0.0000	0.0000
0.0000	0.0000	0.0000	0.0000
0.0000	0.0000	0.0000	0.0000
0.0000	0.0000	0.0000	0.0000

Designed By: GCIT	Date: 7/27/2026 10:09 AM	Scale: 1" = 20'
14931		X-3



14931

K-5

CROSS SECTIONS - RED PINE DRIVE

WESTWIND - PHASE 2

M:\DESIGN\Projects\14931\CAD\Streets\14931EN-Xsections.dwg





14931







MADISON, WI







9586






CONTRACT NO:

[illegible]

[illegible]









MAINTENANCE LEGEND:

= TERRACE REQUIRE MOWING BY CITY

= SIDEWALK AND BIKE PATHS REQUIRE SNOW REMOVAL BY CITY

= BUS STOP PAD REQUIRES SNOW REMOVAL BY CITY

= CROSSWALK OR CONCRETE WATERWAY REQUIRE SNOW REMOVAL BY CITY

= PRIVATELY MAINTAINED (MEDIANS, ISLAND, ROUNDABOUTS & PRIVATE OUTLOTS)

= PUBLIC CITY ENGINEERING STORMWATER PROPERTY

= PUBLIC CITY PARK PROPERTY

= PRIVATE OUTLOT

= PHASE BOUNDARY

SPECIAL FEATURES LEGEND:

= SUSPENDED PAVEMENT SYSTEM

= STORM WATER FEATURE

= UNDERDRAIN

NOT FOR CONSTRUCTION -
CITY RECORDS ONLY

14931

MADISON, WI

CONTRACT NO: 9386

MAINTENANCE PLAN

WESTWIND - PHASE 2

14931

MN-1

MARK

REVISION

DATE

BY

14931

14931

7/27/2026 10:27 AM

MN-1

M:\DESIGN\Projects\14931\CAD\Streets\14931-EN-Maintenance.dwg